## Statement of Work for Rebuild of the Amplifier-Power Supply, AM-7152 NSN 5895-01-127-5855 P/O AN/GRC-213

SOW-05-PMM122-8D054B-1/1

Prepared by
Marine Corps Systems Command, Code PMM122R
Marine Corps Logistics Bases, Albany, GA.

# **Table of Contents**

Section/Paragraph						
1.0	SCOPE	1				
1.1	Background	1				
2.0	APPLICABLE DOCUMENTS	1				
2.1	Military Standards	1				
2.2	Other Government Documents and Publications					
2.3	Industry Standards	2				
3.0	REQUIREMENTS	2				
3.1	General Tasks	2 2 3 3 3 3				
3.2	Detail Tasks	3				
3.2.1	Phase I - Pre-induction	3				
3.2.2	Phase II - Rebuild	3				
3.2.3	Phase III - Inspection, Testing and Acceptance					
3.2.4	Packaging, Handling, Storage and Transportation (PHS&T)					
3.3	Configuration Control	4				
3.4	Government Furnished Equipment (GFE)/Government					
	Furnished Materiel (GFM)					
3.5	Contractor Furnished Materiel (CFM)					
3.6	Electrostatic Discharge (ESD) Control Program					
3.7	Electromagnetic Environmental Effects (E <sup>3</sup> ) Procedures					
3.8	Quality Assurance Provisions					
3.9	Acceptance	5				
3.10	Rejection	5				
	Appendix					
	Appendix A Pre-Induction Checklist	Α-				

### Statement of Work (SOW) for the Rebuild of the Amplifier-Power Supply NSN 5895-01-127-5855

- 1.0 <u>SCOPE</u>. This Statement of Work (SOW) establishes, sets forth tasks and identifies the work efforts that shall be performed by the Contractor (for purposes of this SOW, Contractor is defined as the commercial or government entity performing the rebuild) in the rebuild effort of the Amplifier-Power Supply. This document contains requirements to restore the Amplifier-Power Supply to Condition Code "A". Condition Code "A" is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned material which is serviceable and issuable to all customers without limitation or restriction, including material with more than six months shelf-life remaining".
- 1.1 <u>Background</u>. Rebuild is defined as "that maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repair or replacement of worn or unserviceable elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the items".
- 2.0 <u>APPLICABLE DOCUMENTS</u>. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

#### 2.1 Military Standards

MIL-STD-129 DoD Standard Practice: Military Marking for Shipment and

Storage

MIL-STD-2073-1D(1) DoD Standard Practice for Military Packaging

#### 2.2 Other Government Documents and Publications

TM 09179A-12/1 w/chg 1	Maintenance Instructions for the AN/GRC-213	PCN 184 091790 00
TM 09179A-45/2 w/chg 1, 2	Maintenance Instructions for the AN/GRC-213	PCN 184 091791 00
TM 11-5820-923-40P	Maintenance Instructions for AN/GRC-213	PCN 351 597610 00

TI-5820-25/22A

Standards for the AN/GRC-213

PCN 168047801 00

DoD 4000.25-1-M

Military Standard Requisitioning

and Issue Procedures (MILSTRIP) Manual

Military Handbooks (For Guidance)

MIL-HDBK-61

Configuration Management Guidance

2.3 Industry Standards

JESD625-A

Requirements for Handling Electrostatic-Discharge-

Sensitive (ESDS) Devices

ANSI/ISO/

ASQC Q9001-2000

Quality Management Systems-Requirements

Industry Standards (For Guidance)

ANSI/EIA-649

National Consensus Standard for Configuration

Management

Copies of Military Standards and Specifications are available from the DoD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, PA. 19111-5094, commercial telephone number (215) 697-2179 or DSN 442-2179, or on the Internet at <a href="http://www.dodssp.daps.mil/">http://www.dodssp.daps.mil/</a>. Copies of other government documents and publications required by Contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Contracts Department (Code 891), P.O. Drawer 43019, 814 Radford Blvd., Marine Corps Logistics Command, Albany, Georgia 31704-3019, commercial telephone number (229) 639-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, shall be obtained from Supply Chain Management Center, Attn: Code 566-1A, 814 Radford Blvd., STE 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6476 or DSN 567-6476.

#### 3.0 REQUIREMENTS

- 3.1 General Tasks. In fulfilling the specified requirements, the Contractor shall:
- a. Provide materials, labor, equipment, facilities and missing/repair parts, necessary to inspect, diagnose, restore, test and calibrate the Amplifier-Power Supply. Upon completion of rebuild, the subject item shall be Condition Code "A".
- b. Conduct in-process and final on-site testing for witness by a Marine Corps Systems Command (MCSC), (Code PMM122R), Albany, Georgia authorized representative.

- 3.2 <u>Detail Tasks</u>. The following tasks describe the different phases for rebuild of the Amplifier-Power Supply.
- 3.2.1 <u>Phase I Pre-induction</u>. The Contractor shall perform a pre-induction inspection analysis for each Amplifier-Power Supply using the Contractor Facility's diagnosis, inspection and testing techniques to determine extent of work and parts required. These findings shall be annotated on the Pre-Induction Checklist (Appendix A).
- 3.2.2 <u>Phase II Rebuild</u>. After pre-induction tests and inspections have been completed, repair of the Amplifier-Power Supply shall be accomplished by the Contractor in accordance with this SOW. Deficiencies noted on the Pre-Induction Checklist (Appendix A) during Phase I shall be repaired/replaced. Components or assemblies shall not be disassembled for replacement of parts unless that part has failed, or the component assembly wherein the part is located is disassembled for repair. Any Modification Instructions (MIs) or Engineering Change Proposals (ECPs) not previously applied shall be incorporated.

#### a. Hardware

- (1) Replace broken, unserviceable and/or missing hardware including nuts, bolts, screws, washers, turn lock fasteners, mandatory replacement items, safety, and one-time use items in accordance with this SOW. Unserviceable would include any of the above that failed to function properly.
- (2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.
- (3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.
- 3.2.3 <u>Phase III Inspection, Testing and Acceptance</u>. The Contractor shall conduct inspection, testing and acceptance of the Amplifier-Power Supply in accordance with TM 09179A-12/1 w/chg 1, TM 09179A-45/2 w/chg 1, 2, TM 11-5820-923-40P, and TI-5820-25/22A.

### 3.2.4 Packaging, Handling, Storage and Transportation (PHS&T)

- a. The Contractor shall be responsible for preservation and packaging of items being repaired under the terms of this SOW. Items scheduled for long-term storage or overseas shipment shall be in accordance with the Level "A" requirements of MIL-STD-2073-1D(1), Appendix A, Table A.VI., Electronic Equipment. Items scheduled for domestic shipment for immediate use or short-term storage shall be Level "B" requirements.
  - b. Marking for shipment and storage shall be in accordance with MIL-STD-129.
- c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of the repaired equipment. The Contractor shall be responsible for arranging for shipment to the

pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the equipment to and from the Contractor.

- 3.3 <u>Configuration Control</u>. The Contractor shall apply configuration control procedures to established configuration items. The Contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the Contractor shall prepare and submit a Request For Deviation. MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing this configuration control document.
- 3.4 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). The Management Control Activity (MCA) (Code 581-1B) will coordinate GFE/GFM requests and maintain a central control system on all government owned assets in the Contractor's possession. The MCA will forward a GFE Accountability Agreement to the Contractor for signature on an annual basis to establish a chain of custody and identify property responsibilities for Marine Corps assets. The Contractor is to acknowledge receipt of GFM to the MCA within 15 days of receipt. This can be done by mailing a copy of the DD1348 to Materiel and Distribution Management Department, Distribution Management Branch, Management Control Activity (Code 581-1B), 814 Radford Blvd., STE 20320, Albany, Georgia 31704-0320 or faxing a copy to commercial telephone number (229) 639-5498 or DSN 567-5498.
- 3.5 <u>Contractor Furnished Materiel (CFM)</u>. The Contractor may requisition materiel as required in the performance of the SOW through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP) Chapter 11 provides guidance to Contractors on the requisitioning process. The Contractor's decision to utilize CFM procured from the DoD Supply System shall be based upon cost effectiveness, availability of materiel and the required completion/delivery date.
- 3.6 <u>Electrostatic Discharge (ESD) Control Program.</u> The Contractor shall establish, implement and document an ESD control program following the guidelines provided in JESD625-A. ESD protective measures shall be used during manufacturing, handling, inspection, testing, marking, packaging, storing and transporting ESD sensitive components.
- 3.7 <u>Electromagnetic Environmental Effects (E3) Procedures</u>. The Contractor shall plan for and use proper (E3) control procedures in the rebuild process and shall utilize TI-5820-25/22A in conjunction with the detailed requirements specified in this document.
- 3.8 Quality Assurance Provisions. The Contractor shall provide and maintain a Quality System that, as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9001-2000, Quality Management Systems Requriements. The program shall ensure quality throughout all areas to include fabrication, processing, assembly, inspection, testing, maintenance, and preparation for delivery and shipping. Unless otherwise specified in the contract, the Contractor shall be responsible for performance of all inspection requirements. MCSC, Code PMM122R, Albany, Georgia reserves the right to perform any of the inspections set forth in the contract where such inspections are deemed necessary to assure products and services conform to the prescribed requirements.

4

- 3.9 <u>Acceptance</u>. The performance of the Contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and MCSC, Code PMM122R, Albany, Georgia representatives shall be permitted to observe the work or to conduct an inspection. Final inspection and acceptance testing shall be conducted at the Contractor's Facility. Final acceptance shall be conducted on 100 percent of items to verify that the units meet all requirements.
- 3.10 <u>Rejection</u>. Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCSC, Code PMM122R, Albany, Georgia representative. The Contractor shall, at no additional cost to MCSC, Code PMM122R, Albany, Georgia, correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures is demonstrated.

# **Pre-Induction Checklist**

Amplifier-Power Supply, AN/GRC-213

- 1. Using the following criteria, inspect the items listed below.
  - a. Inspect for dirt, dust, and sand.
  - b. Inspect for rust and/or corrosion damage.
  - c. Inspect for any physical damage. (cuts, dents, cracks, broken pins)
  - d. Ensure that all screws, washers, nuts, bolts, are attached.
  - e. Inspect for dry rot on all rubber and plastic components.
  - f. Ensure that all covers and caps are attached.
  - g. Ensure that all knobs, switches and breakers operate freely and properly.

S - Serviceable	U - Unserviceable	M - Missing	
Remarks:			
	1.0	- VP-LOTO	
			78.01

APPENDIX A

### **CONTRACT DATA REQUIREMENTS LIST**

(1 Data Item)

Form Approved OMB No. 0704-0188

The public is corting barden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0701-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 2220-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the

A. CONTRACT LINE ITEM NO.		B. EXHIE	BIT	C. CATEGORY:					
			TDP TM		OTHER X				
D. SYSTEM/ITEM Amplifier-Po	W ower Supply, AM	E. CONTRACT	/PR NO.	F. CONT	RACTOR				
					3. SUBTITL	E			<b> </b> [F
A001	A001 Request For Deviation				Configuration Mar	ageme	nt		
	Acquisition Document No	.)	5. CONTRACT REF			6. REQUIRING OFFICE			1 1
DI-CMAN-80640C SOW 3.3					MCLCA	A (566)	)		
7. DD 250 REQ	9. DIST STATEMENT REQUIRED	10. FREQU		12. DATE OF FIRST SUB		14. DISTRIB	UTION		
LT			SREQ	See Blk 1			b. COPIES		<u>:</u>
8. APP CODE		11. AS OF	DATE	13. DATE OF SUBSEQUENT SUBMISSION		a. ADDRESSEE	Draft	Final	
A	Α	L	····	See Blk 1	6			Reg	Repro
16. REMARKS Blk 4: Contract	tor format using .	doc or .p	df software ap	plications is autho	rized.	MCLCA (566-1)	0	1	0
Blks 10 & 12: nonconforming documentation.	RFDs shall be sub material that does	mitted to s not med	o obtain author et the prescribe	ization to deliver ed configuration					
RFDs will be reviewed and disposition determined within 20 working days upon receipt by the Government.									
Block 14: RFD	s shall be transmi	tted via e	e-mail to the fo	ollowing address:					
mbmatcomcon	os shall be transmi figmngmnt@logco	m.usmc.	mil						
									<b>⊢</b>
Distribution Sta	atement A: Appro	ved for F	Public Release;	Distribution is					<b>⊢</b>
Ommitted.									i
							ļ		i
								<b></b>	
							ļ	<u> </u>	ļ
							-		<b>  </b>
							<b></b>		
:									
							ļ <u>.</u>		
C DREDARED D	v	1 1	U DATE	I Apppove	D DV	15. TOTAL	0	1	0 j
Diano L. Bradley JUN 29 2004 Julian Jondes							J. DA	1 <u>1</u>	<u> </u>
DD FORM 14	123-1, AUG 96	(EG)	PREVIO	OUS EDITION MAY	BE USED.	Pag	je 1	of	Pages

18. ESTIMATED TOTAL PRICE