Statement of Work
for
Rebuild of Tank Circuit Module Assembly (1A8)
NSN 5998-01-047-9165

SOW-03-847-2-87786B-1/1

Prepared by
Marine Corps Systems Command, Code C4I
Marine Corps Logistics Bases, Albany, GA.

Table of Contents

Section/Para		Page
1.0	SCOPE	1
1.1	Background	1
2.0	APPLICABLE DOCUMENTS	1
2.1	Military Standards	1
2.2	Other Government Documents and Publications	1
2.3	Industry Standards	2
3.0	REQUIREMENTS	2
3.1	General Tasks	2
3.2	Detail Tasks	3
3.2.1	Phase I - Pre-Induction	3
3.2.2	Phase II - Rebuild	3
3.2.3	Phase III - Inspection, Testing and Acceptance	3
3.2.4	Packaging, Handling, Storage and Transportation (PHS&T)	3
3.3	Configuration Control	4
3.4	Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM)	4
3.5	Contractor Furnished Materiel (CFM)	4
3.6	Electrostatic Discharge (ESD) Control Program	4
3.7	Electromagnetic Environmental Effects (E^3) Procedures	4
3.8	Quality Assurance Provisions	5
3.9	Acceptance	5
3.10	Rejection	5
Appendix A		A-1

STATEMENT OF WORK FOR THE
Rebuild of the Tank Circuit Module Assembly (1A8)
NSN 5998-01-047-9165

1.0 SCOPE. This Statement of Work (SOW) establishes and sets forth tasks and identifies the work efforts that shall be performed by the Contractor (for purposes of this SOW, Contractor is defined as the commercial or government entity performing the rebuild) in the rebuild effort of the Tank Circuit Module Assembly 1A8. This document contains requirements to restore the Tank Circuit Module Assembly to Condition Code "A." Condition Code "A" is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction, including materiel with more than six months shelf-life remaining."

1.1 Background. REBUILD is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repairs or replacement of worn or unserviceable elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the items."

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards.

MIL-STD-129	DoD Standard Practice for Military Marking
MIL-STD-2073-1D	DoD Standard Practice for Military Packaging

2.2 Other Government Documents and Publications. The issues of those documents cited below shall be used.

TM-87107B-34/1	Maintenance Instructions for The Power Amplifier AM-6545 /GRC-193 w\Ch. 1 and 2	PCN 184 087106 00
SL-4-07743A/07749A	Repair Parts List for AN/MRC-138 w/Chg 1-15	PCN 124 077430 00
SL-4-07743A/07749A	Changes 16-24	PCN 124 077430 16-24

RS-87107B-50/3 w/Ch. 1-2	Depot Maintenance and Rebuild Standard for AM-6545B/GRC-193	PCN 170 080107 00
TI-5820-25/22	Electromagnetic Environmental Effects Procedures for Installation of Communication Equipment on US Marine Corps Platforms	PCN 168 047801 00
DOD 4000.25-1-M	MILSTRIP Manual	

Military Handbook (For Guidance)

MIL-HDBK-61	Configuration Management Guidance

2.3 Industry Standards.

JESD625-A	Requirements for Handling Electrostatic-Discharge Sensitive ESDS Devices
ANSI/ISO/ASQC Q9003-1994	Quality Systems-Model for Quality Assurance in Final Inspection and Test

Industry Standards (For Guidance)

ANSI/EIA-649	National Consensus Standard for Configuration Management

Copies of Military Standards and Specifications are available from the DOD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, Pa. 19111-5094, Telephone (215) 697-2179 or DSN 442-2179, or http://www.dodssp.daps.mil. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Contracts Department (Code 891), P.O. Drawer 43019, 814 Radford Blvd., Marine Corps Logistics Bases, Albany, Georgia 31704-3019, commercial telephone number (229) 639-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, shall be obtained from Supply Chain Management Center, Attn: Code 583-1, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6410 or DSN 567-6410.

3.0 REQUIREMENTS.

3.1 General Tasks. In fulfilling the specified requirements, the Contractor shall:

a. Provide materials, labor, equipment, facilities and missing/repair parts, necessary to inspect, diagnose, restore, test and calibrate the Tank Circuit Module Assembly. Upon completion of rebuild, the subject item shall be Condition Code "A".

b. Conduct in-process and final on-site testing for witness by a Marine Corps Systems Command (MCSC), (Code C4IHF), Albany, Georgia authorized representative.

3.1 Detail Tasks. The following tasks describe the different rebuild phases of the Tank Circuit Module Assembly.

3.2.1 Phase I- Pre-Induction. A Pre-Induction Inspection Analysis shall be performed for each Tank Circuit Module Assembly using the Contractor Facility's diagnosis, inspection and testing techniques to determine extent of work and parts required. These findings shall be annotated on the Pre-Induction Checklist (Appendix A).

3.2.2 Phase II -Rebuild. After Pre-Induction Tests and Inspections have been completed, repair of the Tank Circuit Module Assembly shall be accomplished in accordance with this SOW. Deficiencies noted on the Pre-Induction Checklist (Appendix A) during Phase I shall be repaired/replaced. Components or assemblies shall not be disassembled for replacement of parts unless that part has failed, or the component assembly wherein the part is located is disassembled for repair. Any approved Modification Instructions (MIs) and Engineering Change Proposals (ECPs) not previously applied shall be incorporated.

a. Hardware.

(1) Replace broken, unserviceable and/or missing hardware including nuts, bolts, screws, washers, turn lock fasteners, mandatory replacement items, safety and one-time use items, etc. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

3.2.3 Phase III - Inspection, Testing and Acceptance.

Inspection, Testing and Acceptance of the Tank Circuit Module Assembly shall be conducted in accordance with TM-87107B-34/1 w/Ch. 1-2, SL-4-07743A/07749A w/Ch. 1-24, RS-87107B-50/3 w/Ch. 1-2 and DoD 4000.25-1-M.

3.2.4 Packaging, Handling, Storage and Transportation (PHS&T)

a. The Contractor shall be responsible for preservation and packaging of items being repaired under the terms of this statement of work. Items scheduled for long-term storage or shipment to overseas destinations shall be in accordance with the level "A" requirements of MIL-STD-2073-1D, Appendix J., Table J.Ia., Specialized Preservation Code "GX." Items scheduled for domestic shipment and for immediate use or short-term storage shall be to level "B" requirements. Electrostatic Sensitive items shall be packed into a reusable fast-pack container.

b. Marking for shipment and storage shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the contractor with the shipping address(es) for delivery of the rebuilt equipment. The contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the subject equipment to and from the Contractor.

3.3 Configuration Control. The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the contractor shall prepare and submit a Request For Deviation (RFD). MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing this configuration control document.

3.4 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). The Management Control Activity (MCA/Code 573-2) will coordinate Government Furnished Equipment/Government Furnished Materiel (GFE)/(GFM) requests and maintain a central control system on all government owned assets in the contractor's possession. The MCA will forward a GFE Accountability Agreement to the contractor for signature on an annual basis to establish a chain of custody and identify property responsibilities for Marine Corps assets. The contractor is to acknowledge receipt of GFM to the MCA within 15 days of receipt. (This can be done by mailing (Materiel Management Department, Management Control Activity (Code 573-2) 814 Radford Blvd, STE 20320, Albany, GA 31704-0320) or faxing (commercial 229-639-5498 or DSN 567-5498) a copy of the DD1348).

3.5 Contractor Furnished Materiel (CFM). The contractor may requisition materiel as required in the performance of the SOW through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP) Chapter 11 provides guidance to contractors on the requisitioning process. The contractor's decision to utilize CFM procured from the DoD Supply System shall be based upon cost effectiveness, availability of materiel and the required completion/delivery date.

3.6 Electrostatic Discharge (ESD) Control Program. The contractor shall establish, implement and document an ESD control program following the guidelines provided in JESD625-A. ESD protective measures shall be used during manufacturing, handling, inspection, testing, marking, packaging, storing and transporting ESD sensitive components.

3.7 Electromagnetic Environmental Effects (E3) Procedures. The Contractor shall plan for and use proper (E3) control procedures in the Rebuild process and shall utilize TI-5820-25/22 in conjunction with the detailed requirements specified in this document.

3.8 Quality Assurance Provisions.

The Contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9003-1994, Quality Systems-Model for Quality Assurance in Final Inspection and Test. The program shall ensure quality throughout all areas to include processing, assembly, inspection, testing, maintenance and preparation for delivery and shipping. Unless otherwise specified in the contract, the contractor shall be responsible for performance of all inspection requirements. MCSC, (Code C4I), Albany, Georgia reserves the right to perform any of

the inspections set forth in the contract where such inspections are deemed necessary to assure products and services conform to the prescribed requirements. The Contractor shall provide an Inspection and Test Plan that will ensure the Tank Circuit Module Assembly will meet or exceed the original performance characteristics of the Tank Circuit Module Assembly. Inspection Test Plan shall be sent to: Marine Corps Systems Command, (MCSC) Attn: Logistics Management Specialist (Code C4I), 814 Radford Blvd., Albany, Georgia 31704-1128.

3.9 Acceptance. The performance of the Contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and MCSC, (Code C4I), Albany, Georgia representative shall be permitted to observe the work or to conduct an inspection. Final Inspection and Acceptance Testing shall be conducted at the Contractor's Facility. Final acceptance shall be conducted on 100 percent of items to verify that the units meet all requirements.

3.10 Rejection. Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCSC, (Code C4I), Albany, Georgia, representative. The Contractor shall, at no additional cost to MCSC, (Code C4I), Albany, Georgia, correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures is demonstrated.

Pre-Induction Checklist

Tank Circuit Module Assembly (1A8)

1. Using the following criteria, inspect the items listed below.

   a. Inspect for dirt, dust, sand, etc.
   b. Inspect for rust and/or corrosion damage.
   c. Inspect for any physical damage. (cuts, dents, cracks, broken pins, etc.)
   d. Ensure that all screws, washers, nuts, bolts, etc. are attached.
   e. Inspect for dry rot on all rubber and plastic components.
   f. Ensure that all covers and caps are attached.
   g. Ensure that all knobs, switches and breakers operate freely and properly.

S - Serviceable **U** - Unserviceable **M** - Missing

Remarks:

_____
_____
_____
_____
_____
_____
_____
_____

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 1704-0188

The Public reporting burden for this collection of information is authorized to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302 and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government issuing Contract Officer for the contract/PR No. listed in block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP _____ TM _____ Other XXX
D. SYSTEM/ITEM: Tank Circuit Module Assembly (1A8)	E. CONTRACT/PR No.	F. CONTRACTOR
1. DATA ITEM No.: A001	2. TITLE OF DATA ITEM: Inspection and Test Plan	3. SUBTITLE: Quality Control/Assurance and Inspection
4. AUTHORITY *(Data Acquisition Document No.)*: DI-QCIC-81110	5. CONTRACT REFERENCE: Paragraph 3.8	6. REQUIRING OFFICE: MARCORSYSCOM Albany (C4IHF)
7. DD 250 REQ.: DD	9. DIST STATEMENT REQUIRED: A	10. FREQUENCY: ONE/R
8. APP CODE: A	11. AS OF DATE	12. DATE OF FIRST SUBMISSION: See Blk 16
		13. DATE OF SUBSEQUENT SUBMISSION: See Blk 16

17. PRICE GROUP

18. ESTIMATED TOTAL PRICE

16. REMARKS

Block 12 – Submit 30 days after contract award by LT. Government requires 60 days to review and comment.

Block 13 – Final due 30 days after receipt of Government comments. Submit final plan by DD250.

Distribution Statement A: Approved for public release, distribution is unlimited.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES: Draft	FINAL: Reg	FINAL: Repro
MCSC Alby (C4I)	0	1	0
15. TOTAL	0	1	0

G. PREPARED BY:	H. DATE: 11-5-01	I. APPROVED BY: William H. Bender	J. DATE: 5 NOV 01

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED

Designed using Perform Pro, WHS/D/or, Aug 96

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 1704-0188

The Public reporting burden for this collection of information is authorized to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302 and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government issuing Contract Officer for the contract/PR No. listed in block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ Other XXX
D. SYSTEM/ITEM: Tank Circuit Module Assembly (1A8)	E. CONTRACT/PR No.	F. CONTRACTOR
1. DATA ITEM No.: B001	2. TITLE OF DATA ITEM: **REQUEST FOR DEVIATION (RFD)**	3. SUBTITLE: **CONFIGURATION MANAGEMENT**
4. AUTHORITY *(Data Acquisition Document No.)*: **DI-CMAN-80640C**	5. CONTRACT REFERENCE: **Para 3.3**	6. REQUIRING OFFICE: MARCORLOGBASES 583-1

7. DD 250 REQ.	9. DIST STATEMENT REQUIRED	10. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	**A**	**AS REQ**	**SEE BLOCK 16**
8. APP CODE: **A**		11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION

17. PRICE GROUP

18. ESTIMATED TOTAL PRICE

16. REMARKS

Block 4: Contractor Format using .doc or .pdf software applications is authorized.

Block 10 & 12: RFDs shall be submitted to obtain authorization to deliver nonconforming material which does not meet the prescribed configuration documentation.

RFDs will be reviewed and disposition determined within 20 working days upon receipt by the government.

RFDs shall be transmitted via e-mail to the following address: mbmatcomconfigmngmnt@matcom.usmc.mil.

Distribution Statement A: Approved for public release, distribution is unlimited.

14. DISTRIBUTION	b. COPIES		
a. ADDRESSEE	Draft	FINAL Reg	FINAL Repro
MCLBA 583-1	**0**	**1**	**0**
15. TOTAL	**0**	**1**	**0**

G. PREPARED BY:	H. DATE	I. APPROVED BY:	J. DATE
Diane L. Bradley Diane Collins	2 NOV 01	William H. Bender	5 NOV 01

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED

Designed using Perform Pro, WHS/D/or, Aug 96