

SOW-07-PMML51-101 10A-14

08 December 2003

DRAFT
Maintenance Concept Remains Consistent With Prior Fiscal Year

STATEMENT

OF

WORK

(SOW)

FOR THE REBUILD OF THE
BED ASSEMBLY, TRUCK,
TELEPHONE MAINTENANCE
5-TON, 6X6,
NSN 2320-01-387-5781
M876A1

SOW-07-PMM151-101 bA-lu

EFFECTIVE DATE:

1 OCT 2005

SOW-07-PMML5 1-101 bA-hi

08 December 2003

TABLE OF CONTENTS

Section and Heading	Page
1.0 SCOPE	1
1.1 Background	
2.0 APPLICABLE DOCUMENTS	1
2.1 Military Standards	I
2.2 Other Government Documents and Publications	1
2.3 Industry Standards	2
3.0 REQUIREMENTS	3
3.1 General Tasks	3
3.2 Detailed Tasks	3
3.2.1 Phase 1 Pre-Induction	3
3.2.2 Phase II REBUILD	3
3.2.3 Phase III Inspection, Testing, and Acceptance	4
3.2.4 Packaging, Handling, Storage and Transportation (PHS&T)	5
3.3 Configuration Control	6
3.4 Government Furnished Equipment (GFE)!	
Government Furnished Equipment (GFM)	6
3.5 Contractor Furnished Materiel	6
3.6 Quality Assurance Provisions	6
3.7 Rejection	6
4.0 REPORTS	7
4.1 Final Inspection Checklist	7

SOW-07-PMML51-10b bOA-i/I

08 December 2003

STATEMENT OF WORK

FOR THE REBUILD of the
Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1

NSN 2320-01-387-578 1

1.0 SCOPE. This Statement of Work (SOW) establishes, sets forth tasks and identifies the work

efforts that shall be performed by the contractor in the rebuild effort of the Bed Assembly only

on the Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1. This document contains requirements to restore the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 to Condition Code "A." Condition Code "A" is defined as "serviceable/issuable without qualification, new, used, repaired, or reconditioned materiel which is

serviceable and

issuable to all customers without limitation or restriction. National Stock Number 2320-01-387-

5781 shall be known as the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1. The contractor shall be provided an M925A1, 5-Ton, 6X6 Truck Chassis (NSN 2320-01-206-4088) as Government Furnished Equipment. After rebuild of the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1, the contractor shall install that bed on the Government furnished chassis per MI-ioi bOA-SO/i.

1.1 Background. Rebuild is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and

life expectancy. This is accomplished through a maintenance technique or complete disassembly

of the item, inspection of all parts or components, repair or replacement of worn or unserviceable

parts/elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the item."

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the

Department of Defense Index of Specifications and Standards (DODISS) and supplement

thereto which is in effect on the date of solicitation. In the event of conflict between the

documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards

MJL-STD-i29	DoD Standard Practice: Military Marking for Shipment and Storage
-------------	--

MJL-STD-3003	Vehicles, Wheeled; Preparation for Shipment and Storage of
--------------	--

2.2 Other Government Documents and Publications

ASTM D 3951	Standard Practice for Commercial Packaging
-------------	--

TM-3 080-50	Corrosion Prevention Control
-------------	------------------------------

SOW-07-PMM151-i0i bOA-i/i

08 December 2003

DOD 4000.25-1-M

TM 9-2320-272-20-i

TM 9-2320-272-20-2

TM 9-2320-272-34-i

TM 9-2320-272-34-2

TM 9-2320-272-24P-1

TM 9-2320-272-34P-1

MI-10i bA-SO/i

MI-ioi iOA-35/2

Military Standard Requisitioning and Issue Procedures
(MILSTRIP)

Telephone Maintenance Truck

Telephone Maintenance Truck

Telephone Maintenance Truck

Telephone Maintenance Truck

Telephone Maintenance Truck

Telephone Maintenance Truck

Install D845-Tr Digger to ST TRK

FRI Outrigger Assembly On To TRK
Military Handbooks (For Guidance)

MJL-HDBK-6 1

2.3 Industry Standards

ANSIIJSO/ASQC

Q900 i -2000

Configuration Management Guidance

Quality Management Systems - Requirements
Industry Standards (For Guidance)

ANS]YEIA-649

National Consensus Standard for Configuration
Management

Copies of Military Standards and Specifications are available from the DoD Single
Stock
Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue,
Philadelphia, PA 191 i i-5094, commercial telephone number (215) 697-2179 or DSN 442-
2i79,
or <http://www.dodssp.daps.mil>. Copies of other government documents and publications
required by contractors in connection with specific SOW requirements shall be obtained
through
the Contracts Department, (Code 891), P. O. Drawer 43019, 814 Radford Blvd., Marine Corps
Logistics Command, Albany, GA 3i704-30i9, commercial telephone number (229) 639-676i
or DSN 567- 6761. Copies of engineering drawings, if applicable, shall be obtained from
the
Supply Chain Management Center, Attn: Code 566-iA, 814 Radford Blvd. Suite 20320, Albany,
Georgia 3 1704-0320, commercial telephone number (229) 639-6476 or DSN 567-6476.

3.0 Requiirements.

3.1 General Tasks. In fulfilling the specified requirements, the contractor shall:

- a. Provide materials, labor, facilities, repair parts, and missing parts necessary to inspect, diagnose, restore, and test the Bed Assembly, of the Truck, Telephone Maintenance, 5 Ton, 6X6,

M876Ai. Upon completion of rebuild, the Bed Assembly shall be Condition Code "A."

b. Provide all tools and test equipment required to test, inspect, and calibrate the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876Ai.

c. Conduct final on-site testing for witness by a Marine Corps Systems Command (MCSC), (Code PMMI5 1), Albany, Georgia, representative.

d. Be responsible for all structural, electrical and mechanical requirements associated with the restoration of the Bed Assembly of the Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 using TM 9-2320-272-20-1 and 2, TM 9-2320-272-34-1 and 2, TM 9-2320-272-24P-1 and TM 9-2320-272-34P-1 as guidance.

e. Conduct 100 percent replacement of hydraulic hoses.

f. Be responsible for all corrosion prevention and control in accordance with the latest TM-3080-50.

3.2 Detailed Tasks. The following tasks describe the different phases for rebuild of the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1:

3.2.1 Phase I – Pre-Induction. A Pre-Induction Inspection Analysis shall be performed for each Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 to determine extent of work and parts required in accordance with TM 9-2320-272-20-1 and 2, and TM 9-2320-272-34-1 and 2. If it is determined that the cost of repair exceeds the standard unit price or acquisition!

the replacement cost as imposed by current Marine Corps directives or for any other reason,

contractor facility rejects a rebuild candidate, the government shall be provided by the contractor facility, a completed copy of the Initial Inspection Checklist to include a cost estimate

and a request for specific instructions to MCSC (Code PMM1 51), Albany, Georgia. The intent of this clause is to preclude the arbitrary rejection of "rebuild" candidates by the contractor

based solely on cost criteria directed by current Marine Corps directives. MCSC (Code PMM1S 1), Albany,

Georgia retains the right to make the final decision to restore the end item to a serviceable (condition code "A") asset in the most expeditious manner to enhance Marine Corps readiness.

readiness.

3.2.2 Phase II – REBUILD. After Pre-Induction Tests and Inspections have been completed, repair of the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876Ai shall be accomplished in accordance with this SOW at the contractor's facility. Deficiencies noted on the Initial Inspection Checklist during Phase I shall be repaired/replaced.

SOW-07-PMM151-101 bA-hi

08 December 2003

a. Data plate. Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 shall have a REBUILD data plate located on the control station of the derrick next to the original manufacturer's capacity placard data plate. This plate (refer to Figure 1) shall be constructed of metal and is to be attached after the vehicle has completed the rebuild cycle. The data plate shall contain the following information:

REBUILT EN ACCORDANCE WITH SOW-06-PMMI 51-101 bA-hi
SER. NO _____ DATE _____
CONTRACTOR _____

(Figure 1)

b. Hardware

(1) Replace broken, unserviceable, and/or missing hardware including nuts, bolts, screws, washers, turnlock fasteners, etc., in accordance with the TM 9-2320-272-20-1 and 2, and TM 9-2320-272-34-1 and 2. Unserviceable would include any of the above that failed to function

properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

(4) The contractor is authorized to fabricate "by sample" any item/part for the Bed Assembly, Truck, Telephone Maintenance, 5-Ton 6x6, M876A1 for which an Engineering Drawing does not exist or for any other reason the government may approve. The hydraulic hoses are acceptable items for this method.

c. Application of Modification Instruction (MIs) and Technical Instructions (TI).

The following MIs shall be applied during this phase of the rebuild process:

MI-101 bOA-SO/I	Install D845-Tr Digger to 51 TRK
Mi-i 011 OA-35/2	FRI Outrigger Assembly On To IRK

3.2.3 Phase III - Inspection, Testing, and Acceptance

a. Inspection, Testing and Acceptance of the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 shall be conducted in accordance with TM 9-2320-272-20- 1 and 2, TM 9-2320-272-34-1 and 2.

4

SOW-07-PMM15b-b0b bOA-b/b

08 December 2003

b. The contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are available to complete the final acceptance. Acceptance tests shall be held at the contractor's facility. MCSC (Code PMM1 Sb), Albany, Georgia, representatives shall be given a minimum of two weeks notice prior to beginning acceptance testing. The test area shall be cleared of all equipment parts, components, etc., not required for testing.

c. The contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCSC (PMM1S 1), Albany, Georgia may require the contractor to repeat tests, or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

d. Acceptance testing on Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1 under the provisions of this SOW shall be accomplished in accordance with TM 9-2320-272-20-b and 2 and TM 9-2320-272-34-1 and 2.

3.2.4 Packaging. Handling. Storage and Transportation (PHS&T)

a. The Contractor shall be responsible for the preservation and packaging of items being

storage, repaired/rebuilt under the terms of this Statement of Work. Items shipped for long-term storage, as directed by the Program Manager or Logistics Management Specialist, shall be in accordance with MIL-STD-3003. Items shipped domestically for immediate use shall be shipped in accordance with the requirements of ASTM D 3951, Standard Practice for Commercial Packaging, ensuring that equipment shall be delivered without damage being incurred.

Items to be shipped to overseas destinations shall be in accordance with ASTM D 395b, paragraph 6.1, Export requirements and shall have a label affixed "NOT FOR WEATHER DECK STOWAGE". Both shall be in accordance with Drive-on/Drive-off application as described below. Items scheduled for Maritime Pre-Positioned Forces shall be prepared in accordance with the best commercial practices of ASTM D 395b and in accordance with MPF Modified Drive-away below.

(1) Definition of Drive-on/Drive-off and MPF Modified Drive-away are as follows:

vehicle (a) Drive-on/Drive-off: Batteries shall be hot and disconnected from the electrical system, terminals and leads shall be taped. Fuel Tank(s) shall be V4 filled with JP5/8. The air intake, exhaust and brake systems, drive train and gauges shall be de-preserved.

(b) MPF Modified Drive-away: Batteries shall be hot and connected to the vehicle electrical system. Fuel Tank(s) shall be 3/4 full of JP5/8. The air intake, exhaust and brake systems, drive train and gauges shall be de-preserved. Fire extinguisher brackets and seats shall be installed.

b. Marking for shipment and Storage shall be in accordance with MIL-STD-b 29.

c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of the repaired equipment. The Contractor shall be responsible for delivery of the equipment to the pre-designated site(s). The Marine Corps will be responsible for the

5

SOW-07-PMM15 1-1011 OA-b/1

08 December 2003

transportation costs associated with the delivery of the subject equipment to and from the Contractor's facility.

3.3 Configuration Control. The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to depart from the authorized configuration baseline, the contractor shall submit a Request for Deviation. MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing these configuration control documents.

3.4 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM) The Management Control Activity (MCA) (Code 58b-bB) will coordinate GFE/GFM requests and maintain a central control system on all government owned assets in the contractor's possession.

The MCA will forward a GFE Accountability Agreement to the contractor for signature on an annual basis to establish a chain of custody and identify property responsibilities for Marine Corps assets. The contractor is to acknowledge receipt of GFM to the MCA within 15 days of receipt. This can be done by mailing a copy of the DD1 348 to Materiel Management Department, Management Control Activity (Code 58b-bB), 8b4 Radford Blvd., STE 20320, Albany, GA 3 1704-0320, or faxing a copy to commercial telephone number (229) 639-5498 or DSN 567-5498.

3.5 Contractor Furnished Materiel (CFM). The Contractor may requisition materiel as required in the performance of the SOW through the DoD Supply System. DoD 4000.25-1-M (MILSTRJP), Chapter 11, provides guidance to contractors on the requisitioning process. The contractor's decision to utilize CFM procured from the DoD Supply System shall be based upon cost effectiveness, availability of materiel and the required completion/delivery date.

3.6 Quality Assurance Provisions. The contractor shall provide and maintain a Quality

System

that, as a minimum, adheres to the requirement of ANSI/JSO/ASQC Q900b-2000, Quality Management Systems – Requirements. MCSC (Code PMM15 b) Albany, GA retains the right to conduct in-process reviews and inspections for compliance with these procedures and standards.

MCSC, (Code PMM1 SI) Albany, GA further retains the right for in-process reviews and inspections of the quality of work delivered, material provided and documents written

during

contract performance. Failure of the contractor to promptly correct deficiencies

discovered shall

be reason for suspension of acceptance until corrective action has been accomplished.

3.7 Rejection. Failure to comply with any of the specified requirements listed herein

shall be

reason for rejection by MCSC (Code PMM1 51), Albany, Georgia. The contractor shall, at no additional cost to MCSC (Code PMM15 1), Albany, Georgia, provide the following:

a. Develop an approach for modification or correction of all deficiencies.

b. Upon approval of a documented approach, the contractor shall correct the

deficiencies

and repeat the verification until an acceptable compliance with acceptance test

procedures

requirements is demonstrated.

SOW-07-PMM151-101 bA-i/i
4.0 REPORTS

08 December 2003

4.1 Final Inspection Checklist. The contractor shall provide Final Inspection Checklist
Contractors format for each Bed Assembly, Truck, Telephone Maintenance, S Ton, 6X6,
M876A1. These documents shall be available during final acceptance testing. One copy of
document shall be provided to Marine Corps Systems Command, (Code PMM1 51), Marine
Corps Logistics Command, 814 Radford Blvd. Suite 20343, Albany, Georgia 31704-0343,
final acceptance of the Bed Assembly, Truck, Telephone Maintenance, 5 Ton, 6X6, M876A1.