

**STATEMENT  
OF  
WORK  
(SOW)  
FOR THE REBUILD OF THE  
TRAILER, DROPSIDE  
LOGISTICS VEHICLE SYSTEM**

**MK-17**

**NSN 2320-01-176-0468**

**CONTROL NR: SOW-03-835-1-08784A-1/1**

**EFFECTIVE DATE: 1 OCTOBER 01**

## TABLE OF CONTENTS

<u>Section and Heading</u>	<u>Page</u>
1.0 Scope	1
1.1 Background	1
2.0 Applicable Documents	1
2.1 Military Standards	1
2.2 Other Government Documents and Publications	1
2.3 Industry Standards	2
3.0 Requirements	2
3.1 General Tasks	2
3.2 Detailed Tasks	3
3.2.1 Phase I Pre-Induction	3
3.2.2 Phase II REBUILD	3
3.2.3 Phase III Inspection, Testing, and Acceptance	4
3.2.4 Preparation for Shipment and Storage	4
3.3 Configuration Control	4
3.4 Government Furnished Equipment (GFE)/ Government Furnished Materiel (GFM)	5
3.5 Contractor Furnished Materiel (CFM)	5
3.6 Quality Assurance Provisions	5
3.7 Rejection	6
4.0 REPORTS	6
4.1 Parts Usage Data Report	6
4.2 Road Test and Final Inspection Checklist	6

appendix A – Sample Parts Usage Data Report

STATEMENT OF WORK FOR THE  
Trailer, Dropside, Logistics Vehicle System (LVS) MK17  
NSN 2320-01-176-0468  
Rebuild

1.0 SCOPE. This Statement of Work (SOW), along with Rebuild Standard RS 08784A-50, establishes and sets forth tasks and identifies the work efforts that shall be performed by the contractor in the REBUILD effort of the Trailer, Dropside, LVS MK-17. These documents contain minimum requirements to restore the Trailer, Dropside, LVS MK-17 to Condition Code "A." Condition Code A is defined as "serviceable/issuable without qualification, new, used, repaired, or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction. Includes materiel with more than six months shelf-life remaining." National Stock Number 2320-01-176-0468 shall be known as the LVS MK17.

1.1 Background. REBUILD is defined as "That maintenance technique that determines the repairs necessary to restore equipment components and/or assemblies to a prescribed maintenance serviceability and standard that approximates the original or new condition in appearance, performance, and life expectancy." The Contractor shall disassemble all assemblies/sub-assemblies, inspect, test, repair and/or replace. All worn parts/components that are beyond the specified tolerances and wear limits shall be replaced. Unless otherwise provided for in this SOW all parts and components may be reused if they meet the criteria established in RS 08784A-50.

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the issue of Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards

MIL-STD-129

DoD Standard Practice for Military Markings

2.2 Other Government Documents and Publications. The issues of those documents cited below shall be used.

MI-2320-35/75

Fabrication/Installation of Tool Box Support For the  
Logistics Vehicle (LVS) MK14, MK15, MK17  
Trailers

MI-2320-25/68

Spacer Blocks on Hydraulic Hose Clamps on the  
MK15/17 LVS Crane

MI-08784A-25/1

Installation of Spring Clips on the Logistics  
Vehicle, Trailer MK17

MI-08784A-45/2	Air Lift Bracket Installation on the Logistics Vehicle System, MK17
RS 08784A-50	Depot Maintenance Manual LVS MK17
TM 3080-50	Corrosion Prevention and Control
ATPD 2241	Vehicles, Wheeled: Preparation for Shipment and Storage of.
DOD 4000.25-1-M	MILSTRIP Manual
NAVICPINST 4491.2A	Requisitioning of Contractor Furnished Materiel from the Federal Supply System

**Military Handbooks (For Guidance)**

<b><i>MIL-HDBK-61</i></b>	<b><i>Configuration Management Guidance</i></b>
---------------------------	---

2.3 Industry Standards

ANSI/ISO/ASQC Q9002-1994	Quality Systems-Model for Quality Assurance in Production, Installation, and Servicing
--------------------------	--

**Industry Standards (For Guidance)**

<b><i>ANSI/EIA-649</i></b>	<b><i>National Consensus Standard for Configuration Management</i></b>
----------------------------	--

Copies of Military Standards and Specifications are available from the DOD Single Stock Point, Document Automation and Production Service, Building 4D, 700 Robbins Avenue, Philadelphia, PA. 19111-5094, Telephone (215) 697-2179 or DSN 442-2179, or <http://www.dodssp.daps.mil>. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Commander, Attn: Contracting Officer (Code 891), Marine Corps Logistics Bases, 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number (229) 639-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, shall be obtained from Life Cycle Management Center, Attn: Code 851-3, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6410 or DSN 567-6410.

3.0 REQUIREMENTS

3.1 General Tasks. In fulfilling the specified requirements, the contractor shall:

a. Provide materials, labor, facilities, repair parts, and missing parts necessary to inspect, diagnose, restore, and test the LVS MK17. Upon completion of REBUILD, repaired vehicles shall be Condition Code "A."

- b. Provide all tools and test equipment required to test, inspect, and calibrate the LVS MK17.
- c. Conduct final on-site testing for witness by a MCLB, Albany, Georgia, representative (Code 835).
- d. Be responsible for all structural, electrical and mechanical requirements associated with the restoration of the LVS MK17.
- e. Be responsible for all corrosion prevention and control in accordance with the latest TM 3080-50.

3.2 Detailed Tasks. The following tasks describe the different phases for REBUILD of the LVS MK17:

3.2.1 Phase I- Pre-Induction. A pre-induction inspection analysis is not required since the LVS MK17 is a rebuild effort.

3.2.2 Phase II - REBUILD. Rebuild of the LVS MK17 shall be accomplished in accordance with this SOW and RS 08784A-50 at the contractors facility. Rebuild of the LVS MK17 shall be accomplished by the application of contractor maintenance techniques by experienced journeyman level personnel to meet quality standards and inspection criteria contained in RS 08784A-50.

a. Data plate. LVS MK17 shall have a REBUILD data plate located next to the original manufacturer's data plate. This plate (refer to Figure 1) shall be constructed of metal and is to be attached after the vehicle has completed the REBUILD cycle. The data plate shall contain the following information:

VEH. SER. NO. \_\_\_\_\_ DATE \_\_\_\_\_

REBUILT IN ACCORDANCE WITH RS 08784A-50

CONTRACTOR \_\_\_\_\_

(Figure 1)

b. Hardware

(1) Replace broken, unserviceable, and/or missing hardware including nuts, bolts, screws, washers, turnlock fasteners, etc., in accordance with the LVS MK17 RS 08784A-50. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

c. Application of Modification Instructions (MI's). The following MI's shall be applied during this phase of the REBUILD process: MI-2320-35/75, MI-2320-25/68, MI-08784A-25/1, and MI-08784A-45/2.

### 3.2.3 Phase III - Inspection, Testing, and Acceptance.

a. Inspection, Testing and Acceptance of the LVS MK17 shall be conducted in accordance with the Road Test and Final Inspection Checklist located in Table 2-4 of RS 08784A-50. This completed document shall be provided in accordance with Section 4.0 of this SOW.

b. The contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are available to complete the final acceptance. Acceptance tests shall be held at the contractor's facility. MCLB, Albany, Georgia, representatives (Code 835) shall be given a minimum of two weeks notice prior to beginning acceptance testing. The test area shall be cleared of all equipment parts, components, etc., not required for testing.

c. The contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCLB, Albany, Georgia, (Code 835) may require the contractor to repeat tests or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

d. Acceptance testing on all LVS MK17 vehicles repaired under the provisions of this SOW shall be accomplished in accordance with RS 08784A-50.

### 3.2.4 Packaging, Handling, Storage and Transportation (PHS&T).

a. The contractor shall be responsible for the application of preservation and packaging of items being repaired under the terms of this statement of work. Items being prepared for long term storage or shipment to overseas destinations shall be preserved and packaged in accordance with the level A requirements of ATPD 2241. Items being prepared for domestic shipment, immediate use or short-term storage shall be to level B requirements.

b. Marking shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the contractor with the shipping address(es) for delivery of the repaired equipment, and the contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the subject equipment to and from the Contractor.

**3.3 Configuration Control. *The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the contractor shall prepare and submit a Request For Deviation. MIL-HDBK-61 (paragraph 4.3***

*and Table 4-9) and ANSI/EIA-649 (paragraph 5.3.4) provide guidance for preparing this configuration control document.*

**3.4 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM)** GFE is government owned equipment authorized by contract for use by a commercial/ Government contractor. It is neither consumed during production nor incorporated into any product. GFM is materiel furnished to a contractor that will be consumed during the course of production or incorporated into the product being manufactured/remanufactured under a contract/ statement of work. In the event the Marine Corps does have GFE/GFM requirements the Management Control Activity (MCA/Code 827-2), Marine Corps Logistics Bases, Albany, Georgia, will coordinate required GFE and will maintain a central control on Marine Corps assets in the Contractor's possession. The MCA will forward a GFE Accountability agreement to the Contractor Facility for signature to establish a chain of custody and property responsibilities for Marine Corps assets.

**3.5 Contractor Furnished Materiel (CFM)** The Marine Corps has adopted the Navy's procedures regarding Contractor Furnished Materiel (NAVICPINST 4491.2A). In the event Contractor Furnished Materiel (CFM) is required for repair parts, the Contractor shall requisition through the DoD Supply System. DoD 4000.25-1-M, (MILSTRIP) Chapter 11 authorizes contractors to requisition through the DoD Supply System.

**3.6 Quality Assurance Provisions.** The contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirement of ANSI/ISO/ASQC Q9002-1994, Quality Systems-Model for Quality Assurance in Production, Installation, and Servicing. Performance of the contractor and the quality of work delivered, materiel provided, and documents written shall be subject to review and inspection by MCLB, (Code 835) Albany representatives during work performance at any work location. Authorized MCLB, (Code 835) Albany, Georgia, representatives shall be permitted to observe the work/task accomplishment or to conduct inspections during working hours. Inspection by MCLB, Albany, Georgia, representatives (Code 835), of test plans and materials furnished hereunder does not relieve the contractor from any responsibility regarding defects or other failures to meet work requirements which may be disclosed prior to final acceptance. Failure of the contractor to promptly correct deficiencies discovered shall be reason for suspension of acceptance until corrective action has been accomplished.

The contractor shall have in place documented procedures and standards for inspection requirements and the contractor's work shall be subject to reviews and inspections for compliance with these procedures and standards by MCLB, Albany, Georgia representatives (Code 835). Noncompliance with procedures resulting in degraded quality of work may result in a stop-work order requiring action by the contractor to correct the work performed and to enforce compliance with quality assurance procedures or face work termination. Notwithstanding such MCLB, Albany, Georgia, representative inspection, it shall be the contractor's responsibility to ensure that the entire system meets the performance requirements delineated and addressed in this SOW.

**3.7 Rejection.** Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCLB, Code 835 Albany, Georgia. The contractor shall, at no additional cost to MCLB, Albany, Georgia, provide the following:

a. Develop an approach for modification or correction of all deficiencies.

b. Upon approval of a documented approach, the contractor shall correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures requirements is demonstrated.

#### 4.0 REPORTS

4.1 Parts Usage Data Report. The Contractor shall provide a Parts Usage Data Report for every twenty vehicles produced. This report shall be in the Contractors format and as a minimum, list by nomenclature, national stock number, part number, price and quantity of all parts replaced. The report shall be provided to Commander (Code 835-1), Marine Corps Logistics Bases, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320. Appendix A is provided as a sample.

4.2 Road Test and Final Inspection Checklist. The contractor shall complete the Road Test and Final Inspection Checklist for each LVS MK17 repaired. These documents shall be available during final acceptance testing. One copy of each document shall be provided to Commander (Code 835-1), Marine Corps Logistics Bases, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320, after final acceptance of the LVS MK17.



	Fig #	Item	Kit No.	FSC	NSN	Part #	Qty	Unit \$	Total \$	Replcd %	Replace	Used
Cab Assm	TM 2320-24P/14B											
			01MRP2801									
	210	1		2510	012332569	123616RU	1	\$3,872.31	\$8,872.31			
	209	1	00MRPXXX	2540	011527909	840	2	\$15.89	\$31.78			
	209	22	01MRP2549	2540	011513844	1325890	2	\$36.35	\$72.70			
	209	30	1759650W	5440	013575699	1759650 W	2	\$46.90	\$93.80			
	312	52		1005	012661233	5705590	1	\$68.87	\$68.87			
	312	54		1095	007637348	11630529	2	\$19.76	\$39.52			
			01MRP2547	5342	012502237	128836C W	1	\$28.49	\$28.49			
			01MRP2547	5340	012479444	1340080 W	1	\$58.24	\$58.24			
			01MRP2547		012484553	129200BU	1	\$82.28	\$82.28			
			01MRP2547		012417405	1340100W	1	\$231.71	\$231.71			
			00MRPXXX		011548406	130726	1	\$311.42	\$311.42			
	222	2			011538448	130723	1	\$38.54	\$38.54			
	222	3		2540	012642024	130724	1	\$83.52	\$83.52			
			00MRPXXX	5340	012366311	1429570	1	\$296.15	\$296.15			
	222	21			013606538	F08900	1	\$82.93	\$82.93			
	222	9		2510	011538450	707774	1	\$48.55	\$48.55			
	209	37	01MRP2636	2540	011554155	1349180	1	\$57.15	\$57.15			
			00MRPXXX	2540	012424866	131026	1	\$432.81	\$432.81			
	222	2			011538448	130723	1	\$38.54	\$38.54			
	222	21	00MRPXXX	5340	012366311	1429570	1	\$296.15	\$296.15			
	209	37	01MRP2636	2540	011554155	1349180	1	\$57.15	\$57.15			
			01MRP2445									
	75	11	01MRP2700	5995	012475725	1500380W	1	\$43.67	\$43.67			
			01MRP2701			1345630	1	?	#VALUE!			
									\$0.00			
	73	4		6620	011428277	0634114	1	\$17.21	\$17.21			
	313	1		6685	011218017	140490	1	\$49.35	\$49.35			
	73	9		6680	011312551	0633915	1	\$17.35	\$17.35			
	73	14		6620	011319620	0634317	1	\$17.14	\$17.14			
	73	20		6685	011324637	0634914	1	\$20.91	\$20.91			
	73	25		6625	011027599	0635215	1	\$14.11	\$14.11			
	73	30		6620	012443425	0697263	1	\$25.01	\$25.01			
	73	36		6680	011319693	535K1/47711	1	\$96.06	\$96.06			
	73	8		6680	012674356	47828	1	\$114.03	\$114.03			
									\$0.00			
	73	57		6210	010531290	1053628	3	\$23.07	\$69.21			
	75	2		6210	012064754	1053621	2	\$20.74	\$41.48			

Shield, Light	71/19 73/53	75	1	6210	010549460	1215	3	\$3.05	\$9.15
Buzzer Warning System		75	29	6350	001024210	SC628	1	\$85.77	\$85.77
Low Air Pressure Alarm		73	77	6350	010524043	443724	1		\$0.00
Drive Line Lockup Valve		161	55	4820	010505584	285402	1	\$63.92	\$63.92
Air Brake Valve(Air Control)		169	1	01MRP2642	011517984	118569	1	\$162.69	\$162.69
Air Restrictor Indicator		33	6	2940	011544713	RAX007388	1	\$18.18	\$18.18

(1 Data Item)

OMB No. 1704-0188

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY:
		TDP                  TM                  Other XXX

18. ESTIMATED  
TOTAL PRICE

J. DATE

Page 1 of 1 Pages  
Designed using Perform Pro, WHS/D/or, Aug 96