STATEMENT OF WORK
FOR THE
STANDARDIZED
BARE BASE
LAUNDRY FACILITY
NSN 3510-01-165-6845
Inspect Repair Only As Necessary
(IROAN)

TABLE OF CONTENTS

STATEMENT OF WORK FOR THE STANDARDIZED BARE BASE LAUNDRY FACILITY Inspect Repair Only As Necessary (IROAN) NSN 3510-01-165-6845

1.0 SCOPE. This Statement of Work (SOW) establishes and sets forth tasks and identifies the work efforts that shall be performed by the Contractor in the IROAN effort of the Standardized Bare Base Laundry Facility, hereafter referred to as the Laundry Unit. This document contains requirements to restore the Laundry Unit to Condition Code "A." Condition Code A is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction, including materiel with more than six months shelf-life remaining." National Stock Number (NSN) 3510-01-165-6845 shall be known as the Laundry Unit, Bare Base.

1.1 Background. IROAN is defined as "That maintenance technique which determines the minimum repairs necessary to restore equipment components or assemblies to prescribed maintenance serviceability standards by utilizing all available diagnostic equipment and test procedures in order to minimize disassembly and parts replacement."

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Specifications

MIL-C-46168	Coating, Aliphatic Polyurethane, Chemical Agent Resistant
MIL-C-53039	Coating, Aliphatic Polyurethane, Single Component, Chemical Agent Resistant

2.2 Military Standards

MIL-STD-129	DoD Standard Practice for Military Marking
MIL-STD-130	Identification Marking of US. Military Property
MIL-STD-461	Requirements for the Control of Electromagnetic Interference Characteristics of Subsystems and Equipment
MIL-STD-2073-1D	DoD Standard Practice for Military Packaging

2.3 Other Government Documents and Publications

DOD 4160.21-M-1	Defense Demilitarization Manual
DOD 4000.25-1-M	MILSTRIP Manual
SL-3-09950A	Field Laundry Unit
TM 09950A-14/1 M/S	Laundry Facility, Std Bare Base
TM 09950A-14/1 M/S, CH00A	Laundry Facility, Std Bare Base
TM 09950A-14/1 M/S, Supplement 1	Laundry Facility, Std Bare Base
TM 3080-12	Corrosion Prevention and Control for Marine Corps Equipment
TM 3080-50	Corrosion Control Procedures Depot Maintenance Activities for Marine Corps Equipment
TM 4700-15/1H	Ground Equipment Record Procedures
TM 4750-15/1	Painting and Registration Marking for Marine Corps Combat and Tactical Equipment
TM 4750-15/2	Camouflage Paint Patterns
Military Handbooks (For Guidance)	
MIL-HDBK-61	Configuration Management Guidance

2.4 Industry Standards

ANSI/ISO/ASQC Q9002-1994	Quality Systems-Model for Quality Assurance in Production, Installation, and Servicing
Industry Standards (For Guidance)	
ANSI/EIA-649	National Consensus Standard for Configuration Management

Copies of Military Specifications and Standards are available from the DOD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2179 or DSN 442-2179, or http://www.dodssp.daps.mil. Copies of other government documents and publications required

by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Contracts Department (Code 891), P.O. Drawer 43019, 814 Radford Blvd., Albany, Georgia 31704-3019, commercial telephone number (229) 639-6753 or DSN 567-6753. Copies of engineering drawings, if applicable, shall be obtained from Supply Chain Management Center, Attn; Code 583-1, 814 Radford Blvd STE 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6410 or DSN 567-6410.

3.0 REQUIREMENTS

3.1 General Tasks. In fulfilling the specified requirements, the Contractor shall:

a. Provide materials, labor, facilities, missing parts, and repair parts necessary to inspect, diagnose, restore, and test the Laundry Unit. Upon completion of IROAN, repaired equipment shall be Condition Code "A".

b. Provide all tools and test equipment required to test, inspect, repair, and calibrate the Laundry Unit.

c. Conduct in-process and final on-site testing for witness by a Marine Corps Systems Command (MCSC) (Code CSLE), Albany, Georgia, representative.

d. Be responsible for all structural, electrical and mechanical requirements associated with the restoration of the Laundry Unit.

3.2 Detail Tasks. The following tasks describe the different phases for IROAN of the Laundry Unit.

3.2.1 Phase I - Pre-Induction. The Contractor shall perform a pre-induction inspection analysis for each Laundry Unit using the Contractor's diagnosis, inspection and testing techniques to determine extent of work and parts required. This inspection shall include all items associated with the Laundry Unit as found in TM 09950A-14/1 M/S, TM 09950A-14/1 M/S CH00A, TM 09950A 14/1 M/S Supplement 1 and SL-3-09950A. These findings shall be annotated on a Pre-Induction Checklist (Appendix A) and shall be provided to the government in accordance with Paragraph 4.0 of this SOW.

3.2.2 Phase II - IROAN. After pre-induction tests and inspections have been completed, repair of the Laundry Unit shall be accomplished in accordance with this SOW. Deficiencies noted on the Pre-Induction Checklist during Phase I shall be repaired/replaced. Components or assemblies shall not be disassembled for replacement of mandatory parts unless that part has failed, or the component assembly wherein the part is located is disassembled for repair.

a. Pre-Induction Checklist - Information recorded on the Pre-Induction Checklist report shall be used as a guide to repair the Laundry Unit system in accordance with this SOW.

b. Technical Instruction (TI) - All TI's not previously applied to the Laundry Unit shall be applied during the IROAN and shall be annotated on Equipment Record Jacket in accordance with TM 4700-15/1H.

c. Corrosion - For corrosion prevention and treatment use TM 3080-12 and TM 3080-50.

d. Fluid Leaks - The following shall be used as a guide in determining degree of fluid loss:

(1) Class I - Seepage of fluid (as indicated by wetness or discoloration) not great enough to form drops.

(2) Class II - Leakage of fluid great enough to form drops, but not enough to cause drops to fall from the item being checked/inspected.

(3) Class III- Leakage of fluid great enough to form drops that fall from the item being checked/inspected.

NOTE:

A Class I Leak, except in fuel or brake systems, is an acceptable condition at any time and does not require corrective action.

e. Belts - Replace all.

f. Data Plates - All required data plates and decals shall be in place and shall be legible. Each repaired Laundry Unit shall have an IROAN data plate affixed to the main unit in close proximity to the existing data plate. The data plate shall meet the requirements of MIL-STD-130 and TM 4750-15/2.

g. Painting/Coating (Exterior/Interior) - If painting/coating is required, refer to TM 4750-15/1 and TM 4750-15/2. The Laundry Unit shall be cleaned in accordance with TM 3080-50, Chapter 4, and coated with Aliphatic Polyurethane Coating, in accordance with MIL-C-46168 or MIL-C-53039.

h. Demilitarization - All end items that are identified as non-repairable and require demilitarization codes, shall be reported to the MCSC (Code CSLE), Albany, Georgia, representatives, who will provide disposition instructions in accordance with DOD 4160.21-M-1.

i. Electromagnetic Emission - All requirements pertaining to control of electromagnetic interference, emission and susceptibility shall be in accordance with MIL-STD-461.

j. Hardware

(1) Replace broken, unserviceable and/or missing hardware including nuts, bolts, screws, washers, turnlock fasteners, mandatory replacement items, safety and one-time use items, etc., in

accordance with TM 09950A-14/1 M/S and SL-3-09950A. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present and operational on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

k. Hoses - All hoses and fittings shall be visually inspected for damage or deterioration. Any hose showing signs of leakage, kinking or separation of outer coating shall be replaced. This inspection shall be performed during the Pre-induction inspection of the Laundry Unit.

l. Cable Assemblies - All cables and cable connections shall be tested and visually inspected for damage or corrosion. Any cable or cable connector showing signs of damage, corrosion or separation of outer coating shall be repaired/replaced and tested with its respective component/assembly to assure satisfactory compliance with all operational tests.

m. Filters - Replace all.

3.2.3 Phase III - Inspection, Testing and Acceptance

a. Inspection, Testing and Acceptance of the Laundry Unit shall be conducted in accordance with TM 09950A-14/1 M/S.

b. The Contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are available to complete the final acceptance. Acceptance tests shall be held at the Contractor's facility. MCSC (Code CSLE), Albany, Georgia, representatives shall be given a minimum of two weeks notice prior to beginning acceptance testing. The test area shall be cleared of all equipment parts, components, etc., not required for the test.

c. The Contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCSC (Code CSLE), Albany, Georgia, representatives may require the Contractor to repeat tests or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

d. Acceptance testing on all Laundry Units repaired under the provisions of this SOW shall be accomplished in accordance with TM 09950A-14/1 M/S. Operational Tests are to be conducted on each Laundry Unit upon completion of repairs and prior to the equipment being returned to stock, to insure the unit will perform as required.

3.2.4 Phase IV - Packaging, Handling, Storage and Transportation (PHS&T).

a. The contractor shall be responsible for the preservation and packaging of items being repaired under the terms of this statement of work. Items scheduled for long-term storage or

shipment to overseas destinations shall be in accordance with the Level "A" requirements of MIL-STD-2073-1D, Method 10. Items being scheduled for domestic shipment, immediate use or short-term storage shall be to Level "B" requirements.

b. Marking for shipment and storage shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the contractor with the shipping address(es) for delivery of the repaired equipment. The contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for the transportation costs associated with shipping the subject equipment to and from the Contractor.

3.3 Configuration Management

3.3.1 Configuration Status Accounting (CSA).

a. The Contractor shall record and submit data on retrofit accomplished during Phase II. Any approved Modification Instructions (MIs) or Engineering Change Proposals (ECP's) not previously applied shall be applied during Phase II of the IROAN process.

b. The Contractor shall determine the application status of approved configuration changes by visual inspections to the extent possible. The government will identify the configuration changes to be inspected by furnishing a Configuration Inspection Checklist to the Contractor. The Contractor shall use one checklist per Laundry Unit to record their inspection findings along with other required data.

c. The Contractor shall record serial numbers of the assemblies listed on the Configuration Inspection Checklist. The Contractor shall record the information on the same form that was used to record the application status of configuration changes.

3.3.2 Configuration Control. The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the contractor shall prepare and submit a Request For Deviation. MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing this configuration control document.

3.4 Quality Assurance Provisions. The Contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9002-1994, Quality Systems - Model for Quality Assurance in Production, Installation, and Servicing. The program shall ensure quality throughout all areas to include processing, assembly, inspection, test, maintenance, and preparation for delivery and shipping. Unless otherwise specified in the contract, the Contractor shall be responsible for performance of all inspection requirements. The Government, MCSC (Code CSLE), Albany, Georgia, reserves the right to perform any of the inspections set forth in the contract where such inspections are deemed necessary to assure

products and services conform to the prescribed requirements. The Contractor shall provide an Inspection and Test Plan.

3.5 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). The Management Control Activity (MCA/Code 573-2) will coordinate Government Furnished Equipment/Government Furnished Materiel (GFE)/(GFM) requests and maintain a central control system on all government owned assets in the contractor's possession. The MCA will forward a GFE Accountability Agreement to the contractor for signature on an annual basis to establish a chain of custody and identify property responsibilities for Marine Corps assets. The contractor is to acknowledge receipt of GFM to the MCA within 15 days of receipt. (This can be done by mailing (Materiel Management Department, Management Control Activity (Code 573-2) 814 Radford Blvd, STE 20320, Albany, GA 31704-0320) or faxing (commercial 229-639-5498 or DSN 567-5498) a copy of the DD1348).

3.6 Contractor Furnished Materiel (CFM). The contractor may requisition materiel as required in the performance of the SOW through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP) Chapter 11 provides guidance to contractors on the requisitioning process. The contractor's decision to utilize CFM procured from the DoD Supply System shall be based upon cost effectiveness, availability of materiel and the required completion/delivery date.

3.7 Acceptance. The performance of the Contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and MCSC (Code CSLE), Albany, Georgia, representatives shall be permitted to observe the work or to conduct inspection at all reasonable hours. Final inspection and acceptance testing shall be conducted at the Contractor's facility. Final acceptance shall be conducted on 100 percent of items to verify that the units meet all requirements.

3.8 Rejection. Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCSC (Code CSLE), Albany, representative. The Contractor shall, at no additional cost to MCSC, Albany, Georgia, provide the following:

a. Develop an approach for modification or correction of all deficiencies.

b. Upon approval of a documented approach, the Contractor shall correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures is demonstrated.

4.0 REPORTS. All report deliverables shall be submitted in hard copy to Commander (Code CSLE), Marine Corps Systems Command, 814 Radford Blvd., Suite 20343, Albany, Georgia 31704-0343, unless directed other wise in a Contract Data Requirements List.

4.1 Repairable Item Inspection Report. The Contractor shall provide a Repairable Item Inspection Report for each Laundry Unit. The report shall be identified by United States Marine Corps Serial Number.

4.2 Monthly Progress Reports. The Contractor shall provide Monthly Progress Reports summarizing the progress and status of the IROAN Program.

4.3 Pre-Induction Checklist. The Contractor shall complete the Pre-Induction Inspection Checklist for each Laundry Unit repaired. These documents shall be available during final acceptance testing. One copy of each document shall be provided to MCSC, Albany, Georgia, Code CSLE, after final acceptance of the Laundry Unit.

a. The inspection checklist shall contain, but not be limited to the following:

(1) Laundry Unit serial number. Appendix A
(2) Condition Code of Laundry Unit at receipt. Appendix A
(3) Results of operational test. Appendix A
(4) List of defective parts and assemblies. Appendix B
(5) List of repair parts and assemblies required for repairs. Appendix C
(6) Corrosion prevention methods that shall be used. Appendix A

COMPONENTS PASS FAIL REMARKS

Serial number:_____ Condition Code at receipt: _____
Results of operational test:

_____
_____
_____
_____
_____
_____
_____
_____
_____

List of defective parts and assemblies. Appendix B
List of repair parts and assemblies required for repairs. Appendix C
Corrosion prevention methods that shall be used.

_____
_____
_____
_____
_____
_____
_____

Inspect all components for operating/malfunction/defective parts per TM 09950A-14/1 M/S. Visually check components for leaks, damage, loose parts & hardware. No disassembly of components is allowed unless the component is determined to be defective.

COMPONENTS	PASS	FAIL	REMARKS
LAUNDRY FACILITY BARE BASE	____	____	_____
MAIN PLATFORM ASSEMBLY,	____	____	_____
(SEE FIGURE 7-2)	____	____	_____
STORAGE BIN ASSEMBLY,	____	____	_____
(SEE FIGURE 7-3)	____	____	_____
LAUNDRY WASHER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-4)	____	____	_____
LAUNDRY WASHER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-7)	____	____	_____
CLAMP ASSEMBLY,	____	____	_____
(SEE FIGURE 7-13)	____	____	_____
COUPLINGS	____	____	_____
COUPLING HALF, QUICK	____	____	_____
DISCONNECT,	____	____	_____
CAM-LOCKINC ALL ENDS	____	____	_____
PLUG, SQ HD,	____	____	_____
ELBOW, ST BRASS	____	____	_____
BUSHING, BRASS,	____	____	_____
COMPRESSOR UNIT,	____	____	_____
RECIPROCATING,	____	____	_____
(SEE FIGURE 7-14)	____	____	_____
CONTROLLER AND	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
ELECTRICAL PANEL,	____	____	_____
(SEE FIGURE 7-16)	____	____	_____
WATER HEATER,	____	____	_____
(SEE FIGURE 7-22)	____	____	_____
HEATER FUEL LINE ASSEMBLY,	____	____	_____
(SEE FIGURE 7-23)	____	____	_____
HEATER TIEDOWN ASSEMBLY,	____	____	_____
(SEE FIGURE 7-24)	____	____	_____
LAUNDRY EXTRACTOR,	____	____	_____
(SEE FIGURE 7-25)	____	____	_____
TIE DOWN CLIP ASSEMBLY,	____	____	_____
(SEE FIGURE 7-30)	____	____	_____
WATER PUMP ASSEMBLY,	____	____	_____
(SEE FIGURE 7-31)	____	____	_____
HOSE CONNECT ASSEMBLY,	____	____	_____
(SEE FIGURE 7-32)	____	____	_____
PUMP TIEDOWN ASSEMBLY,	____	____	_____
(SEE FIGURE 7-33)	____	____	_____
DRYER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-34)	____	____	_____
DRYER FUEL LINE ASSEMBLY,	____	____	_____
(SEE FIGURE 7-23)	____	____	_____
EXHAUST HOSE	____	____	_____
TIEDOWN ASSEMBLY,	____	____	_____
(SEE FIGURE 7-45)	____	____	_____
EXHAUST HOSE	____	____	_____
TIEDOWN ASSEMBLY,	____	____	_____
(SEF, FIGURE 7-46)	____	____	_____
CONDUIT ASSEMBLY,	____	____	_____
(SEE FIGURE 7-47)	____	____	_____
RAIL, SIDE, 84 IN LG	____	____	_____
CLOTHES BIN ASSEMBLY,	____	____	_____
(SEF, FIGURE 7-48)	____	____	_____
POWER CABLE ASSEMBLY,	____	____	_____
(SEE FIGURE, 7-49)	____	____	_____
SPACER	____	____	_____
COVER ASSEMBLY RED 1, 2, & 3	____	____	_____
MAIN PLATFORM ASSEMBLY	____	____	_____
PLATFORM, LEFT ASSEMBLY	____	____	_____
PLATFORM, FRAME ASSEMBLY	____	____	_____
DECK, LARGE TOP ASSEMBLY	____	____	_____
DECK, SMALL TOP ASSEMBLY	____	____	_____
DECK, LARGE BOTTOM	____	____	_____
ASSEMBLY	____	____	_____
DECK, SMALL BOTTOM	____	____	_____
ASSEMBLY	____	____	_____
RAIL	____	____	_____
RAIL, SIDE	____	____	_____
SLEEVE	____	____	_____
STRAP, RETAINING,	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
PLATFORM, RIGHT ASSEMBLY	____	____	_____
JOINING PANEL ASSEMBLY	____	____	_____
STORAGE BIN ASSEMBLY	____	____	_____
BIN, LARGE	____	____	_____
PLATFORM	____	____	_____
BIN, SMALL	____	____	_____
COVER ASSEMBLY	____	____	_____
FASTENER, LINK LOCK	____	____	_____
TRAY	____	____	_____
LAUNDRY WASHER	____	____	_____
WASHER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-5)	____	____	_____
PLATE, TANK MOUNTING	____	____	_____
ELBOW, PIPE,	____	____	_____
TEE, PIPE, STL,	____	____	_____
COCK, DRAIN,	____	____	_____
WASHER ASSEMBLY, OPEN END	____	____	_____
COVER, BASE SIDE LEFT	____	____	_____
COVER, BASE FRONT	____	____	_____
COVER, BASE SIDE RIGHT	____	____	_____
SUPPLY INJECTOR ASSEMBLY	____	____	_____
SHELL ASSEMBLY	____	____	_____
SHELL FRONT ASSEMBLY	____	____	_____
SHELL, EXTRUSION	____	____	_____
RING, SHELL	____	____	_____
PLATE, MOUNTING	____	____	_____
MICROSWITCH	____	____	_____
CAM, DOOR	____	____	_____
HANDLE ASSEMBLY,	____	____	_____
DOOR, ASSEMBLY	____	____	_____
BRACKET, HINGE	____	____	_____
CYLINDER ASSEMBLY	____	____	_____
HOUSING, SHAFT SEAL	____	____	_____
GASKET, SHAFT SEAL	____	____	_____
SEAL, PLAIN, STL,	____	____	_____
COVER, SHAFT RETAINER	____	____	_____
SPACER, SHAFT RETAINER	____	____	_____
KEY, MACHINE, STL	____	____	_____
SPIDER,	____	____	_____
GEAR ASSEMBLY,	____	____	_____
SPEED DECREASER	____	____	_____
MOTOR, ALTERNATING	____	____	_____
MOUNT, MOTOR	____	____	_____
BRACKET, MOTOR MOUNT, LEFT	____	____	_____
BRACKET, MOTOR MOUNT, RIGHT	____	____	_____
BELT GUARD ASSEMBLY	____	____	_____
BRACKET, BELT UPPER	____	____	_____
BELT, V, RBR,	____	____	_____
BRACKET, BELT, LOWER LEFT	____	____	_____
PULLEY, GROOVE,	____	____	_____
BUSHING, SLEEVE	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
V-PULLEY	____	____	_____
BUSHING, SLEEVE	____	____	_____
COVER, SYPHON	____	____	_____
BREAKER	____	____	_____
PIPE, ELBOW	____	____	_____
WATER LEVEL FLOAT,	____	____	_____
CHAMBER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-6)	____	____	_____
SOAP CHUTE	____	____	_____
COVER, SOAP CHUTE	____	____	_____
HINGE, SOAP CHUTE	____	____	_____
ROD, SOAP CHUTE	____	____	_____
PIPE, METALLIC	____	____	_____
HOSE, NONMETALLIC,	____	____	_____
PIPE, WATER INLET	____	____	_____
VALVE, ANGLE,	____	____	_____
WATER LEVEL FLOAT	____	____	_____
CHAMBER ASSEMBLY	____	____	_____
SWITCH, LIQUID LEVEL	____	____	_____
TUBING, GLASS,	____	____	_____
CLAMP, LOOP	____	____	_____
BRACKET, LEVEL CONTROL	____	____	_____
BRACKET, TOP FLOAT	____	____	_____
CHAMBER	____	____	_____
BRACKET, BOTTOM	____	____	_____
FLOAT CHAMBER	____	____	_____
FLOAT ASSEMBLY,	____	____	_____
LIQUID LEVEL	____	____	_____
FLOAT	____	____	_____
ROD, FLOAT,	____	____	_____
SPFED NUT	____	____	_____
LAUNDRY WASHER ASSEMBLY	____	____	_____
FRAME ASSEMBLY	____	____	_____
DOOR ASSEMBLY,	____	____	_____
(SEE FIGURE 7-8)	____	____	_____
DOOR LOCK ASSEMBLY,	____	____	_____
(SEE FIGURE 7-9)	____	____	_____
DRAW BAND, WASHER	____	____	_____
EXTRACTOR	____	____	_____
GASKET, RBR CHLOROPRENE	____	____	_____
DRUM FRONT	____	____	_____
CYLINDER ASSEMBLY	____	____	_____
SPIDER AND SHAFT ASSEMBLY	____	____	_____
ROD, THREADED END	____	____	_____
RING, GASKET CLAMP	____	____	_____
GASKET, SOCK	____	____	_____
MOTOR	____	____	_____
PLATE, MOTOR MOUNTING	____	____	_____
ROD, MOTOR ADJUSTING	____	____	_____
BELT	____	____	_____
PULLEY, GROOVE,	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
BUSHING, SHEAVE	____	____	_____
DRUM ASSEMBLY	____	____	_____
WATER INLET ASSEMBLY,	____	____	_____
(SEE FIGURE 7-10)	____	____	_____
SHEAVE	____	____	_____
BUSHING, SHEAVE	____	____	_____
GEAR ASSEMBLY,	____	____	_____
PLATE, MOUNTING	____	____	_____
SEAL AND CARRIAGE ASSEMBLY,	____	____	_____
SEAL, PLAIN	____	____	_____
DISPENSER ASSEMBLY,	____	____	_____
(SEE FIGURE 7-11)	____	____	_____
GAUGE, TEMPERATURE	____	____	_____
BOTTLE, SUPPLY	____	____	_____
VALVE ASSEMBLY, DRAIN,	____	____	_____
(SEE FIGURE 7-12)	____	____	_____
PLUG, PIPE	____	____	_____
HOSE, DRAIN	____	____	_____
DOOR ASSEMBLY	____	____	_____
DOOR HINGE AND	____	____	_____
HANDLE	____	____	_____
BASE, DOOR HINGE	____	____	_____
BUSHING, FLANGE,	____	____	_____
PIN, DOOR HINGE	____	____	_____
BEARING, WASHER,	____	____	_____
BAR, DOOR	____	____	_____
FASTENER, PAWL	____	____	_____
BOLT, PIVOT	____	____	_____
BUSHING, SLEEVE	____	____	_____
RING, RETAINING	____	____	_____
WINDOW, OBSERVATION, GLASS,	____	____	_____
GASKET, DOOR GLASS	____	____	_____
FRAME, DOOR	____	____	_____
DRAW BAND, DOOR	____	____	_____
GASKET, DRAW BAND	____	____	_____
GASKET, DOOR	____	____	_____
DOOR LOCK ASSEMBLY	____	____	_____
DOOR LOCK COVER AND SWITCH	____	____	_____
COVER, DOOR LOCK	____	____	_____
SWITCH, PUSH	____	____	_____
BOOT, DUST AND MOISTURE	____	____	_____
SEAL	____	____	_____
BRACKET, MOUNTING	____	____	_____
BUSHING, ELECTRICAL	____	____	_____
CONDUCTOR,	____	____	_____
SOLENOID,	____	____	_____
SWITCH,	____	____	_____
PLATE, DOOR LOCK	____	____	_____
SPRING, DOOR LOCK	____	____	_____
BAR, DOOR LOCK	____	____	_____
SPRING, DOOR LATCH	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
WATER INLET ASSEMBLY	___	___	_____
LEVER, MANUAL CONTROL	___	___	_____
CLEVIS, ROD END,	___	___	_____
CYLINDER ASSEMBLY,	___	___	_____
ROD, ADJUSTINC STUD	___	___	_____
BRACKET, MOUNTING	___	___	_____
COUPLER, FEMALE	___	___	_____
COUPLING HALF, QUICK	___	___	_____
DISCONNECT,	___	___	_____
ELBOW, PIPE,	___	___	_____
NIPPLE, PIPE,	___	___	_____
PIPE, METALLIC,	___	___	_____
ELBOW, PIPE TO HOSE,	___	___	_____
ELBOW, PIPE,	___	___	_____
BUSHING, PIPE	___	___	_____
TEE, PIPE	___	___	_____
VALVE, BALL,	___	___	_____
NIPPLE, PIPE,	___	___	_____
DISPENSER ASSEMBLY	___	___	_____
DISPENSER	___	___	_____
COVER	___	___	_____
HOSE, SUPPLY1	___	___	_____
SUPPLY HOSE, AIR	___	___	_____
HOSE, SUPPLY 2	___	___	_____
HOSE, SUPPLY 3	___	___	_____
HOSE, SUPPLY 4	___	___	_____
FITTING, HOSE	___	___	_____
COUPLING, PIPE,	___	___	_____
HOSE, SUPPLY INLET	___	___	_____
ADAPTER, STRAIGHT	___	___	_____
VALVE, SOLENOID,	___	___	_____
MANIFOLD, SUPPLY	___	___	_____
BRACKET, MANIFOLD	___	___	_____
MOUNTING	___	___	_____
DRAIN VALVE ASSEMBLY	___	___	_____
PLATE, TOP	___	___	_____
BELLOWS, RUBBER,	___	___	_____
ADAPTER, STRAIGHT,	___	___	_____
PLATE, MOUNTING	___	___	_____
BRACKET	___	___	_____
HOSE, NONMETALLIC,	___	___	_____
PINCH TUBE	___	___	_____
CLAMP ASSEMBLY	___	___	_____
ANGLE	___	___	_____
ROD, THREADED, SHORT	___	___	_____
RING, HANGER	___	___	_____
AIR COMPRESSOR ASSEMBLY	___	___	_____
GRILLE, METAL	___	___	_____
HANDLE, DOOR, L STYLE	___	___	_____
KIT, SWITCH, (SEE FIGURE 7-15)	___	___	_____
HOUSING, AIR COMPRESSOR	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
CYLINDER, HEAD ASSEMBLY,	___	___	_____
RIGHT HAND	___	___	_____
CYLINDER HEAD ASSEMBLY,	___	___	_____
LEFT HAND	___	___	_____
MOTOR, ALTERNATING	___	___	_____
CABLE ASSEMBLY,	___	___	_____
PRESSURE SWITCH ASSEMBLY	___	___	_____
SWITCH, PRESSURE	___	___	_____
PLUG, BUTTON	___	___	_____
WIRE ASSEMBLY, BLK	___	___	_____
WIRE ASSEMBLY, WHT	___	___	_____
CONTROLLER AND	___	___	_____
ELECTRICAL PANEL SUPPORT	___	___	_____
FRAME ASSEMBLY	___	___	_____
FACE PLATE, LAUNDRY,	___	___	_____
COVER, CONTROLLER	___	___	_____
CONTROLLER ASSEMBLY	___	___	_____
HEAD ASSEMBLY,	___	___	_____
CONTROL BOX, (SEE FIGURE 7-17)	___	___	_____
CONTROL BOX ASSEMBLY,	___	___	_____
(SEE FIGURE 7-18)	___	___	_____
CONTROL CHASIS	___	___	_____
ASSEMBLY, LAUNDRY,	___	___	_____
(SEE FIGURE 7-19)	___	___	_____
HOSE, LOW PRESSURE	___	___	_____
ADAPTER, STRAIGHT	___	___	_____
SLEEVE	___	___	_____
FIRE EXTINGUISHER	___	___	_____
PLATE, MOUNTING	___	___	_____
STAND, CONTROLLER SUPPORT	___	___	_____
LOAD CENTER	___	___	_____
ENCLOSURE	___	___	_____
BRACKET, INTERIOR MOUNT	___	___	_____
KIT, INTERIOR TRIM	___	___	_____
CAP, END SEAL	___	___	_____
MAIN BREAKER, 30 AMP	___	___	_____
CIRCUIT BREAKER, 20 AMP	___	___	_____
BOX, 3 GANG	___	___	_____
GASKET, SYNTH-RBR,	___	___	_____
CONNECTOR, RECEPTACLE	___	___	_____
OUTLET	___	___	_____
COVER, CONDUIT	___	___	_____
COVER, LIFT	___	___	_____
SWITCH, MOTOR STARTING	___	___	_____
HEAD ASSEMBLY	___	___	_____
WINDOW, OBSERVATION,	___	___	_____
LATCH, SPECIAL	___	___	_____
LAMP, 28V	___	___	_____
SOCKET, LAMP	___	___	_____
NAME PLATE	___	___	_____
WARNING	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
NAME PLATE,	___	___	_____
TUBING,	___	___	_____
TYRAP,	___	___	_____
BRACKET, RECEPTACLE	___	___	_____
RECEPTACLE	___	___	_____
ANGLE, CENTER	___	___	_____
DOOR ASSEMBLY, PLASTIC	___	___	_____
WET PART, LAUNDRY	___	___	_____
PARTITION, SWITCH	___	___	_____
SKIRT, TIMING, LAUNDRY	___	___	_____
REAR ASSEMBLY	___	___	_____
BACK	___	___	_____
POWER SUPPLY	___	___	_____
VALVE, SOLENOID,	___	___	_____
STRAINER, SEDIMENT,	___	___	_____
NIPPLE, PIPE,	___	___	_____
ANGLE	___	___	_____
PLUG, PIPE	___	___	_____
BLOCK, MANIFOLD,	___	___	_____
CONTROL CHASIS ASSEMBLY	___	___	_____
CONTROL PANEL ASSEMBLY,	___	___	_____
(SEE FIGURE 7-20)	___	___	_____
FUSE, CARTRIDGE,	___	___	_____
FUSEHOLDER,	___	___	_____
VALVE, SOLENOID,	___	___	_____
VALVE, AIR CONTROL, 3 WAY	___	___	_____
RELAY, 3PDT, IO AMP	___	___	_____
SWITCH, PRESSURE	___	___	_____
RELAY,	___	___	_____
TIMING MOVEMENT,	___	___	_____
MECHANICAL,	___	___	_____
(SEE FIGURE 7-21)	___	___	_____
CONTROL PANEL ASSEMBLY	___	___	_____
PANEL, CONTROL	___	___	_____
TIMER, SEQUENTIAL	___	___	_____
SWITCH, TOGGLE,	___	___	_____
COVER, SWITCH	___	___	_____
REVERSING TIMER ASSEMBLY	___	___	_____
SHAFT, SHOULDERED,	___	___	_____
SWITCH, SENSITIVE,	___	___	_____
ADAPTER, SWITCH	___	___	_____
CAM, CONTROL	___	___	_____
SETSCREW,	___	___	_____
BRACKET, TIMER	___	___	_____
LAUNDRY EXTRACTOR	___	___	_____
ASSEMBLY	___	___	_____
EXTRACTOR, BOCK MOISTRITE	___	___	_____
AND SPEEDRY	___	___	_____
MOTOR ASSEMBLY,	___	___	_____
(SEE FIGURE 7-26)	___	___	_____
MOTOR ASSEMBLY,	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
(SEE FIGURE 7-27)	___	___	_____
SHEAVE, PULLEY	___	___	_____
V-BELT	___	___	_____
LID	___	___	_____
FRAME, LID HINCE	___	___	_____
BASKET BALL	___	___	_____
LID GASKET	___	___	_____
CURB ASSEMBLY	___	___	_____
WASHER, LEAD	___	___	_____
RUBBER WASHER	___	___	_____
HOSE,	___	___	_____
BASKET ASSEMBLY	___	___	_____
POST, CENTER	___	___	_____
SEAL,	___	___	_____
CENTER UNIT ASSEMBLY,	___	___	_____
(SEE FIGURE 7-28)	___	___	_____
HUB, BRAKE	___	___	_____
BACK PANEL ASSEMBLY,	___	___	_____
(SEE FIGURE 7,29)	___	___	_____
BASE ASSEMBLY	___	___	_____
TRUNNION FRAME, ASSEMBLY	___	___	_____
COUPLING HALF,	___	___	_____
MOTOR ASSEMBLY #1	___	___	_____
MOTOR, 3 HP	___	___	_____
SWITCH,	___	___	_____
MOUNT, SWITCH	___	___	_____
COUPLING	___	___	_____
HUB, BODY,	___	___	_____
PLATE, MOTOR MOUNT	___	___	_____
MOTOR ASSEMBLY #2	___	___	_____
MOTOR	___	___	_____
HUB, PULLEY	___	___	_____
PLATE, MOTOR MOUNT	___	___	_____
CENTER UNIT ASSEMBLY	___	___	_____
PIN, STUD	___	___	_____
ARM, BRAKE	___	___	_____
ARM, OPERATING	___	___	_____
BRACKET	___	___	_____
SPRING, HELICAL, EXTENSION	___	___	_____
BRAKE SHOE,	___	___	_____
COVER, TOP END	___	___	_____
SHIELD, SOLENOID	___	___	_____
ROD, SOLENOID	___	___	_____
SOLENOID, BRAKE	___	___	_____
HUB	___	___	_____
BALL, BASKET	___	___	_____
INSERT, NYLON	___	___	_____
PACKING,	___	___	_____
CAP, BUMPER	___	___	_____
BUMPER RUBBERS	___	___	_____
CAP, TRUNNION	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
RUBBER, TRUNNION	___	___	_____
HUB, PULLEY	___	___	_____
SHEAVES, PULLEY	___	___	_____
BACK PANEL ASSEMBLY	___	___	_____
BUTTON, START	___	___	_____
SWITCH, PUSH-PULL,	___	___	_____
BUTTON, RED	___	___	_____
LIGHT, INDICATOR	___	___	_____
MICROSWITCH	___	___	_____
SOLENOID,	___	___	_____
RELAY, ELECTRO MAGNETIC	___	___	_____
TIMER,	___	___	_____
FUSE HOLDER	___	___	_____
FUSE, CARTRIDGE,	___	___	_____
TERMINAL BOARD	___	___	_____
COVER	___	___	_____
PLATE, BOTTOM	___	___	_____
BACK AND SIDES, CONTROL	___	___	_____
PANEL	___	___	_____
PLATE, MOUNT	___	___	_____
PLATE, TOP	___	___	_____
TIE DOWN CLIP ASSEMBLY	___	___	_____
BAR, TIE DOWN CLIP	___	___	_____
LEG, TIE DOWN CLIP	___	___	_____
PLATFORMS	___	___	_____
WATER PUMP ASSEMBLY	___	___	_____
WATER PUMP ASSEMBLY	___	___	_____
FRAME, AL-ALY	___	___	_____
SWITCH BOX ASSEMBLY	___	___	_____
COVERS	___	___	_____
COVER, BOX, FRONT	___	___	_____
PUMP UNIT	___	___	_____
BRACKET	___	___	_____
MOTOR, ALTERNATING	___	___	_____
CAP,	___	___	_____
COUPLING HALF,	___	___	_____
NIPPLE, PIPE	___	___	_____
HOSE CONNECTION ASSEMBLY	___	___	_____
SUCTION STRAINER ASSEMBLY	___	___	_____
COUPLING, QUICK DISCONNECT	___	___	_____
SUCTION HOSE ASSEMBLY	___	___	_____
COUPLING, HALF	___	___	_____
HEATER INTAKE HOSE	___	___	_____
ASSEMBLY	___	___	_____
WASHER, INTAKE HOSE	___	___	_____
ASSEMBLY	___	___	_____
HOSES, WATER,	___	___	_____
CLOTHES BIN DISCHARGE HOSE	___	___	_____
EXTRACTOR DISCHARGE HOSE	___	___	_____
ASSEMBLY	___	___	_____
PUMP TIE DOWN ASSEMBLY	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
CATCH, FIXED ASSEMBLY	___	___	_____
CATCH, ADJUSTABLE	___	___	_____
PLATFORM ASSEMBLY	___	___	_____
DRYER ASSEMBLY	___	___	_____
BLOWER ASSEMBLY,	___	___	_____
(SEE FIGURE 7-35)	___	___	_____
HOSE ASSEMBLIES	___	___	_____
BURNER TUMBLER ASSEMBLY,	___	___	_____
(SEE FIGURE 7-36)	___	___	_____
SWITCHES, SENSITIVE	___	___	_____
COVER	___	___	_____
LIGHT, INDICATOR,	___	___	_____
ALARM, BUZZER	___	___	_____
BUZZER,	___	___	_____
DOOR ASSEMBLY	___	___	_____
CHAIN, WELDLESS	___	___	_____
TIMER, SEQUENTIAL	___	___	_____
PLATE, INDENT	___	___	_____
LABEL, CAUTION	___	___	_____
LABEL, WARNING	___	___	_____
ARROW	___	___	_____
HANDLE, DOOR	___	___	_____
RING ASSEMBLY	___	___	_____
FRONT SHELL ASSEMBLY,	___	___	_____
(SEE FIGURE 7-39)	___	___	_____
HEATER TUMBLER ASSEMBLY,	___	___	_____
(SEE FIGURE 7-40)	___	___	_____
HOSE, AIR DUCT,	___	___	_____
HOSE, FLEX	___	___	_____
EXHAUST HOSE ADAPTER	___	___	_____
ASSEMBLY	___	___	_____
DUCT, HOSE,	___	___	_____
REDUCER, PIPE,	___	___	_____
ELBOW, AIR CONDITIONING	___	___	_____
HEATING	___	___	_____
PIN ASSEMBLY	___	___	_____
PIN	___	___	_____
CHAIN, SAFETY	___	___	_____
HOOK, CHAIN,	___	___	_____
THERMOMETER	___	___	_____
DISCHARGE SPOUT ASSEMBLY	___	___	_____
COUPLING, HALF	___	___	_____
CONTROL, TEMPERATURE, DIAL	___	___	_____
AND KNOB	___	___	_____
CONNECTOR, ELBOW,	___	___	_____
BOX CONNECTOR,	___	___	_____
FAN ASSEMBLY, (SEE FIGURE 7-	___	___	_____
41)	___	___	_____
COVER	___	___	_____
CONTROL PANEL ASSEMBLY,	___	___	_____
(SEE FIGURE 7-42)	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
TUMBLER SPEED REDUCER	___	___	_____
ASSEMBLY,	___	___	_____
(SEE FIGURE 7-43)	___	___	_____
ROD, THREADED	___	___	_____
CUP, GREASE,	___	___	_____
CUP OIL,	___	___	_____
PLATES, RETAINING,	___	___	_____
GUARD	___	___	_____
CHAIN, STL, 65 LINKS	___	___	_____
WIRE, SAFETY	___	___	_____
TUMBLER ASSEMBLY,	___	___	_____
(SEE, FIGURE 7-44)	___	___	_____
SHELL ASSEMBLY	___	___	_____
TUMBLER BASE ASSEMBLY	___	___	_____
PANEL, SIDE	___	___	_____
INSULATOR, PLATE,	___	___	_____
STRIP	___	___	_____
BLOWER ASSEMBLY	___	___	_____
GUAGE, PRESSURE	___	___	_____
COCK, DRAIN	___	___	_____
TEE	___	___	_____
NIPPLE	___	___	_____
PUMP, FUEL	___	___	_____
SHUTTER ASSEMBLY,	___	___	_____
HOUSING	___	___	_____
HOUSING, BLOWER	___	___	_____
WHEEL, BLOWER	___	___	_____
MOUNT, BLOWER	___	___	_____
KEY	___	___	_____
MOTOR, ALTERNATING	___	___	_____
BURNER TUMBLER ASSEMBLY	___	___	_____
CAP FITTING	___	___	_____
GASKET, PEEP SIGHT,	___	___	_____
GLASS, PEEP HOLE	___	___	_____
NIPPLE	___	___	_____
COVER	___	___	_____
CABLE AND TERMINAL	___	___	_____
ASSEMBLY,	___	___	_____
(SEE FIGURE 7-37)	___	___	_____
ELECTRODE ASSEMBLY,	___	___	_____
(SEE FIGURE 7-38)	___	___	_____
BRACKET, TRANSFORMER	___	___	_____
TRANSFORMER	___	___	_____
BOX, JUNCTION	___	___	_____
COVER	___	___	_____
BOX CONNECTORS,	___	___	_____
CONNECTOR, STRAIGHT	___	___	_____
AIR PLENUM	___	___	_____
CABLE AND TERMINAL	___	___	_____
ASSEMBLY	___	___	_____
CABLE	___	___	_____

COMPONENTS	PASS	FAIL	REMARKS
TERMINAL, LUG,	____	____	_____
ELECTRODE ASSEMBLY	____	____	_____
ELECTRODE	____	____	_____
NOZZLE ASSEMBLY	____	____	_____
NOZZLE	____	____	_____
PIPE	____	____	_____
BASE, BURNER	____	____	_____
FRONT SHELL ASSEMBLY	____	____	_____
DOOR	____	____	_____
HINGE ASSEMBLY	____	____	_____
HINGE	____	____	_____
PIN, SPRING	____	____	_____
FRONT, SHELL	____	____	_____
HEATER TUMBLER ASSEMBLY	____	____	_____
SCREEN ASSEMBLY,	____	____	_____
PANEL, COVER	____	____	_____
HOOD ASSEMBLY	____	____	_____
HOOD	____	____	_____
PLATE	____	____	_____
COVER, FRONT	____	____	_____
COVER, REAR	____	____	_____
BURNER MOUNTING ASSEMBLY	____	____	_____
RETURN BOX NO 5 ASSEMBLY	____	____	_____
COVER, ASSEMBLY	____	____	_____
RETURN BOX NO 3 ASSEMBLY	____	____	_____
RETURN BOX NO 1 ASSEMBLY	____	____	_____
RETURN BOX NO 4 ASSEMBLY	____	____	_____
RETURN BOX NO 2 ASSEMBLY	____	____	_____
MOUNTING PLATE ASSEMBLY	____	____	_____
FAN ASSEMBLY	____	____	_____
FAN	____	____	_____
MOTOR, ALTERNATING,	____	____	_____
ARROW	____	____	_____
COVER, WELDMENT	____	____	_____
CONTROL PANEL ASSEMBLY	____	____	_____
STARTER, MANUAL	____	____	_____
PANEL ASSEMBLY	____	____	_____
CONTROL, FLAME	____	____	_____
PROGRAM TIME CARD,	____	____	_____
TERMINAL BOX, 12 SGL	____	____	_____
RELAY	____	____	_____
BASE, RELAY,	____	____	_____
SHIELD ASSEMBLY	____	____	_____
MOTOR, STARTER	____	____	_____
HEATER ELEMENT,	____	____	_____
TUMBLER SPEED REDUCER ASSEMBLY	____	____	_____
MOTOR, ALTERNATING	____	____	_____
MOUNTING BRACKET ASSEMBLY	____	____	_____
BASE ASSEMBLY	____	____	_____
TUMBLER ASSEMBLY	____	____	_____

COMPONENTS	PASS	FAIL	REMARKS
TIE ROD	____	____	_____
RIB, TUMBLER,	____	____	_____
SPIDER ASSEMBLY	____	____	_____
TUMBLER, CLOTHES DRYER	____	____	_____
EXHAUST TIE DOWN	____	____	_____
ASSEMBLY#1	____	____	_____
LEG	____	____	_____
STRAP, WEBBING,	____	____	_____
LOOP	____	____	_____
THREAD	____	____	_____
EXHAUST TIE DOWN	____	____	_____
ASSEMBLY#2	____	____	_____
LEG	____	____	_____
STRAP	____	____	_____
LOOP	____	____	_____
THREAD	____	____	_____
CONDUIT ASSEMBLY	____	____	_____
GROUND ROD, SECTION	____	____	_____
CONNECTOR, GROUND ROD	____	____	_____
WIRE, #8 STRANDED	____	____	_____
CONDUIT OUTLET	____	____	_____
COVER	____	____	_____
COVER, BLANK	____	____	_____
BODY, CONNECTOR	____	____	_____
COVER, CONNECTER	____	____	_____
PLUG, NYLON	____	____	_____
PLUG, COVER	____	____	_____
CONNECTOR	____	____	_____
BOX, TWO GANG	____	____	_____
BOX CONNECTOR,	____	____	_____
CLOTHES BIN ASSEMBLY	____	____	_____
HANDLE, SHORT	____	____	_____
HANDLE, LONG	____	____	_____
SIDE	____	____	_____
BASE	____	____	_____
COUPLING	____	____	_____
STAND, CLOTHES BIN	____	____	_____
CASTOR	____	____	_____
PLATFORM	____	____	_____
POWER CABLE ASSEMBLY	____	____	_____
BODY	____	____	_____
SHIELD, ELECTRICAL	____	____	_____
CABLE	____	____	_____

COMPONENTS: REMARKS:

LAUNDRY FACILITY BARE BASE
MAIN PLATFORM ASSEMBLY,
(SEE FIGURE 7 2)
STORAGE BIN ASSEMBLY,
(SEE FIGURE 7 3)
LAUNDRY WASHER ASSEMBLY,
(SEE FIGURE 7-4)
LAUNDRY WASHER ASSEMBLY,
(SEE FIGURE 7 7)
CLAMP ASSEMBLY,
(SEE FIGURE 7-13)
COUPLING
COUPLING HALF,
QUICK DISCONNECT,
CAM-LOCKINC ALL ENDS
PLUG, SQ HD,
ELBOW, ST BRASS
BUSHING, BRASS,
COMPRESSOR UNIT,
RECIPROCATING,
(SEE FIGURE 7-14)
CONTROLLER AND
ELECTRICAL PANEL,
(SEE FIGURE 7-16)
WATER HEATER,
(SEE FIGURE 7-22)
HEATER FUEL LINE ASSEMBLY,
(SEE FIGURE 7-23)
HEATER TIEDOWN ASSEMBLY,
(SEE FIGURE 7-24)
LAUNDRY EXTRACTOR,
(SEE FIGURE 7-25)
TIE DOWN CLIP ASSEMBLY,
(SEE FIGURE 7-30)
WATER PUMP ASSEMBLY,
(SEE FIGURE 7-3 1)
HOSE CONNECT ASSEMBLY,
(SEE FIGURE 7 32)
PUMP TIEDOWN ASSEMBLY,
(SEE FIGURE 7 33)
DRYER ASSEMBLY,
(SEE FIGURE 7-34)
DRYER FUEL LINE ASSEMBLY,
(SEE FIGURE 7-23)
EXHAUST HOSE
TIEDOWN ASSEMBLY,
(SEE FIGURE 7-45)
EXHAUST HOSE
TIEDOWN ASSEMBLY,
(SEE, FIGURE 7-46)
CONDUIT ASSEMBLY,
(SEE FIGURE 7-47)

COMPONENTS:	REMARKS:
RAIL, SIDE, 84 IN LG	
CLOTHES BIN ASSEMBLY,	
(SEE, FIGURE 7-49)	
POWER CABLEASSEMBLY,	
(SEE FIGURE, 7 49)	
SPACER	
COVER ASSEMBLY RED 1, 2, & 3	
MAIN PLATFORM ASSEMBLY	
PLATFORM, LEFT ASSEMBLY	
PLATFORM, FRAME ASSEMBLY	
DECK, LARGE TOP ASSEMBLY	
DECK, SMALL TOP ASSEMBLY	
DECK, LARGE BOTTOM ASSEMBLY	
DECK, SMALL BOTTOM ASSEMBLY	
RAIL	
RAIL, SIDE	
SLEEVE	
STRAP, RETAINING,	
PLATFORM, RIGHT ASSEMBLY	
JOINING PANEL ASSEMBLY	
STORAGE BIN ASSEMBLY	
BIN, LARGE	
PLATFORM	
BIN, SMALL	
COVER ASSEMBLY	
FASTENER, LINK LOCK	
TRAY	
LAUNDRY WASHER	
WASHER ASSEMBLY,	
(SEE FIGURE 7-5)	
PLATE, TANK MOUNTING	
ELBOW, PIPE,	
TEE, PIPE, STL,	
COCK, DRAIN,	
WASHER ASSEMBLY, OPEN END	
COVER, BASE SIDE LEFT	
COVER, BASE FRONT	
COVER, BASE SIDE RIGHT	
SUPPLY INJECTOR ASSEMBLY	
SHELL ASSEMBLY	
SHELL FRONT ASSEMBLY	
SHELL, EXTRUSION	
RING, SHELL	
PLATE, MOUNTING	
MICROSWITCH	
CAM, CONTROL	
HANDLE ASSEMBLY	
DOOR, ASSEMBLY	
BRACKET, HINGE	
CYLINDER ASSEMBLY	
HOUSING, SHAFT SEAL	
GASKET, SHAFTSEAL	

COMPONENTS:	REMARKS:
SEAL, PLAIN, STL,	
COVER, SHAFT RETAINER	
SPACER, SHAFT RETAINER	
KEY, MACHINE, STL	
SPIDER,	
GEAR ASSEMBLY,	
SPEED DECREASER	
MOTOR, ALTERNATING	
MOUNT, MOTOR	
BRACKET, MOTOR MOUNT, LEFT	
BRACKET, MOTOR MOUNT, RIGHT	
BELT GUARD ASSEMBLY	
BRACKET, BELT UPPER	
BELT, V, RBR,	
BRACKET, BELT, LOWER LEFT	
PULLEY, GROOVE,	
BUSHING, SLEEVE	
V-PULLEY	
BUSHING, SLEEVE	
COVER, SYPHON	
BREAKER	
PIPE, ELBOW	
WATER LEVEL FLOAT,	
CHAMBER ASSEMBLY,	
(SEE FIC3URE 7-6)	
SOAP CHUTE	
COVER, SOAP CHUTE	
HINGE, SOAP CHUTE	
ROD, SOAP CHUTE	
PIPE, METALLIC	
HOSE, NONMETALLIC,	
PIPE, WATER INLET	
VALVE, ANGLE,	
WATER LEVEL FLOAT	
CHAMBER ASSEMBLY	
SWITCH, LIQUID LEVEL	
TUBING, GLASS,	
CLAMP, LOOP	
BRACKET, LEVEL CONTROL	
BRACKET, TOP FLOAT	
CHAMBER	
BRACKET, BOTTOM	
FLOAT CHAMBER	
FLOAT ASSEMBLY,	
LIQUID LEVEL	
FLOAT	
ROD, FLOAT,	
SPEED NUT	
LAUNDRY WASHER ASSEMBLY	
FRAME ASSEMBLY	
DOOR ASSEMBLY, (SEE FIGURE 7-8)	

COMPONENTS:	REMARKS:
DOOR LOCK ASSEMBLY,	
(SEE FIGURE 7-9)	
DRAW BAND, WASHER	
EXTRACTOR	
GASKET, RBR CHLOROPRENE	
DRUM FRONT	
CYLINDER ASSEMBLY	
SPIDER AND SHAFT ASSEMBLY	
ROD, THREADED END	
RING, GASKET CLAMP	
GASKET, SOCK	
MOTOR	
PLATE, MOTOR MOUNTING	
ROD, MOTOR ADJUSTING	
BELT	
PULLEY, GROOVE,	
BUSHING, SHEAVE	
DRUM ASSEMBLY	
WATER INLET ASSEMBLY,	
(SEE FIGURE 7-10)	
SHEAVE	
BUSHING, SHEAVE	
GEAR ASSEMBLY,	
PLATE, MOUNTING	
SEAL AND CARRIAGE ASSEMBLY,	
SEAL, PLAIN	
DISPENSER ASSEMBLY,	
(SEE FIGURE 7-11)	
GAUGE, TEMPERATURE	
BOTTLE, SUPPLY	
VALVE ASSEMBLY, DRAIN,	
(SEE FIGURE 7-12)	
PLUG, PIPE	
HOSE, DRAIN	
DOOR ASSEMBLY	
DOOR HINGE AND	
HANDLE	
BASE, DOOR HINGE	
BUSHING, FLANGE,	
PIN, DOOR HINGE	
BEARING, WASHER,	
BAR, DOOR	
FASTENER, PAWL	
BOLT, PIVOT	
BUSHING, SLEEVE	
RING, RETAINING	
WINDOW, OBSERVATION, GLASS,	
GASKET, DOOR GLASS	
FRAME, DOOR	
DRAW BAND, DOOR	
GASKET, DRAW BAND	
GASKET, DOOR	

COMPONENTS:	REMARKS:
DOOR LOCK ASSEMBLY	
DOOR LOCK COVER AND SWITCH	
COVER, DOOR LOCK	
SWITCH, PUSH	
BOOT, DUST AND MOISTURE SEAL	
BRACKET, MOUNTING	
BUSHING, ELECTRICAL	
CONDUCTOR,	
SOLENOID,	
SWITCH,	
PLATE, DOOR LOCK	
SPRING, DOOR LOCK	
BAR, DOOR LOCK	
SPRING, DOOR LATCH	
WATER INLET ASSEMBLY	
LEVER, MANUAL CONTROL	
CLEVIS, ROD END,	
CYLINDER ASSEMBLY,	
ROD, ADJUSTINC STUD	
BRACKET, MOUNTING	
COUPLER, FEMALE	
COUPLING HALF, QUICK	
DISCONNECT,	
ELBOW, PIPE,	
NIPPLE, PIPE,	
PIPE, METALLIC,	
ELBOW, PIPE TO HOSE,	
ELBOW, PIPE,	
BUSHING, PIPE	
TEE, PIPE	
VALVE, BALL,	
NIPPLE, PIPE,	
DISPENSER ASSEMBLY	
DISPENSER	
COVER	
HOSE, SUPPLY1	
SUPPLY HOSE, AIR	
HOSE, SUPPLY 2	
HOSE, SUPPLY 3	
HOSE, SUPPLY 4	
FITTING, HOSE	
COUPLING, PIPE,	
HOSE, SUPPLY INLET	
ADAPTER, STRAIGHT	
VALVE, SOLENOID,	
MANIFOLD, SUPPLY	
BRACKET, MANIFOLD	
MOUNTING	
DRAIN VALVE ASSEMBLY	
PLATE, TOP	
BELLOWS, RUBBER,	
ADAPTER, STRAIGHT,	

COMPONENTS:	REMARKS:
PLATE, MOUNTING	
BRACKET	
HOSE, NONMETALLIC,	
PINCH TUBE	
CLAMP ASSEMBLY	
ANGLE	
ROD, THREADED, SHORT	
RING, HANGER	
AIR COMPRESSOR ASSEMBLY	
GRILLE, METAL	
HANDLE, DOOR, L STYLE	
KIT, SWITCH, (SEE FIGURE 7-15)	
HOUSING, AIR COMPRESSOR	
CYLINDER, HEAD ASSEMBLY,	
RIGHT HAND	
CYLINDER HEAD ASSEMBLY,	
LEFT HAND	
MOTOR, ALTERNATING	
CABLE ASSEMBLY,	
PRESSURE SWITCH ASSEMBLY	
SWITCH, PRESSURE	
PLUG, BUTTON	
WIRE ASSEMBLY, BLK	
WIRE ASSEMBLY, WHT	
CONTROLLER AND ELECTRICAL PANELSUPPORT FRAME ASSEMBLY	
FACE PLATE, LAUNDRY,	
COVER, CONTROLLER	
CONTROLLER ASSEMBLY	
HEAD ASSEMBLY,	
CONTROL BOX, (SEE FIGURE 7-17)	
CONTROL BOX ASSEMBLY,	
(SEE FIGURE 7-18)	
CONTROL CHASIS	
ASSEMBLY, LAUNDRY,	
(SEE FIGURE 7-19)	
HOSE, LOW PRESSURE	
ADAPTER, STRAIGHT	
SLEEVE	
FIRE EXTINGUISHER	
PLATE, MOUNTING	
STAND, CONTROLLER SUPPORT	
LOAD CENTER	
ENCLOSURE	
BRACKET, INTERIOR MOUNT	
KIT, INTERIOR TRIM	
CAP, END SEAL	
MAIN BREAKER, 30 AMP	
CIRCUIT BREAKER, 20 AMP	
BOX, 3 GANG	
GASKET, SYNTH-RBR,	

COMPONENTS:	REMARKS:
CONNECTOR, RECEPTACLE	
OUTLET	
COVER, CONDUIT	
COVER, LIFT	
SWITCH, MOTOR STARTING	
HEAD ASSEMBLY	
WINDOW, OBSERVATION,	
LATCH, SPECIAL	
LAMP, 28V	
SOCKET, LAMP	
NAME PLATE	
WARNING	
NAME PLATE,	
TUBING,	
TYRAP,	
BRACKET, RECEPTACLE	
RECEPTACLE	
ANGLE, CENTER	
DOOR ASSEMBLY, PLASTIC	
WET PART, LAUNDRY	
PARTITION, SWITCH	
SKIRT, TIMING, LAUNDRY	
REAR ASSEMBLY	
BACK	
POWER SUPPLY	
VALVE, SOLENOID,	
STRAINER, SEDIMENT,	
NIPPLE, PIPE,	
ANGLE	
PLUG, PIPE	
BLOCK, MANIFOLD,	
CONTROL CHASIS ASSEMBLY	
CONTROL PANEL ASSEMBLY,	
(SEE FIGURE 7-20)	
FUSE, CARTRIDGE,	
FUSEHOLDER,	
VALVE, SOLENOID,	
VALVE, AIR CONTROL, 3 WAY	
RELAY, 3PDT, IO AMP	
SWITCH, PRESSURE	
RELAY,	
TIMING MOVEMENT,	
MECHANICAL,	
(SEE FIGURE 7-21)	
CONTROL PANEL ASSEMBLY	
PANEL, CONTROL	
TIMER, SEQUENTIAL	
SWITCH, TOGGLE,	
COVER, SWITCH	
REVERSING TIMER ASSEMBLY	
SHAFT, SHOULDERED,	
SWITCH, SENSITIVE,	

COMPONENTS:	REMARKS:
ADAPTER, SWITCH	
CAM, CONTROL	
SETSCREW,	
BRACKET, TIMER	
LAUNDRY EXTRACTOR	
ASSEMBLY	
EXTRACTOR, BOCK MOISTRITE	
AND SPEEDRY	
MOTOR ASSEMBLY,	
(SEE FIGURE 7-26)	
MOTOR ASSEMBLY,	
(SEE FIGURE 7-27)	
SHEAVE, PULLEY	
V-BELT	
LID	
FRAME, LID HINCE	
BASKET BALL	
LID GASKET	
CURB ASSEMBLY	
WASHER, LEAD	
RUBBER WASHER	
HOSE,	
BASKET ASSEMBLY	
POST, CENTER	
SEAL,	
CENTER UNIT ASSEMBLY,	
(SEE FIGURE 7-28)	
HUB, BRAKE	
BACK PANEL ASSEMBLY,	
(SEE FIGURE 7,29)	
BASE ASSEMBLY	
TRUNNION FRAME, ASSEMBLY	
COUPLING HALF,	
MOTOR ASSEMBLY #1	
MOTOR, 3 HP	
SWITCH,	
MOUNT, SWITCH	
COUPLING	
HUB, BODY,	
PLATE, MOTOR MOUNT	
MOTOR ASSEMBLY #2	
MOTOR	
HUB, PULLEY	
PLATE, MOTOR MOUNT	
CENTER UNIT ASSEMBLY	
PIN, STUD	
ARM, BRAKE	
ARM, OPERATING	
BRACKET	
SPRING, HELICAL, EXTENSION	
BRAKE SHOE,	
COVER, TOP END	

COMPONENTS:	REMARKS:
SHIELD, SOLENOID	
ROD, SOLENOID	
SOLENOID, BRAKE	
HUB	
BALL, BASKET	
INSERT, NYLON	
PACKING,	
CAP, BUMPER	
BUMPER RUBBERS	
CAP, TRUNNION	
RUBBER, TRUNNION	
HUB, PULLEY	
SHEAVES, PULLEY	
BACK PANEL ASSEMBLY	
BUTTON, START	
SWITCH, PUSH-PULL,	
BUTTON, RED	
LIGHT, INDICATOR	
MICROSWITCH	
SOLENOID,	
RELAY, ELECTRO MAGNETIC	
TIMER,	
FUSE HOLDER	
FUSE, CARTRIDGE,	
TERMINAL BOARD	
COVER	
PLATE, BOTTOM	
BACK AND SIDES, CONTROL PANEL	
PLATE, MOUNT	
PLATE, TOP	
TIE DOWN CLIP ASSEMBLY	
BAR, TIE DOWN CLIP	
LEG, TIE DOWN CLIP	
PLATFORMS	
WATER PUMP ASSEMBLY	
WATER PUMP ASSEMBLY	
FRAME, AL-ALY	
SWITCH BOX ASSEMBLY	
COVERS	
COVER, BOX, FRONT	
PUMP UNIT	
BRACKET	
MOTOR, ALTERNATING	
CAP,	
COUPLING HALF,	
NIPPLE, PIPE	
HOSE CONNECTION ASSEMBLY	
SUCTION STRAINER ASSEMBLY	
COUPLING, QUICK DISCONNECT	
SUCTION HOSE ASSEMBLY	
COUPLING, HALF	

COMPONENTS:	REMARKS:
HEATER INTAKE HOSE ASSEMBLY	
WASHER, INTAKE HOSE ASSEMBLY	
HOSES, WATER,	
CLOTHES BIN DISCHARGE HOSE	
EXTRACTOR DISCHARGE HOSE ASSEMBLY	
PUMP TIE DOWN ASSEMBLY	
CATCH, FIXED ASSEMBLY	
CATCH, ADJUSTABLE	
PLATFORM ASSEMBLY	
DRYER ASSEMBLY	
BLOWER ASSEMBLY, (SEE FIGURE 7-35)	
HOSE ASSEMBLIES	
BURNER TUMBLER ASSEMBLY, (SEE FIGURE 7-36)	
SWITCHES, SENSITIVE	
COVER	
LIGHT, INDICATOR,	
ALARM, BUZZER	
BUZZER,	
DOOR ASSEMBLY	
CHAIN, WELDLESS	
TIMER, SEQUENTIAL	
PLATE, INDENT	
LABEL, CAUTION	
LABEL, WARNING	
ARROW	
HANDLE, DOOR	
RING ASSEMBLY	
FRONT SHELL ASSEMBLY, (SEE FIGURE 7-39)	
HEATER TUMBLER ASSEMBLY, (SEE FIGURE 7-40)	
HOSE, AIR DUCT,	
HOSE, FLEX	
EXHAUST HOSE ADAPTER ASSEMBLY	
DUCT, HOSE,	
REDUCER, PIPE,	
ELBOW, AIR CONDITIONING HEATING	
PIN ASSEMBLY	
PIN	
CHAIN, SAFETY	
HOOK, CHAIN,	
THERMOMETER	
DISCHARGE SPOUT ASSEMBLY	
COUPLING, HALF	
CONTROL, TEMPERA TURE, DIAL AND KNOB	

COMPONENTS:	REMARKS:
CONNECTOR, ELBOW,	
BOX CONNECTOR,	
FAN ASSEMBLY, (SEE FIGURE 7-41)	
COVER	
CONTROL PANEL ASSEM BLY,	
(SEE FIGURE 7-42)	
TUMBLER SPEED REDUCER	
ASSEMBLY,	
(SEE FIGURE 7-43)	
ROD, THREADED	
CUP, GREASE,	
CUP OIL,	
PLATES, RETAINING,	
GUARD	
CHAIN, STL, 65 LINKS	
WIRE, SAFETY	
TUMBLER ASSEMBLY,	
(SEE, FIGURE 7-44)	
SHELL ASSEMBLY	
TUMBLER BASE ASSEMBLY	
PANEL, SIDE	
INSULATOR, PLATE,	
STRIP	
BLOWER ASSEMBLY	
GUAGE, PRESSURE	
COCK, DRAIN	
TEE	
NIPPLE	
PUMP, FUEL	
SHUTTER ASSEMBLY,	
HOUSING	
HOUSING, BLOWER	
WHEEL, BLOWER	
MOUNT, BLOWER	
KEY	
MOTOR, ALTERNATING	
BURNER TUMBLER ASSEMBLY	
CAP FITTING	
GASKET, PEEP SIGHT,	
GLASS, PEEP HOLE	
NIPPLE	
COVER	
CABLE AND TERMINAL	
ASSEMBLY,	
(SEE FIGURE 7-37)	
ELECTRODE ASSEMBLY,	
(SEE FIGURE 7-38)	
BRACKET, TRANSFORMER	
TRANSFORMER	
BOX, JUNCTION	
COVER	
BOX CONNECTORS,	

COMPONENTS:	REMARKS:
CONNECTOR, STRAIGHT	
AIR PLENUM	
CABLE AND TERMINAL ASSEMBLY	
CABLE	
TERMINAL, LUG,	
ELECTRODE ASSEMBLY	
ELECTRODE	
NOZZLE ASSEMBLY	
NOZZLE	
PIPE	
BASE, BURNER	
FRONT SHELL ASSEMBLY	
DOOR	
HINGE ASSEMBLY	
HINGE	
PIN, SPRING	
FRONT, SHELL	
HEATER TUMBLER ASSEMBLY	
SCREEN ASSEMBLY,	
PANEL, COVER	
HOOD ASSEMBLY	
HOOD	
PLATE	
COVER, FRONT	
COVER, REAR	
BURNER MOUNTING ASSEMBLY	
RETURN BOX NO 5 ASSEMBLY	
COVER, ASSEMBLY	
RETURN BOX NO 3 ASSEMBLY	
RETURN BOX NO 1 ASSEMBLY	
RETURN BOX NO 4 ASSEMBLY	
RETURN BOX NO 2 ASSEMBLY	
MOUNTING PLATE ASSEMBLY	
FAN ASSEMBLY	
FAN	
MOTOR, ALTERNATING,	
ARROW	
COVER, WELDMENT	
CONTROL PANEL ASSEMBLY	
STARTER, MANUAL	
PANEL ASSEMBLY	
CONTROL, FLAME	
PROGRAM TIME CARD,	
TERMINAL BOX, 12 SGL	
RELAY	
BASE, RELAY,	
SHIELD ASSEMBLY	
MOTOR, STARTER	
HEATER ELEMENT,	
TUMBLER SPEED REDUCER ASSEMBLY	

COMPONENTS:	REMARKS:
MOTOR, ALTERNATING	
MOUNTING BRACKET ASSEMBLY	
BASE ASSEMBLY	
TUMBLER ASSEMBLY	
TIE ROD	
RIB, TUMBLER,	
SPIDER ASSEMBLY	
TUMBLER, CLOTHES DRYER	
EXHAUST TIE DOWN ASSEMBLY#1	
LEG	
STRAP, WEBBING,	
LOOP	
THREAD	
EXHAUST TIE DOWN ASSEMBLY#2	
LEG	
STRAP	
LOOP	
THREAD	
CONDUIT ASSEMBLY	
GROUND ROD, SECTION	
CONNECTOR, GROUND ROD	
WIRE, #8 STRANDED	
CONDUIT OUTLET	
COVER	
COVER, BLANK	
BODY, CONNECTOR	
COVER, CONNECTER	
PLUG, NYLON	
PLUG, COVER	
CONNECTOR	
BOX, TWO GANG	
BOX CONNECTOR,	
CLOTHES BIN ASSEMBLY	
HANDLE, SHORT	
HANDLE, LONG	
SIDE	
BASE	
COUPLING	
STAND, CLOTHES BIN	
CASTOR	
PLATFORM	
POWER CABLE ASSEMBLY	
BODY	
SHIELD, ELECTRICAL	
CABLE	

COMPONENTS:

REMARKS:

LAUNDRY FACILITY BARE BASE
MAIN PLATFORM ASSEMBLY,
(SEE FIGURE 7 2)
STORAGE BIN ASSEMBLY,
(SEE FIGURE 7 3)
LAUNDRY WASHER ASSEMBLY,
(SEE FIGURE 7-4)
LAUNDRY WASHER ASSEMBLY,
(SEE FIGURE 7 7)
CLAMP ASSEMBLY,
(SEE FIGURE 7-13)
COUPLING
COUPLING HALF,
QUICK DISCONNECT,
CAM-LOCKINC ALL ENDS
PLUG, SQ HD,
ELBOW, ST BRASS
BUSHING, BRASS,
COMPRESSOR UNIT,
RECIPROCATING,
(SEE FIGURE 7-14)
CONTROLLER AND
ELECTRICAL PANEL,
(SEE FIGURE 7-16)
WATER HEATER,
(SEE FIGURE 7-22)
HEATER FUEL LINE ASSEMBLY,
(SEE FIGURE 7-23)
HEATER TIEDOWN ASSEMBLY,
(SEE FIGURE 7-24)
LAUNDRY EXTRACTOR,
(SEE FIGURE 7-25)
TIE DOWN CLIP ASSEMBLY,
(SEE FIGURE 7-30)
WATER PUMP ASSEMBLY,
(SEE FIGURE 7-3 1)
HOSE CONNECT ASSEMBLY,
(SEE FIGURE 7 32)
PUMP TIEDOWN ASSEMBLY,
(SEE FIGURE 7 33)
DRYER ASSEMBLY,
(SEE FIGURE 7-34)
DRYER FUEL LINE ASSEMBLY,
(SEE FIGURE 7-23)
EXHAUST HOSE
TIEDOWN ASSEMBLY,
(SEE FIGURE 7-45)
EXHAUST HOSE
TIEDOWN ASSEMBLY,
(SEE, FIGURE 7-46)
CONDUIT ASSEMBLY,

COMPONENTS:	REMARKS:
(SEE FIGURE 7-47)	
RAIL, SIDE, 84 IN LG	
CLOTHES BIN ASSEMBLY,	
(SEE, FIGURE 7-49)	
POWER CABLEASSEMBLY,	
(SEE FIGURE, 7 49)	
SPACER	
COVER ASSEMBLY RED 1, 2, & 3	
MAIN PLATFORM ASSEMBLY	
PLATFORM, LEFT ASSEMBLY	
PLATFORM, FRAME ASSEMBLY	
DECK, LARGE TOP ASSEMBLY	
DECK, SMALL TOP ASSEMBLY	
DECK, LARGE BOTTOM ASSEMBLY	
DECK, SMALL BOTTOM ASSEMBLY	
RAIL	
RAIL, SIDE	
SLEEVE	
STRAP, RETAINING,	
PLATFORM, RIGHT ASSEMBLY	
IOINING PANEL ASSEMBLY	
STORAGE BIN ASSEMBLY	
BIN, LARGE	
PLATFORM	
BIN, SMALL	
COVER ASSEMBLY	
FASTENER, LINK LOCK	
TRAY	
LAUNDRY WASHER	
WASHER ASSEMBLY,	
(SEE FIGURE 7-5)	
PLATE, TANK MOUNTING	
ELBOW, PIPE,	
TEE, PIPE, STL,	
COCK, DRAIN,	
WASHER ASSEMBLY, OPEN END	
COVER, BASE SIDE LEFT	
COVER, BASE FRONT	
COVER, BASE SIDE RIGHT	
SUPPLY INJECTOR ASSEMBLY	
SHELL ASSEMBLY	
SHELL FRONT ASSEMBLY	
SHELL, EXTRUSION	
RING, SHELL	
PLATE, MOUNTING	
MICROSWITCH	
CAM, CONTROL	
HANDLE ASSEMBLY	
DOOR, ASSEMBLY	
BRACKET, HINGE	
CYLINDER ASSEMBLY	

COMPONENTS:	REMARKS:
HOUSING, SHAFT SEAL	
GASKET, SHAFTSEAL	
SEAL, PLAIN, STL,	
COVER, SHAFT RETAINER	
SPACER, SHAFT RETAINER	
KEY, MACHINE, STL	
SPIDER,	
GEAR ASSEMBLY,	
SPEED DECREASER	
MOTOR, ALTERNATING	
MOUNT, MOTOR	
BRACKET, MOTOR MOUNT, LEFT	
BRACKET, MOTOR MOUNT, RIGHT	
BELT GUARD ASSEMBLY	
BRACKET, BELT UPPER	
BELT, V, RBR,	
BRACKET, BELT, LOWER LEFT	
PULLEY, GROOVE,	
BUSHING, SLEEVE	
V-PULLEY	
BUSHING, SLEEVE	
COVER, SYPHON	
BREAKER	
PIPE, ELBOW	
WATER LEVEL FLOAT,	
CHAMBER ASSEMBLY,	
(SEE FIC3URE 7-6)	
SOAP CHUTE	
COVER, SOAP CHUTE	
HINGE, SOAP CHUTE	
ROD, SOAP CHUTE	
PIPE, METALLIC	
HOSE, NONMETALLIC,	
PIPE, WATER INLET	
VALVE, ANGLE,	
WATER LEVEL FLOAT	
CHAMBER ASSEMBLY	
SWITCH, LIQUID LEVEL	
TUBING, GLASS,	
CLAMP, LOOP	
BRACKET, LEVEL CONTROL	
BRACKET, TOP FLOAT	
CHAMBER	
BRACKET, BOTTOM	
FLOAT CHAMBER	
FLOAT ASSEMBLY,	
LIQUID LEVEL	
FLOAT	
ROD, FLOAT,	
SPEED NUT	
LAUNDRY WASHER ASSEMBLY	

COMPONENTS:	REMARKS:
FRAME ASSEMBLY	
DOOR ASSEMBLY, (SEE FIGURE 7-8)	
DOOR LOCK ASSEMBLY, (SEE FIGURE 7-9)	
DRAW BAND, WASHER EXTRACTOR	
GASKET, RBR CHLOROPRENE	
DRUM FRONT	
CYLINDER ASSEMBLY	
SPIDER AND SHAFT ASSEMBLY	
ROD, THREADED END	
RING, GASKET CLAMP	
GASKET, SOCK	
MOTOR	
PLATE, MOTOR MOUNTING	
ROD, MOTOR ADJUSTING	
BELT	
PULLEY, GROOVE,	
BUSHING, SHEAVE	
DRUM ASSEMBLY	
WATER INLET ASSEMBLY, (SEE FIGURE 7-10)	
SHEAVE	
BUSHING, SHEAVE	
GEAR ASSEMBLY,	
PLATE, MOUNTING	
SEAL AND CARRIAGE ASSEMBLY,	
SEAL, PLAIN	
DISPENSER ASSEMBLY, (SEE FIGURE 7-11)	
GAUGE, TEMPERATURE	
BOTTLE, SUPPLY	
VALVE ASSEMBLY, DRAIN, (SEE FIGURE 7-12)	
PLUG, PIPE	
HOSE, DRAIN	
DOOR ASSEMBLY	
DOOR HINGE AND HANDLE	
BASE, DOOR HINGE	
BUSHING, FLANGE,	
PIN, DOOR HINGE	
BEARING, WASHER,	
BAR, DOOR	
FASTENER, PAWL	
BOLT, PIVOT	
BUSHING, SLEEVE	
RING, RETAINING	
WINDOW, OBSERVATION, GLASS,	
GASKET, DOOR GLASS	

COMPONENTS:	REMARKS:
FRAME, DOOR	
DRAW BAND, DOOR	
GASKET, DRAW BAND	
GASKET, DOOR	
DOOR LOCK ASSEMBLY	
DOOR LOCK COVER AND SWITCH	
COVER, DOOR LOCK	
SWITCH, PUSH	
BOOT, DUST AND MOISTURE SEAL	
BRACKET, MOUNTING	
BUSHING, ELECTRICAL	
CONDUCTOR,	
SOLENOID,	
SWITCH,	
PLATE, DOOR LOCK	
SPRING, DOOR LOCK	
BAR, DOOR LOCK	
SPRING, DOOR LATCH	
WATER INLET ASSEMBLY	
LEVER, MANUAL CONTROL	
CLEVIS, ROD END,	
CYLINDER ASSEMBLY,	
ROD, ADJUSTINC STUD	
BRACKET, MOUNTING	
COUPLER, FEMALE	
COUPLING HALF, QUICK	
DISCONNECT,	
ELBOW, PIPE,	
NIPPLE, PIPE,	
PIPE, METALLIC,	
ELBOW, PIPE TO HOSE,	
ELBOW, PIPE,	
BUSHING, PIPE	
TEE, PIPE	
VALVE, BALL,	
NIPPLE, PIPE,	
DISPENSER ASSEMBLY	
DISPENSER	
COVER	
HOSE, SUPPLY1	
SUPPLY HOSE, AIR	
HOSE, SUPPLY 2	
HOSE, SUPPLY 3	
HOSE, SUPPLY 4	
FITTING, HOSE	
COUPLING, PIPE,	
HOSE, SUPPLY INLET	
ADAPTER, STRAIGHT	
VALVE, SOLENOID,	
MANIFOLD, SUPPLY	
BRACKET, MANIFOLD	

COMPONENTS:	REMARKS:
MOUNTING	
DRAIN VALVE ASSEMBLY	
PLATE, TOP	
BELLOWS, RUBBER,	
ADAPTER, STRAIGHT,	
PLATE, MOUNTING	
BRACKET	
HOSE, NONMETALLIC,	
PINCH TUBE	
CLAMP ASSEMBLY	
ANGLE	
ROD, THREADED, SHORT	
RING, HANGER	
AIR COMPRESSOR ASSEMBLY	
GRILLE, METAL	
HANDLE, DOOR, L STYLE	
KIT, SWITCH, (SEE FIGURE 7-15)	
HOUSING, AIR COMPRESSOR	
CYLINDER, HEAD ASSEMBLY,	
RIGHT HAND	
CYLINDER HEAD ASSEMBLY,	
LEFT HAND	
MOTOR, ALTERNATING	
CABLE ASSEMBLY,	
PRESSURE SWITCH ASSEMBLY	
SWITCH, PRESSURE	
PLUG, BUTTON	
WIRE ASSEMBLY, BLK	
WIRE ASSEMBLY, WHT	
CONTROLLER AND ELECTRICAL	
PANELSUPPORT FRAME	
ASSEMBLY	
FACE PLATE, LAUNDRY,	
COVER, CONTROLLER	
CONTROLLER ASSEMBLY	
HEAD ASSEMBLY,	
CONTROL BOX, (SEE FIGURE 7-17)	
CONTROL BOX ASSEMBLY,	
(SEE FIGURE 7-18)	
CONTROL CHASIS	
ASSEMBLY, LAUNDRY,	
(SEE FIGURE 7-19)	
HOSE, LOW PRESSURE	
ADAPTER, STRAIGHT	
SLEEVE	
FIRE EXTINGUISHER	
PLATE, MOUNTING	
STAND, CONTROLLER SUPPORT	
LOAD CENTER	
ENCLOSURE	
BRACKET, INTERIOR MOUNT	

COMPONENTS:	REMARKS:
KIT, INTERIOR TRIM	
CAP, END SEAL	
MAIN BREAKER, 30 AMP	
CIRCUIT BREAKER, 20 AMP	
BOX, 3 GANG	
GASKET, SYNTH-RBR,	
CONNECTOR, RECEPTACLE	
OUTLET	
COVER, CONDUIT	
COVER, LIFT	
SWITCH, MOTOR STARTING	
HEAD ASSEMBLY	
WINDOW, OBSERVATION,	
LATCH, SPECIAL	
LAMP, 28V	
SOCKET, LAMP	
NAME PLATE	
WARNING	
NAME PLATE,	
TUBING,	
TYRAP,	
BRACKET, RECEPTACLE	
RECEPTACLE	
ANGLE, CENTER	
DOOR ASSEMBLY, PLASTIC	
WET PART, LAUNDRY	
PARTITION, SWITCH	
SKIRT, TIMING, LAUNDRY	
REAR ASSEMBLY	
BACK	
POWER SUPPLY	
VALVE, SOLENOID,	
STRAINER, SEDIMENT,	
NIPPLE, PIPE,	
ANGLE	
PLUG, PIPE	
BLOCK, MANIFOLD,	
CONTROL CHASIS ASSEMBLY	
CONTROL PANEL ASSEMBLY,	
(SEE FIGURE 7-20)	
FUSE, CARTRIDGE,	
FUSEHOLDER,	
VALVE, SOLENOID,	
VALVE, AIR CONTROL, 3 WAY	
RELAY, 3PDT, IO AMP	
SWITCH, PRESSURE	
RELAY,	
TIMING MOVEMENT,	
MECHANICAL,	
(SEE FIGURE 7-21)	
CONTROL PANEL ASSEMBLY	

COMPONENTS:

REMARKS:

PANEL, CONTROL
TIMER, SEQUENTIAL
SWITCH, TOGGLE,
COVER, SWITCH
REVERSING TIMER ASSEMBLY
SHAFT, SHOULDERED,
SWITCH, SENSITIVE,
ADAPTER, SWITCH
CAM, CONTROL
SETSCREW,
BRACKET, TIMER
LAUNDRY EXTRACTOR ASSEMBLY
EXTRACTOR, BOCK MOISTRITE AND SPEEDRY
MOTOR ASSEMBLY,
(SEE FIGURE 7-26)
MOTOR ASSEMBLY,
(SEE FIGURE 7-27)
SHEAVE, PULLEY
V-BELT
LID
FRAME, LID HINCE
BASKET BALL
LID GASKET
CURB ASSEMBLY
WASHER, LEAD
RUBBER WASHER
HOSE,
BASKET ASSEMBLY
POST, CENTER
SEAL,
CENTER UNIT ASSEMBLY,
(SEE FIGURE 7-28)
HUB, BRAKE
BACK PANEL ASSEMBLY,
(SEE FIGURE 7,29)
BASE ASSEMBLY
TRUNNION FRAME, ASSEMBLY
COUPLING HALF,
MOTOR ASSEMBLY #1
MOTOR, 3 HP
SWITCH,
MOUNT, SWITCH
COUPLING
HUB, BODY,
PLATE, MOTOR MOUNT
MOTOR ASSEMBLY #2
MOTOR
HUB, PULLEY
PLATE, MOTOR MOUNT

COMPONENTS:	REMARKS:
CENTER UNIT ASSEMBLY	
PIN, STUD	
ARM, BRAKE	
ARM, OPERATING	
BRACKET	
SPRING, HELICAL, EXTENSION	
BRAKE SHOE,	
COVER, TOP END	
SHIELD, SOLENOID	
ROD, SOLENOID	
SOLENOID, BRAKE	
HUB	
BALL, BASKET	
INSERT, NYLON	
PACKING,	
CAP, BUMPER	
BUMPER RUBBERS	
CAP, TRUNNION	
RUBBER, TRUNNION	
HUB, PULLEY	
SHEAVES, PULLEY	
BACK PANEL ASSEMBLY	
BUTTON, START	
SWITCH, PUSH-PULL,	
BUTTON, RED	
LIGHT, INDICATOR	
MICROSWITCH	
SOLENOID,	
RELAY, ELECTRO MAGNETIC	
TIMER,	
FUSE HOLDER	
FUSE, CARTRIDGE,	
TERMINAL BOARD	
COVER	
PLATE, BOTTOM	
BACK AND SIDES, CONTROL PANEL	
PLATE, MOUNT	
PLATE, TOP	
TIE DOWN CLIP ASSEMBLY	
BAR, TIE DOWN CLIP	
LEG, TIE DOWN CLIP	
PLATFORMS	
WATER PUMP ASSEMBLY	
WATER PUMP ASSEMBLY	
FRAME, AL-ALY	
SWITCH BOX ASSEMBLY	
COVERS	
COVER, BOX, FRONT	
PUMP UNIT	
BRACKET	

COMPONENTS:	REMARKS:
MOTOR, ALTERNATING	
CAP,	
COUPLING HALF,	
NIPPLE, PIPE	
HOSE CONNECTION ASSEMBLY	
SUCTION STRAINER ASSEMBLY	
COUPLING, QUICK DISCONNECT	
SUCTION HOSE ASSEMBLY	
COUPLING, HALF	
HEATER INTAKE HOSE ASSEMBLY	
WASHER, INTAKE HOSE ASSEMBLY	
HOSES, WATER,	
CLOTHES BIN DISCHARGE HOSE	
EXTRACTOR DISCHARGE HOSE ASSEMBLY	
PUMP TIE DOWN ASSEMBLY	
CATCH, FIXED ASSEMBLY	
CATCH, ADJUSTABLE	
PLATFORM ASSEMBLY	
DRYER ASSEMBLY	
BLOWER ASSEMBLY, (SEE FIGURE 7-35)	
HOSE ASSEMBLIES	
BURNER TUMBLER ASSEMBLY, (SEE FIGURE 7-36)	
SWITCHES, SENSITIVE	
COVER	
LIGHT, INDICATOR,	
ALARM, BUZZER	
BUZZER,	
DOOR ASSEMBLY	
CHAIN, WELDLESS	
TIMER, SEQUENTIAL	
PLATE, INDENT	
LABEL, CAUTION	
LABEL, WARNING	
ARROW	
HANDLE, DOOR	
RING ASSEMBLY	
FRONT SHELL ASSEMBLY, (SEE FIGURE 7-39)	
HEATER TUMBLER ASSEMBLY, (SEE FIGURE 7-40)	
HOSE, AIR DUCT,	
HOSE, FLEX	
EXHAUST HOSE ADAPTER ASSEMBLY	
DUCT, HOSE,	
REDUCER, PIPE,	
ELBOW, AIR CONDITIONING	

COMPONENTS:	REMARKS:
HEATING	
PIN ASSEMBLY	
PIN	
CHAIN, SAFETY	
HOOK, CHAIN,	
THERMOMETER	
DISCHARGE SPOUT ASSEMBLY	
COUPLING, HALF	
CONTROL, TEMPERA TURE, DIAL AND KNOB	
CONNECTOR, ELBOW,	
BOX CONNECTOR,	
FAN ASSEMBLY, (SEE FIGURE 7-41)	
COVER	
CONTROL PANEL ASSEM BLY, (SEE FIGURE 7-42)	
TUMBLER SPEED REDUCER ASSEMBLY, (SEE FIGURE 7-43)	
ROD, THREADED	
CUP, GREASE,	
CUP OIL,	
PLATES, RETAINING,	
GUARD	
CHAIN, STL, 65 LINKS	
WIRE, SAFETY	
TUMBLER ASSEMBLY, (SEE, FIGURE 7-44)	
SHELL ASSEMBLY	
TUMBLER BASE ASSEMBLY	
PANEL, SIDE	
INSULATOR, PLATE, STRIP	
BLOWER ASSEMBLY	
GUAGE, PRESSURE	
COCK, DRAIN	
TEE	
NIPPLE	
PUMP, FUEL	
SHUTTER ASSEMBLY,	
HOUSING	
HOUSING, BLOWER	
WHEEL, BLOWER	
MOUNT, BLOWER	
KEY	
MOTOR, ALTERNATING	
BURNER TUMBLER ASSEMBLY	
CAP FITTING	
GASKET, PEEP SIGHT,	
GLASS, PEEP HOLE	
NIPPLE	

COMPONENTS:	REMARKS:
COVER	
CABLE AND TERMINAL	
ASSEMBLY,	
(SEE FIGURE 7-37)	
ELECTRODE ASSEMBLY,	
(SEE FIGURE 7-38)	
BRACKET, TRANSFORMER	
TRANSFORMER	
BOX, JUNCTION	
COVER	
BOX CONNECTORS,	
CONNECTOR, STRAIGHT	
AIR PLENUM	
CABLE AND TERMINAL	
ASSEMBLY	
CABLE	
TERMINAL, LUG,	
ELECTRODE ASSEMBLY	
ELECTRODE	
NOZZLE ASSEMBLY	
NOZZLE	
PIPE	
BASE, BURNER	
FRONT SHELL ASSEMBLY	
DOOR	
HINGE ASSEMBLY	
HINGE	
PIN, SPRING	
FRONT, SHELL	
HEATER TUMBLER ASSEMBLY	
SCREEN ASSEMBLY,	
PANEL, COVER	
HOOD ASSEMBLY	
HOOD	
PLATE	
COVER, FRONT	
COVER, REAR	
BURNER MOUNTING ASSEMBLY	
RETURN BOX NO 5 ASSEMBLY	
COVER, ASSEMBLY	
RETURN BOX NO 3 ASSEMBLY	
RETURN BOX NO 1 ASSEMBLY	
RETURN BOX NO 4 ASSEMBLY	
RETURN BOX NO 2 ASSEMBLY	
MOUNTING PLATE ASSEMBLY	
FAN ASSEMBLY	
FAN	
MOTOR, ALTERNATING,	
ARROW	
COVER, WELDMENT	
CONTROL PANEL ASSEMBLY	

COMPONENTS:	REMARKS:
STARTER, MANUAL	
PANEL ASSEMBLY	
CONTROL, FLAME	
PROGRAM TIME CARD,	
TERMINAL BOX, 12 SGL	
RELAY	
BASE, RELAY,	
SHIELD ASSEMBLY	
MOTOR, STARTER	
HEATER ELEMENT,	
TUMBLER SPEED REDUCER ASSEMBLY	
MOTOR, ALTERNATING	
MOUNTING BRACKET ASSEMBLY	
BASE ASSEMBLY	
TUMBLER ASSEMBLY	
TIE ROD	
RIB, TUMBLER,	
SPIDER ASSEMBLY	
TUMBLER, CLOTHES DRYER	
EXHAUST TIE DOWN ASSEMBLY#1	
LEG	
STRAP, WEBBING,	
LOOP	
THREAD	
EXHAUST TIE DOWN ASSEMBLY#2	
LEG	
STRAP	
LOOP	
THREAD	
CONDUIT ASSEMBLY	
GROUND ROD, SECTION	
CONNECTOR, GROUND ROD	
WIRE, #8 STRANDED	
CONDUIT OUTLET	
COVER	
COVER, BLANK	
BODY, CONNECTOR	
COVER, CONNECTER	
PLUG, NYLON	
PLUG, COVER	
CONNECTOR	
BOX, TWO GANG	
BOX CONNECTOR,	
CLOTHES BIN ASSEMBLY	
HANDLE, SHORT	
HANDLE, LONG	
SIDE	
BASE	

COMPONENTS:	REMARKS:
COUPLING	
STAND, CLOTHES BIN	
CASTOR	
PLATFORM	
POWER CABLE ASSEMBLY	
BODY	
SHIELD, ELECTRICAL	
CABLE	

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 0704-0188

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP _____ TM _____ OTHER X

D. SYSTEM/ITEM	E. CONTRACT/PR NO.	F. CONTRACTOR
Standardized Bare Base Laundry Facil		

1. DATA ITEM NO.	2. TITLE OF DATA ITEM	3. SUBTITLE	17. PRICE GROUP
A001	Contractor's Progress, Status, and Management Report	Management	

4. AUTHORITY *(Data Acquisition Document No.)*	5. CONTRACT REFERENCE	6. REQUIRING OFFICE	18. ESTIMATED TOTAL PRICE
DI-MGMT-80227	SOW 4.2	MCSC (CSLE), Albany, GA	

7. DD 250 REQ	8. DIST STATEMENT REQUIRED	9. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	A	MTHLY	See Blk 16

8. APP CODE	11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION
		See Blk 16

16. REMARKS

Contractor format is authorized.

Blk 4 - Tailor DI-MGMT-80227 as follows: Delete paragraphs 10.3g, 10.3h, 10.3i, and 10.3j, 10.3k, and 10.3n.

Blk 12 - The reporting period shall be from the first to last business day of each month. Initial submission shall be 60 DAC.

Blk 13 - Subsequent submissions shall be 10 days after the last business day of each month.

Distribution StatementA: Approved for public release; Distribution is unlimited.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES		
	Draft	Final	
		Reg	Repro
MCSC (CSLE) Albany, GA	0	1	0
15. TOTAL →	0	1	0

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Leka Dawson	3/1/02	Leka Dawson	3/1/02

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 0704-0188

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ OTHER X

D. SYSTEM/ITEM	E. CONTRACT/PR NO.	F. CONTRACTOR
Standardized Bare Base Laundry Facil		

1. DATA ITEM NO.	2. TITLE OF DATA ITEM	3. SUBTITLE
B001	Repairable Item Inspection Report	Integrated Logistic Support Standards

4. AUTHORITY *(Data Acquisition Document No.)*	5. CONTRACT REFERENCE	6. REQUIRING OFFICE
DI-ILSS-80386	SOW 4.1	MCSC (CSLE), Albany, GA

7. DD 250 REQ	8. DIST STATEMENT REQUIRED	10. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	A	ASREQ	See Blk 16
9. APP CODE		**11. AS OF DATE**	**13. DATE OF SUBSEQUENT SUBMISSION**
			See Blk 16

16. REMARKS

Blk 4 - Contractor format is authorized.

Blks 10 - A separate report shall be submitted for each Standardized Bare Base Laundry Facility repaired.

Blks 12 & 13 - Submit report by Marine Corps Serial Number 30 days after completion of each Standardized Bare Base Laundry Facility.

Distribution Statement A. Approved for public release; Distribution is unlimited.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES		
	Draft	Final	
		Reg	Repro
MCSC (CSLE) Albany, GA	0	1	0
15. TOTAL →	0	1	0

17. PRICE GROUP	18. ESTIMATED TOTAL PRICE

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Leroy Rawls	3/1/02	Leroy Rawls	3/1/02

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 0704-0188

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP _____ TM _____ OTHER X

D. SYSTEM/ITEM	E. CONTRACT/PR NO.	F. CONTRACTOR
Standardized Bare Base Laundry Facil		

1. DATA ITEM NO.	2. TITLE OF DATA ITEM	3. SUBTITLE	17. PRICE GROUP
C001	Request For Deviation	Configuration Management	

4. AUTHORITY *(Data Acquisition Document No.)*	5. CONTRACT REFERENCE	6. REQUIRING OFFICE	18. ESTIMATED TOTAL PRICE
DI-CMAN-80640C	SOW 3.3.2	MCLBA (583)	

7. DD 250 REQ	8. DIST STATEMENT REQUIRED	10. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	A	ASREQ	See Blk 16

9. APP CODE	11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION
A		

16. REMARKS

Blk 4 - Contractor format submitted in .pdf or .doc format is authorized.

Blks 10 & 12 - RFDs shall be submitted to obtain authorization to deliver nonconforming material which does not meet prescribed configuration documentation.

RFDs will be reviewed and disposition determined within 30 calendar days upon receipt by the Government.

Block 14: RFDs shall be transmitted via E-Mail to the following address: mbmatcomconfigmngmnt@matcom.usmc.mil

Distribution Statement A: Approved for public release; Distribution is unlimited.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Rep	Final Repro
MCLBA (583-1)	0	1	0
15. TOTAL →	0	1	0

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
L Elroy Rivera	3/1/02	L Elroy Rivera	3/1/02

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED.