

STATEMENT  
OF  
WORK (SOW)  
FLOODLIGHT SET, MODEL SM-4A3-0  
INSPECT AND REPAIR ONLY AS NECESSARY  
(IROAN)  
NSN 6230-01-170-1408  
EFFECTIVE DATE: 25 OCTOBER 1999

## TABLE OF CONTENTS

<b>Section and Reading</b>	<b>Page</b>
1.0 Scope	1
1.1 Background	1
2.0 Applicable Documents	1
2.1 Military Standards	1
2.2 Other Government Documents and Publications	1
2.3 Engineering Drawings	2
2.4 Industry Standards	2
3.0 Requirements	3
3.1 General Tasks	3
3.2 Detail Tasks	3
3.2.1 Phase I Pre-Induction	3
3.2.2 Phase II – IROAN	3
3.2.3 Phase III - Inspection, Testing and Acceptance	4
3.2.4 Phase IV - Packaging, Handling, Storage, and Transportation (PHS&T)	5
3.3 Configuration Management	5
3.3.1 Configuration Status Accounting (CSA)	5
3.3.2 Configuration Control	6
3.4 Government Furnished Equipment (GFE)/ Government Furnished Material (GFM)	6 6
3.5 Contractor Furnished Materiel	6
3.6 Quality Assurance Provisions	6
3.7 Acceptance	7
3.8 Rejection	7

STATEMENT OF WORK FOR THE  
**FLOODLIGHT SET SM-4A3-0**  
Inspect Repair Only As Necessary (IROAN)  
6230-01-170-1408

1.0 SCOPE. This Statement of Work (SOW) establishes and sets forth tasks and identifies the work efforts that shall be performed by the Contractor in the IROAN effort of the FLOODLIGHT SET SM-4A3-0, hereafter referred to as the FLOODLIGHT SET. These documents contain requirements to restore the FLOODLIGHT SET to Condition Code "A." Condition Code A is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction. Includes materiel with more than 6 months shelf-life remaining." National Stock Number (NSN) 6230-01-170-1408 shall be known as the FLOODLIGHT SET.

1.1 Background. IROAN is defined as "That maintenance technique which determines the minimum repairs necessary to restore equipment components or assemblies to prescribed maintenance serviceability standards by utilizing all available diagnostic equipment and test procedures in order to minimize disassembly and parts replacement."

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards.

MIL-STD-129	DoD Standard Practice for Military Marking
MIL-STD-130	Identification Marking of US. Military Property
MIL-STD-2073-1C	DoD Standard Practice for Military Packaging
<u>Military Standards - (Guidance Only)</u>	
MIL-STD-973	Configuration Management

2.2 Other Government Documents and Publications

DODD 4160.21-M-1	Defense Demilitarization Manual.
DoD 4000.25-1-M	MILSTRIP Manual

Furnished Materiel	NAVICPINST 4491.2A Requisitioning of Contractor from the Federal Supply System
SL-3-08857A	Floodlight Set, Skid Mounted
TM 3080-12	Corrosion Prevention and Control for Marine Corps Equipment
TM 3080-50	Corrosion Control Procedures Depot Maintenance Activities for Marine Corps Equipment
TM 4700-15/1H	Ground Equipment Record Procedures
TM 4750-15/1	Painting and Registration Marking for Marine Corps Combat and Tactical Equipment.
TM 08857A-14/1	Operation and Maintenance Instructions for Floodlight Set

2.3 Engineering Drawings. The following Government drawing packages form a part of this SOW to the extent specified herein.

ENGINEERING DRAWINGS – Marine Corps

845001A0000 Floodlight Set SM-4A3-0.

2.4 Industry Standards.

ANSI/ISO/ASQC Q9002-1994 Quality Systems

Copies of military specifications and standards are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Commander, Marine Corps Logistics Bases, (Code 891), 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number 912-439-6753 or DSN 567-6753. Copies of Engineering Drawings, if applicable, shall be obtained from Life Cycle Management Center, Attn: Code 825-3, 814 Radford Blvd, Suite 20320, Albany, Georgia 31704-0320.

3.0 REQUIREMENTS

3.1 General Tasks. In fulfilling the specified requirements, the Contractor shall:

- a. Provide materials, labor, facilities, missing parts, and repair parts necessary to inspect, diagnose, restore, and test the FLOODLIGHT SET. Upon completion of IROAN, repaired equipment shall be Condition Code "A".
- b. Provide all tools and test equipment required to test, inspect, repair, and calibrate the FLOODLIGHT SET.
- c. Conduct in-process and final on-site testing for witness by an MCLB, Albany, representative.
- d. Be responsible for all structural, electrical and mechanical requirements associated with the restoration of the FLOODLIGHT SET.
- e. If corrosion exists, remove and take action in accordance with TM-3080-12 and TM-3080-50.

3.2 Detail Tasks. The following tasks describe the different phases for IROAN of the FLOODLIGHT SET.

3.2.1 Phase I - Pre-induction. A pre-induction inspection analysis shall be performed for each FLOODLIGHT SET using the Contractor's diagnosis, inspection and testing techniques to determine extent of work and parts required. This inspection shall include all items associated with the FLOODLIGHT SET to include all SL3 components identified in SL-3-08857A. These findings shall be annotated on a Pre-Induction Check list that shall be located, identified and provided to the government in accordance with Appendix A of this SOW. Upon completion of this requirement and the identification of serviceable components, all SL3 components, not installed or used to test the FLOODLIGHT SET shall be returned to Fleet Support Division (FSD) Code 870, for their action. Coordination to facilitate this requirement shall be the responsibility of the Contractor. The FLOODLIGHT SET, although a principle end item, cannot be operated by itself. It must be powered by a Generator Set, 10kw, 60hz, Model MEP-003A, NSN 6115-00-465-1030 to perform both the initial and final inspections. If required and upon request, the Generator can be furnished as GFE under provisions of this SOW.

3.2.2 Phase II - IROAN. After pre-induction tests and inspections have been completed, repair of the FLOODLIGHT SET shall be accomplished in accordance with this SOW. Deficiencies noted on the Pre-Induction Checklist during Phase I shall be repaired/replaced. Components or assemblies shall not be disassembled for replacement of mandatory parts unless that part has failed, or the component assembly wherein the part is located is disassembled for repair.

- a. Inspection Report - Information recorded on the Inspection Report shall be used as a guide to repair the FLOODLIGHT SET system in accordance with this SOW.

b. Technical Instruction (TI) - All TI's not previously applied to the FLOODLIGHT SET shall be applied during the IROAN and shall be annotated on Equipment Record Jacket in accordance with TM 4700-15/1H.

c. Data Plates - All required data plates and decals shall be in place and shall be legible. Each repaired FLOODLIGHT SET shall have an IROAN data plate affixed to the main unit in close proximity to the existing data plate. The data plate shall meet the requirements of MIL-STD-130.

d. Painting/Coating - If painting/coating is required, the FLOODLIGHT SET shall be cleaned in accordance with TM 3080-50, Chapter 4, and painted in accordance with TM 4750-15/1.

e. Demilitarization - All end items that are identified as non-repairable and require demilitarization codes, shall be reported to the Marine Corps Logistics Bases representatives Code 837-1, who will provide disposition instructions in accordance with DODD 4160.21-M-1.

f. Hardware

(1) Replace broken, unserviceable and/or missing hardware including nuts, bolts, screws, washers, turnlock fasteners, mandatory, safety, and one-time use items, etc., in accordance with TM 08857A-14/1. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present and operational on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

g. Cable Assemblies - All cables and cable connections shall be tested and visually inspected for damage or corrosion. Any cable or cable connector showing signs of damage, corrosion or separation of outer coating shall be repaired/replaced and tested with it's respective component box/assembly to assure satisfactory compliance with all operational test.

### 3.2.3 Phase III - Inspection, Testing and Acceptance

a. Inspection, Testing and Acceptance of the FLOODLIGHT SET shall be conducted in accordance with TM 08857A-14/1.

b. The Contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are available to complete the final acceptance. Acceptance tests shall be held at the Contractor's facility. MCLB (Code 837-1), Albany, Georgia, representatives shall be given a minimum of two weeks notice prior to beginning acceptance testing. The test area shall be cleared of all equipment parts, components, etc., not required for the test.

c. The Contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCLB (Code 837-1), Albany, Georgia, representatives may require the

Contractor to repeat tests or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

d. Acceptance testing on all FLOODLIGHT SET repaired under the provisions of this SOW shall be accomplished in accordance with TM 08857A-14/1. The Operational Tests are to be conducted on each FLOODLIGHT SET, upon completion of repairs and prior to the equipment being returned to stock.

### 3.2.4 Phase IV - Packaging, Handling, Storage, and Transportation (PHS&T)

a. The contractor shall be responsible for preservation and packaging of items being repaired under the terms of this statement of work. Items being repaired for long term storage or shipment to overseas destinations shall be in accordance with level "A" requirements of MIL-STD-2073-1C, method 10. Items being prepared for immediate use or domestic shipment shall be packaged in accordance with level "B" requirements.

b. Markings shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of the repaired equipment. The Contractor shall be responsible for arranging for shipment of the equipment to the pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the subject equipment to and from the Contractor.

### 3.3 Configuration Management

#### 3.3.1 Configuration Status Accounting (CSA)

a. The Contractor shall record and submit data on retrofit accomplished during Phase II.

b. The Contractor shall determine the application status of approved configuration changes by visual inspections to the extent possible. The government will identify the configuration changes to be inspected by furnishing a Configuration Inspection Checklist to the Contractor. The Contractor shall use one checklist per FLOODLIGHT SET to record their inspection findings along with other required data.

c. The Contractor shall record serial numbers of the assemblies listed on the Configuration Inspection Checklist. The Contractor shall record the information on the same form that was used to record the application status of configuration changes.

3.3.2 Configuration Control. The baseline configuration for the FLOODLIGHT SET has been established by Marine Corps Drawing number 845001A0000. No deviations from this baseline configuration shall be allowed unless authorized by MCLB Albany (Code 837-1). The Contractor shall process Requests for Deviations or Requests for Waivers using MIL-STD-973 (paragraph 5.4.3, 5.4.4, and Appendix E) as a guide.

### 3.4 Government Furnished Equipment (GFE)/Government Furnished Material (GFM)

a. GFE is government owned equipment authorized by contract for use by a commercial/government contractor. It is neither consumed during production nor incorporated into any product. GFM is materiel furnished to a contractor that will be consumed during the course of production or incorporated into the product being manufactured/remanufactured under a contract/statement of work. In the event the Marine Corps does have GFE/GFM requirements, the Management Control Activity (MCA/320), Marine Corps Logistics Bases, Albany, Georgia, will coordinate required GFE and will maintain a central control on Marine Corps assets in the Contractor's possession. The MCA will forward a GFE Accountability Agreement to the Contractor Facility for signature to establish a chain of custody and property responsibilities for Marine Corps assets.

b. The following GFE will be provided, if requested:

(1) Generator Set, 10kw, 60hz, Model MEP-003A, NSN 6115-00-465-1030.

3.5 Contractor Furnished Materiel (CFM). The Marine Corps has adopted the Navy's procedure regarding Contractor Furnished Materiel (NAVICPINST 4491.21A). In the event that Contractor Furnished Materiel (CFM) is required for repair parts, the contractor shall requisition repair parts through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP), Chapter 11 authorizes contractors to requisition through the DOD Supply System.

### 3.6 Quality Assurance Provisions

The contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9002-1994, Quality System Model for Quality Assurance in Production, Installation, and Servicing. The program shall ensure quality throughout all areas to include design, fabrication, processing, assembly, inspection, test, maintenance, and preparation for delivery and shipping. Unless otherwise specified in the contract, the Contractor shall be responsible for performance of all inspection requirements. The Government reserves the right to perform any of the inspections set forth in the contract where such inspections are deemed necessary to assure products and services conform to the prescribed requirements. The Contractor shall provide an Inspection and Test Plan.

### 3.7 Acceptance.

The performance of the Contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and Marine Corps representatives shall be permitted to observe the work or to conduct inspection at all reasonable hours. Final inspection and acceptance testing shall be conducted at the Contractor's facility. Final acceptance shall be conducted on 100 percent of items to verify that the units meet all requirements.

3.8 Rejection

Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCLB, Albany, representative. The Contractor shall, at no additional cost to MCLB, Albany, Georgia, provide the following:

- a. Develop an approach for modification or correction of all deficiencies.
- b. Upon approval of a documented approach, the Contractor set shall correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures is demonstrated.

**FLOODLIGHT SET PRE-INDUCTION INSPECTION CHECKLIST**

FLOODLIGHT SET SERIAL NUMBER \_\_\_\_\_

CONDITION CODE UPON RECEIPT \_\_\_\_\_

CORROSION PREVENTION METHODS TO BE USED \_\_\_\_\_

\_\_\_\_\_

**REPAIR PARTS/ASSEMBLIES REQUIRED FOR REPAIRS**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**DEFECTIVE PARTS AND ASSEMBLIES**

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_





