STATEMENT OF WORK (SOW)
REBUILD OF
MOUNT TELESCOPE, M172
NSN 1240-01-037-7290

1.0 Scope. This Statement of Work (SOW) establishes and sets forth tasks and identifies the work efforts that shall be performed by the Contractor in the rebuild effort of the Mount Telescope, M172, NSN 1240-01-037-7290 in support of the M198 Howitzer, ID# 08198A, TAMCN E0665. (For purposes of this SOW, Contractor is defined as the commercial or government entity performing the rebuild). This document contains requirements to restore the Mount Telescope M172 to condition code 'A'. Condition code 'A' is defined as serviceable/issuable without qualification, new, used, repaired, or reconditioned material which is serviceable and issuable to all customers without limitation or restriction, including materiel with more than six months shelf-life remaining.

1.1 Background. Rebuild is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repairs or replacement of worn or unserviceable elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the items."

2.0 Applicable Documents. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirements.

2.1 Military Standards

MIL-STD-129	DoD Standard Practice for Military Marking

2.2 Other Government Documents and Publications

DMWR 9-1240-375-2	Mount, Telescope and Quadrant, M172, NSN 1240-01-037-7290 Depot Maintenance Work Requirement(DMWR) dtd Aug 84
SPI AMP10554823	Special Packaging Sheet (SPI)
DoD 4000.25-1-M	MILSTRIP Manual
NAVICPINST 4491.2A	Requisitioning of Contractor Furnished Materiel from the Federal Supply System

Military Handbooks (For Guidance)

MIL-HDBK-61	Configuration Management Guidance

2.3 Industry Standards

ANSI/ISO/ASQC Q9002-1994	Quality Systems-Model for Quality Assurance in Production, Installation, and Servicing

Industry Standards (For Guidance)

ANSI/EIA-649	National Consensus Standard for Configuration Management

Copies of Military Standards and Specifications are available from the DOD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2179 or DSN 442-2179, or http://www.dodssp.daps.mil. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the contracting officer: Commander, Marine Corps Logistics Bases, (Code 891) Attn: Contracting Officer, 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number (229) 639-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, may be obtained by contacting: Supply Chain Management Center, Attn: Code 583-1, 814 Radford Blvd STE 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6410 or DSN 567-6410.

3.0 Requirements

3.1 Rebuild

The Contractor shall rebuild the Mount Telescope M172 in accordance with DMWR 9-1240-375-2.

3.2 Quality Assurance/Quality Control

The Contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9002-1994, Quality Systems-Model for Quality Assurance in Production, Installation, and Servicing.

Quality acceptance and test procedures shall be in accordance with DMWR 9-1240-375-2 Chapter 5.

3.3 Configuration Control. The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without receiving prior written authorization. The baseline configuration has been defined by the written procedures or material contained in manuals, standards, instructions or engineering drawings.
If it is necessary to temporarily depart from the authorized configuration, the contractor shall submit a Request for Deviation. MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing this configuration control document.

3.4 Packaging, Handling, Storage and Transportation (PHS&T)

a. The contractor shall be responsible for preservation and packaging of items being repaired under the terms of this statement of work. Items scheduled for all destinations shall be in accordance with the requirements of SPI AMP10554823 which may be obtained from Supply Chain Management Center, Storage and Distribution Department (Code 581), Suite 20320, 814 Radford Blvd., Albany, GA 31704-0320, telephone commercial (229) 639-6786 or DSN 567-6786.

b. Marking for shipment and storage shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of repaired equipment. The Contractor shall be responsible for arranging for shipment to the pre-designated site. The Marine Corps will be responsible for transportation costs associated with shipping the equipment to and from the Contractor.

3.5 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM)

GFE is government owned equipment authorized by contract for use by a commercial/ Government Contractor. It is neither consumed during production nor incorporated into any product. GFM is materiel furnished to a Contractor that will be consumed during the course of production or incorporated into the product being manufactured/remanufactured under a contract/ statement of work. In the event the Marine Corps does have GFE/GFM requirements the Management Control Activity (MCA/Code 573-2), Marine Corps Logistics Bases, Albany, Georgia, will coordinate required GFE and will maintain a central control on Marine Corps assets in the Contractor's possession. The MCA will forward a GFE Accountability agreement to the Contractor Facility for signature to establish a chain of custody and property responsibilities for Marine Corps assets. The contractor shall report receipt of all GFM and report consumption of GFM to the MCA.

3.6 Contractor Furnished Materiel

The Marine Corps has adopted the Navy's procedures regarding Contractor Furnished Materiel (NAVICPINST 4491.2A). In the event Contractor Furnished Materiel is required for repair parts, the Contractor shall requisition through the DoD Supply System. DoD 4000.25-1-M, (MILSTRIP) Chapter 11 authorizes contractors to requisition through the DoD Supply System.

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 1704-0188

The Public reporting burden for this collection of information is authorized to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports 1215 Jefferson Davis Highway, Suite 1204 Arlington, VA 22202-4302 and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government issuing Contract Officer for the contract/PR No. listed in block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ Other XXX
D. SYSTEM/ITEM: Mount Telescope, M172	E. CONTRACT/PR No.	F. CONTRACTOR
1. DATA ITEM No.: A001	2. TITLE OF DATA ITEM: Request for Deviation (RFD)	3. SUBTITLE: Configuration Management
4. AUTHORITY (Data Acquisition Document No.): DI-CMAN-80640C	5. CONTRACT REFERENCE: Paragraph 3.3	6. REQUIRING OFFICE: MARCORLOGBASES (583)
7. DD 250 REQ: LT	9. DIST STATEMENT REQUIRED: A	10. FREQUENCY: AS REQ
12. DATE OF FIRST SUBMISSION: See Blk 16	8. APP CODE	11. AS OF DATE
13. DATE OF SUBSEQUENT SUBMISSION	17. PRICE GROUP	18. ESTIMATED TOTAL PRICE

16. REMARKS

Blk 4: Contractor format is authorized and shall be submitted in .doc and .pdf format.

Blk 10 & 12: RFDs shall be submitted to obtain authorization to deliver nonconforming material which does not meet the prescribed configuration documentation.

RFDs will be reviewed and disposition determined within 30 calendar days upon receipt by the government.

RFDs shall be transmitted via e-mail to the following address: mbmatcomconfigmngmnt@matcom.usmc.mil

Distribution Statement A: Approved for public release, distribution is unlimited.

14. DISTRIBUTION			
a. ADDRESSEE	b. COPIES: Draft	FINAL: Reg	FINAL: Repro
MCLBA (583-1)	0	1	0
15. TOTAL	0	1	0

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
[illegible]	18 July 2001	Darrell W Taylor	24 July 01

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED

Designed using Perform Pro, WHS/DIOR, Aug 96