

**Statement Of Work
For
Rebuild of the Conditioned Diphase Adapter
CV-4089/MRC-142
NSN 5895-01-351-5099**

SOW-01-847-2-8E698B-1/1

**Prepared by
Life Cycle Management Center, Code 847-2
Marine Corps Logistics Bases, Albany, GA.**

Table of Contents

Section/Para	Page
1.0 Scope	1
1.1 Background	1
2.0 Applicable Documents	1
2.1 Military Standards	1
2.2 Industry Standards	1
2.3 Other Government Documents and Publications	2
3.0 Requirements	2
3.1 General Tasks	2
3.2 Detail Tasks	3
3.2.1 Phase I - Pre-induction	3
3.2.2 Phase II - Rebuild	3
3.2.3 Phase III - Inspection, Testing and Acceptance	3
3.2.4 Packaging, Handling, Storage and Transportation (PHS&T)	4
3.3 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM)	4
3.4 Configuration Control	4
3.5 Contractor Furnished Materiel	4
3.6 Electrostatic Discharge (ESD) Control Program	4
3.7 Electromagnetic Environmental Effects (E ³) Procedures	5
3.8 Quality Assurance Provisions	5
3.9 Acceptance	5
3.10 Rejection	5
Appendix A	A-1

STATEMENT OF WORK FOR THE
Rebuild of the Conditioned Diphas Adapter
CV-4089/MRC-142
NSN 5895-01-351-5099

1.0 Scope. This Statement of Work (SOW) establishes and sets forth tasks and identifies the work efforts that shall be performed by the Contractor (for purposes of this SOW, Contractor is defined as the commercial or government entity performing the rebuild in the rebuild effort of the Conditioned Diphas Adapter (CDA). This document contains requirements to restore the Conditioned Diphas Adapter (CDA) to Condition Code "A." Condition Code A is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction, including materiel with more than 6 months shelf-life remaining."

1.1 Background. Rebuild is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repairs or replacement of worn or unserviceable elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the items."

2.0 Applicable Documents. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards

MIL-STD-129	DoD Standard Practice for Military Marking
-------------	--

MIL-STD-2073-1C	DoD Standard Practice for Military Packaging
-----------------	--

Military Standards (For Reference Only)

MIL-STD-973	Configuration Management
-------------	--------------------------

2.2 Industry Standards

ANSI/EIA 625	Requirements for Handling Electrostatic-Discharge Sensitive ESDS Devices
--------------	--

ANSI/ISO/ASQC Q9002-1994	Quality Systems- Model for Quality Assurance in Final Inspection and Test
--------------------------	---

2.3 Other Government Documents and Publications. The issues of those documents cited below shall be used.

TM 09543A-35/1, Vol I of II;	PCN 184 095433 00
TM 09543A-35/1, Vol I of II, CH001	PCN 184 095433 01
TM 09543A-35/2, Vol II of II;	PCN 184 095434 00
SL-4-09543A w/CH003	PCN 124 095430 03
TI-5820-25/22	PCN 168 047801 00
Engineer Drawing 90001A1000 CAGE 01365	Conditioned Diphase Assembly
DOD 4000.25-1-M	MILSTRIP Manual
NAVICPINST 4491-2A	Requisitioning of Contractor Furnished Material from the Federal Supply System

Copies of Military Standards and Specifications are available from the DOD Single Stock Point, Defense Automation Production Service Philadelphia, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2179 or DSN 442-2179, or <http://www.dodssp.daps.mil>. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the contracting officer: Commander, Marine Corps Logistics Bases, (Code 891) Attn: Contracting Officer, 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number (912) 439- 6773 or DSN 567-6773. Copies of engineering drawings, if applicable, shall be obtained from Life Cycle Management Center, Attn: Code 825-3, 814 Radford Blvd. STE 20320, Albany, Georgia 31704-0320, commercial telephone number (912) 439-6410 or DSN 567-6410.

3.0 Requirments.

3.1 General Tasks. In fulfilling the specified requirements, the Contractor shall:

a. Provide materials, labor, equipment, facilities and missing/repair parts, necessary to inspect, diagnose, restore, and test and calibrate the Conditioned Diphase Adapter. Upon completion of rebuild, the subject item shall be Condition Code "A."

b. Conduct in-process and final on-site testing for witness by a Marine Corps authorized representative.

3.2 Detail Tasks. The following tasks describe the different phases for rebuild of the Conditioned Diphas Adapter.

3.2.1 Phase I- Pre-Induction. A pre-induction inspection analysis shall be performed for each Conditioned Diphas Adapter using the Contractor Facility's diagnosis, inspection and testing techniques to determine extent of work and parts required. These findings shall be annotated on the Pre- Induction Checklist (Appendix A).

3.2.2 Phase II -Rebuild. After pre-induction tests and inspections have been completed, repair of the Conditioned Diphas Adapter shall be accomplished in accordance with this SOW. Deficiencies noted on the Pre-Induction Checklist (Appendix A) during Phase I shall be repaired/replaced. Components or assemblies shall not be disassembled for replacement of parts unless that part has failed, or the component assembly wherein the part is located is disassembled for repair. Incorporate all current Engineering Change Proposals (ECPs) and Modification Instruction (MIs).

a. Hardware

(1) Replace broken, unserviceable and/or missing hardware including nuts, bolts, screws, washers, turn lock fasteners, mandatory replacement items, safety, and one-time use items, etc., in accordance with this SOW. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

3.2.3 Phase III - Inspection, Testing and Acceptance

a. Inspection, Testing and Acceptance of the Conditioned Diphas Adapter shall be conducted in accordance with this Statement of Work and TM 09543A-35/1, Vol I of II, TM 09543A-35/1, Vol I of II, CH001, TM 09543A-35/2, Vol II of II, SL-4-09543A CH003, TI-5820-25/22 and Engineer Drawing 90001A1000 CAGE 01365.

b. The Contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are notified prior to completion of the final acceptance. Acceptance tests shall be held at the contractor's facility, MCLB (Code 891), Albany, Georgia, representatives shall be given a minimum of two weeks notice prior to commencement of acceptance testing.

c. The Contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCLB (Code 891), Albany, Georgia, representatives may require the Contractor to repeat tests or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

3.2.4 Packaging, Handling, Storage and Transportation (PHS&T).

a. The Contractor shall be responsible for preservation and packaging of items being repaired under the terms of this statement of work. Items being prepared for long term storage or shipment to overseas destinations shall be in accordance with MIL-STD-2073-1C, Appendix A., Table A.VI., Electronic Equipment. Items being prepared for domestic shipment and immediate use shall be to level "B" requirements.

b. Marking shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of the repaired equipment. The Contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for costs associated with shipping the subject equipment to and from the Contractor.

3.3 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). GFE is government owned equipment authorized by contract for use by a Commercial/Government contractor. It is neither consumed during production nor incorporated into any product. GFM is materiel furnished to a contractor that will be consumed during the course of production or incorporated into product being manufactured/remanufactured under a contract/statement of work. In the event the Marine Corps does have GFE/GFM requirements the Management Control Activity (MCA/827-2), Marine Corps Logistics Bases, Albany, Georgia, will coordinate required GFE and will maintain a central control on Marine Corps assets in the Contractor's possession. The MCA will forward a GFE Accountability agreement to the Contractor Facility for signature to establish a chain of custody and property responsibilities for Marine Corps assets.

3.4 Configuration Control. The contractor shall implement configuration control to established configuration items. Deviation from the established baseline configuration will not be allowed without the approval in writing from the Weapon System/Equipment Manager (Code 847-2). If necessary to temporarily depart from the authorized configuration, the contractor shall prepare and submit a Request for Deviation/Request for Waiver using MIL-STD-973, paragraph 5.4.3 and 5.4.4 and Appendix E, as a guide.

3.5 Contractor Furnished Materiel. The Marine Corps has adopted the Navy's procedures regarding Contractor Furnished Materiel (NAVICPINST 4491-2A). In the event that Contractor Furnished Materiel is required for repair parts, the contractor shall requisition through the DOD Supply System.DOD 4000.25-1-M, (MILSTRIP) Chapter 11 authorizes contractors to requisition through the DOD Supply System.

3.6 Electrostatic Discharge (ESD) Control Program. The contractor shall establish, implement and document an ESD control program following the guidelines provided in ANSI/EIA-625. ESD protective measures shall be used during manufacturing, handling, inspection, test, marking, packaging, storing and transporting ESD sensitive components.

3.7 Electromagnetic Environmental Effects (E3) Procedures. The Contractor shall plan for and use proper (E3) control procedures in the Rebuild process and shall utilize TI-5820-25/22 in conjunction with the detailed requirements specified in this document.

3.8 Quality Assurance Provisions

The Contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9003-1994, Quality System Model for Quality Assurance in Final Inspection and Test. The program shall ensure quality throughout all areas to include fabrication, processing, assembly, inspection, test, maintenance, and preparation for delivery and shipping. Unless otherwise specified in the contract, the contractor shall be responsible for performance of all inspection requirements. The Government reserves the right to perform any of the inspections set forth in the contract where such inspections are deemed necessary to assure products and services conform to the prescribed requirements. The Contractor shall provide an Inspection and Test Plan that will ensure the Conditioned Diphase Adapter will meet or exceed the original performance characteristics of the Conditioned Diphase Adapter.

3.9 Acceptance.

The performance of the Contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and Marine Corps representatives shall be permitted to observe the work or to conduct an inspection. Final inspection and acceptance testing shall be conducted at the Contractor's Facility. Final acceptance shall be conducted on 100 percent of items to verify that the units meet all requirements.

3.10 Rejection

Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCLB (Code 891), Albany, representative. The Contractor shall, at no additional cost to MCLB, Albany, Georgia, correct the deficiencies and repeat the verification until acceptable compliance with acceptance test procedures is demonstrated.

Pre-Induction Checklist
CV-4089/MRC-142

1. Inspect for dirt, dust, sand, etc.
2. Inspect for rust and/or corrosion damage.
3. Inspect for any physical damage to unit, cuts, dents, cracks, or broken pins.
4. Ensure that all screws, washers, nuts, bolts, etc. are attached.
5. Inspect for dry rot.
6. Ensure that all covers and caps are attached.
7. Ensure that all knobs and switches operate freely and properly.

S - Serviceable

U - Unserviceable

M - Missing

Front Panel Inventory/Serviceability check:

	Condition	Remarks
1. Handset Connector, and cover, J9	_____	_____
3. Trunk Loop Rate Switch	_____	_____
4. Volume Control	_____	_____
5. Orderwire Mode Switch	_____	_____
6. AVOW and DVOW Call Lamp	_____	_____
7. Orderwire Call Switch	_____	_____
8. Timing Select Switch	_____	_____
9. Operating Mode Control Switch	_____	_____
10. Loopback Selector Switch	_____	_____
11. Power On/Off Circuit Breaker	_____	_____
12. Audible Alarm Speaker	_____	_____
13. Reset Switch	_____	_____
14. Alarm Status Monitors	_____	_____
15. Test Switch	_____	_____
16. NSW Indicator	_____	_____
17. FRM Indicator	_____	_____
18. INCM Indicator	_____	_____
19. FLT Indicator	_____	_____
20. PWR Indicator	_____	_____

Rear Panel Inventory/Serviceability Check:

1. Power Connector, and cover, J1	_____	_____
2. KY-57 Black, and cover, J2	_____	_____
3. KG-194A Black, and cover, J3	_____	_____
4. KG-194A Red, and cover, J4	_____	_____
5. KY-57 Red, and cover, J5	_____	_____
6. RPTR, and cover, J6	_____	_____
7. Radio, and cover, J7	_____	_____
8. Ground, E1	_____	_____
9. Cable conn. and cover, J8	_____	_____

APPENDIX A

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0701-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.

A. CONTRACT LINE ITEM NO.		B. EXHIBIT		C. CATEGORY: TDP _____ TM _____ OTHER <input checked="" type="checkbox"/>						
D. SYSTEM/ITEM Conditioned Diphas Adapter		E. CONTRACT/PR NO.		F. CONTRACTOR						
1. DATA ITEM NO. A001	2. TITLE OF DATA ITEM Request For Deviation			3. SUBTITLE Configuration Management						
4. AUTHORITY (Data Acquisition Document No.) DI-CMAN-80640B		5. CONTRACT REFERENCE SOW 3.4		6. REQUIRING OFFICE MCLBA (825)						
7. DD 250 REQ LT	8. DIST STATEMENT REQUIRED	10. FREQUENCY ASREQ	12. DATE OF FIRST SUBMISSION SEE BLK 16	14. DISTRIBUTION						
8. APP CODE	A	11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION	a. ADDRESSEE	b. COPIES					
				Draft	Final Reg Repro					
16. REMARKS Blk 4 - Contractor format is authorized. Blks 10 & 12 - RFDs shall be submitted to obtain authorization to deliver nonconforming material which does not meet prescribed configuration documentation. RFDs will be reviewed and disposition determined within 20 calendar days upon receipt by the Government. RFDs shall be transmitted via E-Mail to the following address: mbmatcomconfigmgmnt@matcom.usmc.mil Distribution Statement A: Approved for public release, distribution is unlimited				MCLBA (825-2)	0	1	0			
				15. TOTAL				0	1	0
				G. PREPARED BY <i>Steve Cullis</i>		H. DATE 24 Jan 00	I. APPROVED BY <i>Robert B. Edwards</i>		J. DATE 000216	

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved

OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0701-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TOP _____ TM _____ OTHER <input checked="" type="checkbox"/>
---------------------------	------------	--

D. SYSTEM/ITEM Conditioned Dipphase Adapter	E. CONTRACT/PR NO.	F. CONTRACTOR
--	--------------------	---------------

1. DATA ITEM NO. A002	2. TITLE OF DATA ITEM Request For Waiver	3. SUBTITLE Configuration Management
--------------------------	---	---

4. AUTHORITY (Data Acquisition Document No.) DI-CMAN-80641B	5. CONTRACT REFERENCE SOW 3.4	6. REQUIRING OFFICE MCLBA (825)
--	----------------------------------	------------------------------------

7. DD 250 REQ LT	9. DIST STATEMENT REQUIRED A	10. FREQUENCY ASREQ	12. DATE OF FIRST SUBMISSION SEE BLK 16	14. DISTRIBUTION a. ADDRESSEE MCLBA (825-2)	b. COPIES Draft 0	Final Reg 1	Repro 0
8. APP CODE	11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION					

16. REMARKS <p>Blk 4 - Contractor format is authorized.</p> <p>Blks 10 & 12 - RFWs shall be submitted to obtain authorization to deliver nonconforming material which does not meet prescribed configuration documentation.</p> <p>RFWs will be reviewed and disposition determined within 20 calendar days upon receipt by the Government.</p> <p>RFWs shall be transmitted via E-Mail to the following address: mbmatcomconfigmngmnt@matcom.usmc.mil</p> <p>Distribution Statement A: Approved for public release, distribution is unlimited</p>	15. TOTAL 0 1 0
---	--------------------

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

G. PREPARED BY <i>Aime Collins</i>	H. DATE 24 Jan 00	I. APPROVED BY <i>Robert A. Elumbe</i>	J. DATE 000216
---------------------------------------	----------------------	---	-------------------