Statement of Work (SOW)

for the

Rebuild

of the

Trailer, Wrecker, MK-15 and MK-15A1
P/O Logistics Vehicle System (LVS)

NSN 2320-01-176-6928

and

NSN 2320-01-417-8144

Control NR: SOW-07-PMM151-08782A/B-1

Effective Date: 1 October 2006

TABLE OF CONTENTS

SECTION/PARAGRAPH		PAGE
1.0	SCOPE	1
1.1	Background	1
2.0	APPLICABLE DOCUMENTS	1
2.1	Military Standards	1
2.2	Other Government Documents and Publications	1
2.3	Industry Standards	2
3.0	REQUIREMENTS	2
3.1	General Tasks	2
3.2	Detailed Tasks	3
3.2.1	Phase I - Pre-Induction	3
3.2.2	Phase II - Rebuild	3
3.2.3	Phase III - Inspection, Testing and Acceptance	4
3.2.4	Packaging, Handling, Storage and Transportation (PHS&T)	4
3.3	Configuration Control	4
3.4	Government Furnished Equipment(GFE)/ Government Furnished Materiel(GFM)	5
3.5	Contractor Furnished Materiel(CFM)	5
3.6	Quality Assurance Provisions	5
3.7	Rejection	5
4.0	REPORTS	5
4.1	Road Test and Final Inspection Checklist	5

Statement of Work (SOW)
for the Rebuild of the
Trailer, Wrecker, MK-15 and MK-15A1, P/O Logistics Vehicle System (LVS)
NSN 2320-01-176-6928 and NSN 2320-01-417-8144

1.0 SCOPE. This Statement of Work (SOW), along with RS 08782A-50, establishes, sets forth tasks and identifies the work efforts that shall be performed by the Contractor in the rebuild effort of the Trailer, Wrecker, MK-15 and MK-15A1, P/O Logistics Vehicle System (LVS). This document contains minimum requirements to restore the Trailer, Wrecker, MK-15 and MK-15A1, P/O Logistics Vehicle System (LVS), (hereafter referred to as the MK-15), to Condition Code "A". Condition Code "A" is defined as "serviceable/issuable without qualification, new, used, repaired, or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction and includes materiel with more than six months shelf-life remaining".

1.1 Background. Rebuild is defined as "that maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repair or replacement of worn or unserviceable parts/elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the item".

2.0 APPLICABLE DOCUMENTS. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards

MIL-STD-129	DoD Standard Practice: Military Marking for Shipment and Storage
MIL-STD-3003	Vehicles, Wheeled; Preparation for Shipment and Storage of

2.2 Other Government Documents and Publications

MI-2320-35/75	Fabrication/Installation of Tool Box Support For the Logistics Vehicle (LVS) MK14, MK-15, MK17 Trailers
MI-2320-25/68	Spacer Blocks on Hydraulic Hose Clamps on the MK-15/17 LVS Crane

MI-2320-25/81	Install Anti-Locking Brake System on Truck 8x8 Logistics Vehicle System. This kit will be provided by SCMC.
RS 08782A-50	Depot Maintenance Manual MK-15
TM 3080-50	Corrosion Prevention and Control
DoD 4000.25-1-M	Military Standard Requisitioning and Issue Procedures (MILSTRIP)

Military Handbooks (For Guidance)

MIL-HDBK-61	Configuration Management Guidance

2.3 Industry Standards

ANSI/ISO/ASQC Q9001-2000	Quality Management Systems – Requirements

Industry Standards (For Guidance)

ANSI/EIA-649	National Consensus Standard for Configuration Management

Copies of Military Standards and Specifications are available from the DoD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, commercial telephone number (215) 697-2179 or DSN 442-2179, or on the Internet at http://www.dodssp.daps.mil. Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Contracts Department (Code 891), P. O. Drawer 43019, 814 Radford Blvd., Marine Corps Logistics Command, Albany, Georgia 31704-3019, commercial telephone number (229) 639-6761 or DSN 567- 6761. Copies of engineering drawings, if applicable, shall be obtained from the Supply Chain Management Center, Attn: Code 566-1A, 814 Radford Blvd., STE 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6476 or DSN 567-6476.

3.0 REQUIREMENTS

3.1 General Tasks. The Contractor shall disassemble all assemblies/subassemblies, inspect, test, repair and/or replace. All worn parts/components that are beyond the specified tolerances and wear limits shall be replaced. Unless otherwise provided for in this SOW all parts and components may be reused if they meet the criteria established in RS 08782A-50.

a. Provide materials, labor, facilities, repair parts, and missing parts necessary to inspect, diagnose, restore, and test the MK-15. Upon completion of rebuild, repaired vehicles shall be Condition Code "A".

b. Provide all tools and test equipment required to test, inspect and calibrate the MK-15.

c. Conduct final on-site testing for witness by a Marine Corps Systems Command (MCSC), Code PMM151, Albany, Georgia representative.

d. Be responsible for all structural, electrical and mechanical requirements associated with the restoration of the MK-15.

e. Be responsible for all corrosion prevention and control in accordance with TM 3080-50.

3.2 Detailed Tasks. The following tasks describe the different phases for rebuild of the MK-15.

3.2.1 Phase I- Pre-Induction. A Pre-Induction Inspection Analysis is not required since the MK-15 is a rebuild effort.

3.2.2 Phase II - Rebuild. Rebuild of the MK-15 shall be accomplished in accordance with this SOW and RS 08782A-50 at the Contractor's facility. Rebuild of the MK-15 shall be accomplished by the application of Contractor maintenance techniques by experienced journeyman level personnel to meet quality standards and inspection criteria contained in RS 08782A-50.

a. Data Plate. MK-15 shall have a rebuild data plate located next to the original manufacturer's data plate. This plate (refer to Figure 1) shall be constructed of metal and attached after the vehicle has completed the rebuild cycle. The data plate shall contain the following information:

VEH. SER. NO._____ DATE

REBUILT IN ACCORDANCE WITH RS 08782A-50

CONTRACTOR_____

(Figure 1)

b. Hardware

(1) Replace broken, unserviceable, and/or missing hardware including nuts, bolts, screws, washers, turnlock fasteners in accordance with the RS 08782A-50. Unserviceable would include any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

c. Application of Modification Instructions (MIs). The following MIs shall be applied during this phase of the rebuild process: MI-2320-35/75, MI-2320-25/68 and MI-2320-25/81.

3.2.3 Phase III - Inspection, Testing and Acceptance

a. Inspection, Testing and Acceptance of the MK-15 shall be conducted in accordance with the Road Test and Final Inspection Checklist located in Table 2-4 of RS 08782A-50. This completed document shall be provided in accordance with Section 4.0 of this SOW.

b. The Contractor shall be responsible for conducting required tests and shall ensure all necessary personnel from the production line and quality assurance are available to complete the final acceptance. Acceptance tests shall be held at the Contractor's facility. MCSC, Code PMM151, Albany, Georgia representatives shall be given a minimum of two weeks notice prior to beginning acceptance testing. The test area shall be cleared of all equipment parts, components not required for testing.

c. The Contractor shall be responsible for correcting any deficiencies identified during inspection/testing. MCSC, Code PMM151, Albany, Georgia may require the Contractor to repeat tests, or portions thereof, if the original tests fail to demonstrate compliance with this SOW.

d. Acceptance testing on all MK-15 vehicles repaired under the provisions of this SOW shall be accomplished in accordance with RS 08782A-50.

3.2.4 Packaging, Handling, Storage and Transportation (PHS&T)

a. The Contractor shall be responsible for the preservation and packaging of item(s) being rebuilt under the terms of this SOW. Items scheduled for long-term storage or shipment to overseas destinations shall be in accordance with the Level "A" requirements of MIL-STD-3003. Items scheduled for domestic shipment for immediate use or short-term storage shall be in accordance with Level "B" requirements.

b. Marking for shipment and storage shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the Contractor with the shipping address(es) for delivery of the repaired equipment, and the Contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the subject equipment to and from the Contractor.

3.3 Configuration Control. The Contractor shall apply configuration control procedures to established configuration items. The Contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the Contractor shall prepare and submit a Request For Deviation. MIL-HDBK-61 and ANSI/EIA-649 provide guidance for preparing this configuration control document.

3.4 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). The Management Control Activity (MCA)(Code 581-1B) will coordinate GFE/GFM requests and maintain a central control system on all government owned assets in the Contractor's possession. The MCA will forward a GFE Accountability Agreement to the Contractor for signature on an annual basis to establish a chain of custody and identify property responsibilities for Marine Corps assets. The Contractor is to acknowledge receipt of GFM to the MCA within 15 days of receipt. This can be done by mailing a copy of the DD 1348 to Materiel and Distribution Management Department, Distribution Management Branch, Management Control Activity (Code 581-1B), 814 Radford Blvd., STE 20320, Albany, Georgia 31704-0320 or faxing a copy to commercial (229)639-5498 or DSN 567-5498. If Depot Source of Repair (DSOR) mandated, assets at repair facility will not be considered GFE/GFM.

3.5 Contractor Furnished Materiel (CFM). The Contractor may requisition materiel as required in the performance of the SOW through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP), Chapter 11, provides guidance to Contractors on the requisitioning process. The Contractor's decision to utilize CFM procured from the DoD Supply System shall be based upon cost effectiveness, availability of materiel and the required completion/delivery date.

3.6. Quality Assurance Provisions. The Contractor shall provide and maintain a Quality System that, as a minimum, adheres to the requirement of ANSI/ISO/ASQC Q9001-2000, Quality Management Systems – Requirements. MCSC, Code PMM151, Albany, Georgia retains the right to conduct in-process reviews and inspections for compliance with these procedures and standards. MCSC, Code PMM151, Albany, Georgia further retains the right for in-process reviews and inspections of the quality of work delivered, material provided and documents written during contract performance. Failure of the contractor to promptly correct deficiencies discovered shall be reason for suspension of acceptance until corrective action has been accomplished.

3.7 Rejection. Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCSC, Code PMM151, Albany, Georgia. The Contractor shall, at no additional cost to MCSC, Code PMM151, Albany, Georgia provide the following:

a. Develop an approach for modification or correction of all deficiencies.

b. Upon approval of a documented approach, the contractor shall correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures requirements is demonstrated.

4.0 REPORTS

4.1 Road Test and Final Inspection Checklist. The Contractor shall complete the Road Test and Final Inspection Checklist for each MK-15 repaired. These documents shall be available during final acceptance testing. One copy of each document shall be provided to Commanding General, Marine Corps Logistics Command, Attn: Code PMM151, 814 Radford Blvd., STE 20343, Albany, Georgia 31704-0343, after final acceptance of the MK-15.

CONTRACT DATA REQUIREMENTS LIST
(1 Data Item)

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0701-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ OTHER X
D. SYSTEM/ITEM: LVS, MK-15 & MK-15A1	E. CONTRACT/PR NO.	F. CONTRACTOR

1. DATA ITEM NO.	2. TITLE OF DATA ITEM	3. SUBTITLE	17. PRICE GROUP
A001	Request For Deviation	Configuration Management	18. ESTIMATED TOTAL PRICE

4. AUTHORITY *(Data Acquisition Document No.)*	5. CONTRACT REFERENCE	6. REQUIRING OFFICE
DI-CMAN-80640C	SOW 3.3	MCLCA (566)

7. DD 250 REQ	9. DIST STATEMENT REQUIRED	10. FREQUENCY	12. DATE OF FIRST SUBMISSION
LT	A	ASREQ	See Blk 16
8. APP CODE		**11. AS OF DATE**	**13. DATE OF SUBSEQUENT SUBMISSION**
A			See Blk 16

16. REMARKS

Blk 4: RFDs shall be submitted electronically. Contractor format is authorized.

Blk 4: RFD text files shall be created using MICROSOFT (.doc) or ADOBE (.pdf) formatted software products.

Blk 4: RFD accompanying figures or graphics shall be created using a MICROSOFT or ADOBE formatted with a minimum density of 600 dpi.

Blks 10 & 12: RFDs shall be submitted to obtain authorization to deliver nonconforming material that does not meet the prescribed configuration documentation.

Block 14: RFDs shall be transmitted via e-mail to the following address: mbmatcomconfigmngmnt@logcom.usmc.mil

Distribution Statement A: Approved for Public Release; Distribution is Unlimited.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES: Draft	Final: Reg	Final: Repro
MCLCA (566-1)	0	1	0
15. TOTAL →	0	1	0

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
[signature]	8-6-04	[signature]	28 Jul 04

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED.

Designed using Perform Pro, WHS/DIOR, Aug 96