

STATEMENT OF WORK FOR THE
REBUILD OF
SIXCON FUEL TANK MODULE
5430-01-240-4578

1.0 SCOPE: This Statement of Work (SOW), along with TM 09003A/09002A-15&P/1 and Marine Corps (MC) drawing 845009A0000 (01365) establishes and sets forth tasks and identifies the work efforts that shall be performed by the contractor. For purposes of this SOW contractor is defined as the commercial or government entity performing the rebuild effort of the SIXCON Fuel Tank Module. These documents contain requirements to restore the Fuel Tank Module to Condition Code "A." Condition Code A is defined as "serviceable/issuable without qualification, new, used, repaired or reconditioned materiel which is serviceable and issuable to all customers without limitation or restriction, including materiel with more than 6 months shelf-life remaining."

1.1 Background: Rebuild is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy. This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repairs or replacement of worn or unserviceable elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the items."

2.0 APPLICABLE DOCUMENTS: The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards

- | | |
|-----------------|--|
| MIL-STD-129 | DOD Standard Practice for Military Marking |
| MIL-STD-130 | DOD Identification Marking of U.S. Military Property |
| MIL-STD-2073-1C | DOD Standard Practice for Military Packaging |

Military Standards (For Guidance Only)

- | | |
|-------------|--------------------------|
| MIL-STD-973 | Configuration Management |
|-------------|--------------------------|

2.2 Other Government Documents and Publications: The issues of those documents cited below shall be used.

- | | |
|-------------------------|---|
| TM 09003A/09002A-15&P/1 | Operation and Maintenance Instructions With Repair Parts List and Components List for SIXCON Fuel Pump Module and SIXCON Fuel Tank Module |
|-------------------------|---|

845009A0000
Cage 01365

SIXCON Fuel Tank Module (MC Drawing)

TM-4750-15/2

Painting and Registration Marking for Marine Corps
Combat and Tactical Equipment

2.3 Industry Standards:

ANSI/ISO/ASQC Q9002-1994 Quality Systems-Model for Quality Assurance in
Production, Installation and Servicing

Copies of Military Standards and Specifications are available from the DOD Single Stock Point, Defense Automatin Production Service Philadelphia, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2179, or DSN 442-2179, or <http://www.dodssp.daps.mil> . Copies of other government documents and publications required by contractors in connection with specific SOW requirements shall be obtained through the Contracting Officer: Commander, Attn: Contracting Officer (Code 891), Marine Corps Logistics Bases 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number (912) 439-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, shall be obtained from Life Cycle Management Center, Attn: Code 825-3, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320, commercial telephone number (912) 439-6410 or DSN 567-6410.

3.0 REQUIREMENTS

3.1 General Tasks: In fulfilling the specified requirements, the contractor shall provide materials, labor, equipment, facilities and missing/repair parts, necessary to inspect, diagnose, restore, and test and calibrate the Fuel Tank Module. Upon completion of rebuild, the subject item shall be Condition Code "A".

3.2 Detail Tasks: The following tasks describe the different phases for rebuild of the Fuel Tank Module.

a. Data Plate: Each repaired Fuel Tank Module shall have a rebuild data plate affixed to the upper front frame cross member, located by manufacture's data plate. The data plate shall meet the requirements of MIL-STD-130 and TM 4750-15/2.

b. Hardware

(1) Replace broken, unserviceable and/or missing hardware to include mechanical assemblies, nuts, bolts, screws, washers, turn lock fasteners, mandatory replacement items, safety, and one-time use items, in accordance with the TM 09003A/09002A-15&P/1 and Drawings 845009A0000 (01365). Unserviceable is defined as any of the above that failed to function properly.

(2) Ensure proper hardware locking devices are present on all moving mechanical assemblies.

(3) Hardware normally supplied with commercial parts shall be used unless specifically prohibited.

3.2.3 Inspection, Testing and Acceptance:

a. Inspection, Testing and Acceptance of the Fuel Tank Module shall be conducted in accordance with TM 09003A/09002A-15&P/1 and Drawing 845009A0000 (01365).

b. The contractor shall be responsible for conducting required tests and shall ensure all necessary personnel are notified prior to completion of final acceptance. Acceptance tests shall be held at the contractor's facility. Final acceptance shall be conducted on one hundred percent of the end items to verify that the units meet all requirements.

c. The contractor shall be responsible for correcting any deficiencies identified during inspection/testing.

d. Acceptance testing on all Fuel Tank Modules repaired under the provisions of this SOW shall be accomplished in accordance with TM 09003A/09002A-15&P/1, and Drawing 845009A0000 (01365).

3.2.4 Packaging, Handling, Storage and Transportation (PHS&T):

a. The contractor shall be responsible for preservation and packaging of items being repaired under the terms of this statement of work. Items scheduled for long term storage or shipment to overseas destinations shall be in accordance with level "A" requirements of MIL-STD-2073-1C, Method "10". Items being prepared for domestic shipment, immediate use or short-term storage shall be to level "B" requirements.

b. Marking shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the contractor with the shipping address(es) for delivery of the repaired equipment. The contractor shall be responsible for arranging for shipment of the equipment to the pre-designated site(s). The Marine Corps will be responsible for transportation costs associated with shipping the subject equipment to and from the Contractor.

3.3 Configuration Control: The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without receiving prior written authorization. The baseline configuration has been defined by the written procedures or material contained in manuals, standards, instructions or engineering drawings. If it is necessary to depart from the authorized configuration baseline, the contractor shall submit a Request for Deviation or Request for Waiver using MIL-STD-973, paragraph 5.4.3 or 5.4.4, as a guide.

3.4 Quality Assurance Provisions: The contractor shall provide and maintain a Quality System that as a minimum, adheres to the requirements of ANSI/ISO/ASQC Q9002-1994, Quality System Model for Quality Assurance in Production, Installation, and Servicing, for supplies and services. The program shall ensure quality throughout all areas to include fabrication, processing, assembly, inspection, test, maintenance, and preparation for delivery and shipping. Unless otherwise specified in the contract, the contractor shall be responsible for performance of all inspection requirements. The government reserves the right to perform any of the inspections set forth in the contract where such inspections are deemed necessary to assure products and services conform to the prescribed requirements.

3.5 Acceptance: The performance of the contractor and the quality of work delivered, including all equipment furnished and documentation written or compiled, shall be subject to in-process review and inspection during performance. Inspection may be accomplished in-plant or at any work site or location, and Marine Corps representatives shall be permitted to observe the work or to conduct an inspection. Final inspection and acceptance testing shall be conducted at the contractor's facility. Final acceptance shall be conducted on one hundred percent of the end items to verify that the units meet all requirements.

3.6 Rejection: Failure to comply with any of the specified requirements listed herein shall be reason for rejection by MCLB (Code 837-2) Albany, representative. The contractor shall, at no additional cost to MCLB, Albany, Georgia, correct the deficiencies and repeat the verification until an acceptable compliance with acceptance test procedures is demonstrated.

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0701-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TOP _____ TM _____ OTHER <input checked="" type="checkbox"/>
----------------------------------	-------------------	---

D. SYSTEM/ITEM SIXCON Fuel Tank Module	E. CONTRACT/PR NO.	F. CONTRACTOR
--	---------------------------	----------------------

1. DATA ITEM NO. A002	2. TITLE OF DATA ITEM Request For Waiver	3. SUBTITLE Configuration Management
---------------------------------	--	--

4. AUTHORITY (Data Acquisition Document No.) DI-CMAN-80641B	5. CONTRACT REFERENCE SOW 3.3	6. REQUIRING OFFICE MCLBA (825)
---	---	---

7. DD 250 REQ LT	8. DIST STATEMENT REQUIRED	9. FREQUENCY ASREQ	10. DATE OF FIRST SUBMISSION SEE BLK 16	14. DISTRIBUTION		
8. APP CODE A		11. AS OF DATE	13. DATE OF SUBSEQUENT SUBMISSION	a. ADDRESSEE MCLBA (825-2)	b. COPIES	
					<i>Draft</i>	Final
						Reg
						Repro

16. REMARKS

Blk 4 - Contractor Format using .doc or .pdf software applications is authorized.

Blks 10 & 12 - RFWs shall be submitted to obtain authorization to deliver nonconforming material which does not meet prescribed configuration documentation.

RFWs will be reviewed and disposition determined within 30 calendar days upon receipt by the Government.

RFWs shall be transmitted via E-Mail to the following address:
mbmatcomconfigmngmnt@matcom.usmc.mil

Distribution Statement A: Approved for public release, distribution is unlimited

15. TOTAL	0	1	0			

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

G. PREPARED BY <i>Carl L. Little</i>	H. DATE 2-16-00	I. APPROVED BY <i>James P. Adams</i>	J. DATE 2/03/00
--	---------------------------	--	---------------------------