STATEMENT OF WORK (SOW)
REBUILD OF
TRANSMISSION OUTPUT REDUCTION W/CONTAINER
RIGHT HAND (FINAL DRIVE)
NSN 2520-00-896-9021

1.0 SCOPE. This Statement of Work (SOW) establishes and sets forth task and identifies the work efforts that shall be preformed by the Contractor to rebuild the Transmission Output Reduction, Right Hand (Final Drive) for the Transmission XT-1410-2, NSN 2520-00-896-9021 in support of the M88A1, ID# 07769A, TAMCN E1377, NSN 2350-00-122-6826. (For purposes of this SOW, Contractor is defined as the commercial or government entity performing the rebuild.) This document contains requirements to rebuild the Transmission Output Reduction, RH (Final Drive) for the Transmission XT-1410-2 to condition code "A". Condition code "A" is defined as serviceable and issuable to all customers without limitation or restriction, including material with more then six months shelf life remaining.

1.1 BACKGROUND. Rebuild is defined as "That maintenance technique to restore an item to a standard as near as possible to original or new condition in appearance, performance, and life expectancy". This is accomplished through a maintenance technique or complete disassembly of the item, inspection of all parts or components, repair or replacement of worn or unserviceable parts/elements using original manufacturing tolerances and/or specifications and subsequent reassembly of the item.

2.0 Applicable Documents. The following documents form a part of this SOW to the extent specified. Unless otherwise specified, the issues of these documents are those listed in the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto which is in effect on the date of solicitation. In the event of conflict between the documents referenced herein and the contents of this SOW, the contents of this SOW shall be the superseding requirement.

2.1 Military Standards.

MIL-STD-129	DoD Standard Practice for Military Marking

2.2 Other Government Documents and Publications.

AK08969021	Special Packaging Instruction
DMWR 9-2520-215	Depot Maintenance Work Requirement (DMWR)-Transmission, Cross Drive, Assemblies Model XT-1410-2 Composed of: Output Reduction, RH, Assembly and Container (2520-00-896-9021)
DoD 4000.25-1-M	MILSTRIP Manual

NAVICPINST 4491.2A	Requisitioning of Contractor Furnished Materiel From the Federal Supply System

Military Handbooks (For Guidance)

MIL-HDBK-61	***Configuration Management Guidance***

2.3 Industry Standards.

ANSI/ISO/ASQC Q9003-1994	Quality Systems - Model for Quality Assurance in Final Inspection and Test

Industry Standards (For Guidance)

ANSI/EIA-649	***National Consensus Standard for Configuration Management***

Copies of Military Specifications and Standards are available from DOD Single Stock Point, Document Automation and Production Service, Building 4/D, 700 Robbins Avenue, Philadelphia, Pa. 19111-5094, Telephone (215) 697-2179 or DSN 422-2179, or http://www.dodssp.daps.mil. Copies of other government documents and publications required by the contractor in connection with specifics SOW requirements shall be obtained through the Contracting Officer: Commander, Attn: Contracting Officer (Code891) Marine Corps Logistics Bases, 814 Radford Blvd., Albany, Georgia 31704-1128, commercial telephone number (229) 639-6761 or DSN 567-6761. Copies of engineering drawings, if applicable, shall be obtained from Life Cycle Management Center, Attn: Code 851-3, 814 Radford Blvd. Suite 20320, Albany, Georgia 31704-0320, commercial telephone number (229) 639-6410 or DSN 567-6410.

3.0 Requirements.

3.1 The Contractor shall rebuild the Transmission Output Reduction, RH (Final Drive) in accordance with DMWR 9-2520-215.

3.2 Quality acceptance and test procedures will be performed in accordance with DMWR 9-2520-215.

3.3 Quality Assurance Provision. The contractor shall provide and maintain a Quality System that as a minimum adheres to the requirements of ANSI/ISO/ASQC Q9003-1994, Quality Systems Model for Quality Assurance in Final Inspection and Test.

3.4 Configuration Control. ***The contractor shall apply configuration control procedures to established configuration items. The contractor shall not implement configuration changes to an item's documented performance or design characteristics without prior written authorization. If it is necessary to temporarily depart from the authorized configuration, the contractor shall prepare and submit a Request For Deviation. MIL-HDBK-61 (paragraph 4.3***

and Table 4-9) and ANSI/EIA-649 (paragraph 5.3.4) provide guidance for preparing these configuration control documents.

3.5 Government Furnished Equipment (GFE)/Government Furnished Materiel (GFM). GFE is government owned equipment authorized by the contract for use by a commercial/government contractor. It is neither consumed during production nor incorporated into any product. GFM is materiel furnished to a contractor that will be consumed during the course of production or incorporated into the product being manufactured/remanufactured under a contract/statement of work. In the event the Marine Corps does have GFE/GFM requirements the Management Control Activity (MCA/Code 827-2), Marine Corps Logistics Bases, Albany, Georgia will coordinate required GFE and will maintain a central control on Marine Corps assets in the Contractor's possession. The MCA will forward a GFE Accountability agreement to the Contractor Facility for signature to establish a chain of custody and property responsibilities for Marine Corps assets.

3.6 Contractor Furnished Materiel (CFM). The Marine Corps has adopted the Navy's procedures regarding Contractor Furnished Materiel NAVICPINST 4491.2A. In the event that Contractor Furnished Materiel (CFM) is required for repair parts, the contractor shall requisition repair parts through the DoD Supply System. DoD 4000.25-1-M (MILSTRIP), Chapter 11 authorizes contractors to requisition through the DoD Supply System.

3.7 Packaging, Handling, Storage and Transportation.

a. The contractor shall be responsible for preservation and packaging of items being repaired under the terms of this Statement of Work. All items scheduled for shipment to all destinations shall be in accordance with level "A" requirements of the Special Packaging Instruction (SPI) AK08969021. The SPI may be obtained from Materiel Management Division, Attn: Logistics Support Section, Suite 20320, 814 Radford Blvd; Albany, Georgia 31704-0320, Commercial telephone (229) 639-6786 or DSN 567-6786.

b. Marking shall be in accordance with MIL-STD-129.

c. The Marine Corps will provide the contractor with the shipping address(es) for delivery of the rebuilt equipment. The contractor shall be responsible for arranging for shipment to the pre-designated site(s). The Marine Corps will be responsible for transportation cost associated with shipping the subject equipment to and from the Contractor.

CONTRACT DATA REQUIREMENTS LIST

(1 Data Item)

Form Approved
OMB No. 1704-0188

The Public reporting burden for this collection of information is authorized to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302 and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government issuing Contract Officer for the contract/PR No. listed in block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP ____ TM ____ Other XXX
D. SYSTEM/ITEM: Transmission Output Reduction, RH (Final Drive) for the Transmission XT-1410-2	E. CONTRACT/PR No.	F. CONTRACTOR
1. DATA ITEM No.: A001	2. TITLE OF DATA ITEM: Request for Deviation (RFD)	3. SUBTITLE: Configuration Management
4. AUTHORITY (*Data Acquisition Document No.*): DI-CMAN-80640C	5. CONTRACT REFERENCE: SOW 3.4	6. REQUIRING OFFICE: MARCORLOGBASES (851)
7. DD 250 REQ.: LT	9. DIST STATEMENT REQUIRED: A	10. FREQUENCY: AS REQ
8. APP CODE	11. AS OF DATE	12. DATE OF FIRST SUBMISSION: See Blk 16
		13. DATE OF SUBSEQUENT SUBMISSION

17. PRICE GROUP

18. ESTIMATED TOTAL PRICE

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES: Draft	FINAL: Reg	FINAL: Repro
MCLBA (833-3)	0	0	0
MCLBA (851-2)	0	1	0
15. TOTAL	0	1	0

16. REMARKS

Block 4 - Contractor format is authorized and shall be submitted in .doc or .pdf format.

Block 12 - RFDs will be reviewed and disposition determined within 30 calendar days upon receipt by the government.

RFDs shall be transmitted via e-mail to the following address: mbmatcomconfigmngmnt@matcom.usmc.mil

Distribution Statement A: Approved for public release, distribution is unlimited.

G. PREPARED BY:	H. DATE	I. APPROVED BY:	J. DATE
[signature]	OCT 12 2000	[signature]	10/12/00

DD FORM 1423-1, AUG 96 (EG) PREVIOUS EDITION MAY BE USED

Designed using Perform Pro, WHS/D/or, Aug 96